


Q:\5100s\5100 - Chicopee - Uniroval LSP Services\Drawing Files\AutoCAD\2019-10-9 ACOE Filing\2019-10-9 OakStreetPumpStation.dwg Plot Date: 10/9/2019 11:41 AM




GENERAL SEQUENCE OF WORK

1. INSTALL EROSION CONTROLS ALONG DOWNGRADE PERIMETER OF INTAKE STRUCTURES.
2. DEWATER STRUCTURES AS NEEDED AND INSTALL TEMPORARY MEASURES TO PREVENT WATER FROM ENTERING STRUCTURE.
3. REMOVE SLUICE GATE AND SEAL BOTTOM PORTION OF STRUCTURE WITH CONCRETE BULKHEAD TO BLOCK FLOW FROM BOTH SIDES.
4. DISMANTLE AND REMOVE ALL EQUIPMENT FOR OPERATIONS OF SLUICE GATE.
5. DEMOLISH WALKWAY, INTAKE STRUCTURES, AND SOUTH HEADWALL.
6. INTAKE STRUCTURES SHALL BE DECOMMISSIONED THROUGH REMOVAL OF SLUICE GATE AND SEALING OF PIPE TO PUMP STATION WITH CONCRETE BULKHEAD WALL.
7. BACKFILL LOWER PORTION OF INTAKE STRUCTURES WITH CLEAN FILL TO GRADE.
8. PROVIDE RIPRAP OVER FOOTPRINT OF INTAKE STRUCTURE TO MATCH EXISTING SLOPE ALONG SLOPE.

NOTES:

1. INTERIOR OF STRUCTURES IS APPROXIMATE ONLY BASED ON LIMITED VISUAL OBSERVATIONS. ACTUAL LAYOUT MAY VARY.



Former Uniroyal Complex & Facemate Properties

154 Grove Street & 75 West Main Street
Chicopee, MA

Figure No. 8

**Oak Street Pump Station
Intake/Discharge Sections**

Issue Date: 10-9-2019