


NARRAGANSETT BAY COMMISSION

PHASE III COMBINED SEWER OVERFLOW PROGRAM
OF-217 CONSOLIDATION CONDUIT

CONTRACT NO. 308.05C

90% DESIGN
APRIL 2021



STATE OF RHODE ISLAND

DANIEL J. MCKEE _____ GOVERNOR



RHODE ISLAND
INFRASTRUCTURE BANK

MERRILL W. SHERMAN _____ CHAIRMAN

JEFFREY R. DIEHL _____ EXECUTIVE DIRECTOR
AND CEO



VINCENT J. MESOLELLA JR. _____ CHAIRMAN

LAURIE A. HORRIDGE _____ EXECUTIVE DIRECTOR

KATHRYN KELLY, P.E. _____ CSO PROGRAM MANAGER

DAVID C. BOWEN, P.E. _____ ENGINEERING
MANAGER

PROGRAM MANAGEMENT TEAM



DESIGN TEAM



LIST OF DRAWINGS

GENERAL

- G-1 LIST OF DRAWINGS
- G-2 LOCATION AND VACINITY MAP
- G-3 SYMBOLS
- G-4 ABBREVIATIONS

CIVIL

- GC-1 NOTES
- GC-2 SYMBOLS
- GC-3 LEGEND & NOTES
- C-1 STAGING PLAN - TIDEWATER SITE
- C-2 CONSOLIDATION CONDUIT PLAN AND PROFILE I: STA 0+00 - 4+00
- C-3 CONSOLIDATION CONDUIT PLAN AND PROFILE II: STA 4+00 - 8+00
- C-4 CONSOLIDATION CONDUIT PLAN AND PROFILE III: STA 8+00 - 12+00
- C-5 CONSOLIDATION CONDUIT PLAN AND PROFILE IV: STA 12+00 - 16+00
- C-6 CONSOLIDATION CONDUIT PLAN AND PROFILE V: STA 16+00 - 18+88
- C-7 OF-217 OUTFALL PLAN AND PROFILE VI: STA 0+00 - 4+46
- C-8 WATER RELOCATION PLAN
- C-9 CIVIL DETAILS I
- C-10 CIVIL DETAILS II
- C-11 CIVIL DETAILS III
- C-12 CIVIL DETAILS IV
- C-13 CIVIL DETAILS V
- C-14 CIVIL DETAILS VI
- C-15 CIVIL DETAILS VII
- C-16 CIVIL DETAILS VIII
- C-17 CIVIL DETAILS IX

GEOTECHNICAL

- B-1 INSTRUMENTATION PLAN STA. 0+00 - 8+00
- B-2 INSTRUMENTATION PLAN STA. 8+00 - 16+00
- B-3 INSTRUMENTATION PLAN STA. 16+00 - 18+88, STA. 0+00 - 4+46
- B-4 INSTRUMENTATION DETAILS
- B-5 INSTRUMENTATION SCHEDULES
- B-6 MINIMUM DESIGN CRITERIA FOR EXCAVATION SUPPORT
- B-7 GEOTECHNICAL NOTES FOR ANALYSIS AND DESIGN
- B-8 SECANT PILE SHAFT REFERENCE DESIGN

TRAFFIC

- T-1 TRAFFIC MANAGEMENT PLAN
- T-2 TRAFFIC MANAGEMENT PLAN - DETAILS

STRUCTURAL

- S-1 OF-217 RELOCATION STRUCTURE PLAN AND SECTIONS
- S-2 OF-217 DIVERSION STRUCTURE PLAN AND SECTIONS
- S-3 OF-217 REVETMENT PLAN AND SECTION

ELECTRICAL


- GE-1 NOTES & SYMBOLS
- GE-2 ABBREVIATIONS
- E-1 ONE LINE DIAGRAM, CONTROL BLOCK WIRING DIAGRAM, AND PANEL SCHEDULE
- E-2 SITE PLAN, DUCTBANK SECTIONS, AND OF-217 DIVERSION STRUCTURE PLAN
- E-3 DETAILS

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSD Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVW_IIA-4_IIA-5_LIST_OF_DRAWINGS.dwg PLOT DATE: Thursday, April 1, 2021 8:14:09 AM


REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE
NO SCALE



DESIGNED C. CRONIN
DRAWN J. PAYNE
CHECKED J. D'ALELIO

90% DESIGN PHASE - APRIL 2021
NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM
NBC CONTRACT NO 308.05C
GENERAL
OF-217 CONSOLIDATION CONDUIT
LIST OF DRAWINGS




SHEET
G-1
195130227

BY: JAMIE PAYNE

PLOT DATE: Thursday, April 1, 2021 8:15:23 AM

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAWT_IIA-4_IIA-5_LOCATION_MAP.dwg

KEY PLAN



LOCATION MAP

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE
NO SCALE

WARNING
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN J. PAYNE
CHECKED J. D'ALESSIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
GENERAL

OF-217 CONSOLIDATION CONDUIT
LOCATION AND VICINITY MAP

SHEET
G-2
195130227

BY: JAMIE PAYNE

PLOT DATE: Thursday, April 1, 2021 8:16:18 AM

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVWT_IIA-5_GENERAL.dwg




GENERAL SYMBOLOGY	
	NEW CONSTRUCTION
	EXISTING (SCREENED)
	FUTURE (PHANTOM)
	EXISTING TO BE REMOVED OR DEMOLISHED

MATERIAL SYMBOLOGY



	CONCRETE (PLAN AND SECTION)
	GROUT OR SAND (PLAN AND SECTION)
	BRICK (PLAN AND SECTION)
	STEEL/METAL/FRP (SMALL SCALE SECTION)
	GRATING OR SOLID FRP GRATING (SECTION)
	FINISHED GRADE
	GRAVEL/DRAINROCK/AGGREGATE BASE

PIPING ENDS (SINGLE-LINE)	
	PIPE MATERIAL CHANGE
	PUSH-ON JOINT - BELL AND SPIGOT
	PUSH-ON JOINT - RESTRAINED

	SLEEVE TYPE COUPLING
	SLEEVE TYPE COUPLING - RESTRAINED



STANDARD DETAILS ARE LOCATED ON DISCIPLINE GENERAL SHEETS, IN NUMERICAL ORDER



MISCELLANEOUS

	SHEET KEY NOTES
	CENTERLINE
	COORDINATE POINT
	ROUND OR DIAMETER

DISCIPLINE SPECIFIC SYMBOLS ARE SHOWN ON THE DISCIPLINE GENERAL DRAWINGS.
FOR WELDING SYMBOLS USE AMERICAN WELDING SOCIETY STANDARD SYMBOLS.


REV 012216

MISCELLANEOUS	
	WATER LEVEL

CONTROL SYMBOLS	
	BM-XX BENCH MARK
	SITE COORDINATES (SEE TABLE ON DRAWINGS)
	SITE COORDINATES
	MONUMENT
	HORIZONTAL CONTROL POINT
	VERTICAL CONTROL POINT
	HORZ AND VERT CONTROL POINT
	FINISHED ELEVATION
	EXISTING ELEVATION
	DELTA

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	NO SCALE
-------	----------



DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALELIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
GENERAL

OF-217 CONSOLIDATION CONDUIT
SYMBOLS

SHEET
G-3
195130227

CIVIL GENERAL NOTES

GENERAL

- THE CONTRACTOR SHALL TAKE ALL PRECAUTIONARY MEASURES NECESSARY TO PROTECT EXISTING IMPROVEMENTS WHICH ARE TO REMAIN IN PLACE FROM DAMAGE. ALL IMPROVEMENTS DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE EXPEDITIOUSLY REPAIRED OR RECONSTRUCTED AT THE CONTRACTOR'S EXPENSE WITHOUT ADDITIONAL COMPENSATION.
- THE CONTRACTOR SHALL PROPERLY DISPOSE OF ALL DEBRIS FROM DEMOLITION AT CONTRACTOR'S EXPENSE.
- ALL BUILDING COORDINATES ARE TO OUTSIDE CORNER OF COLUMN OR BUILDING.
- THE CONTRACTOR SHALL DISPOSE OF ALL NON-ORGANIC WASTES SUCH AS OLD GUNITE, PIPING, ROCK RUBBLE ETC., AT AN APPROVED LANDFILL OR OTHER SUITABLE DISPOSAL SITE IN ACCORDANCE WITH SPECIFICATION SECTION 02200 and 02075.
- CONTRACTOR SHALL RESTORE ALL SURVEY MONUMENTS THAT ARE DAMAGED OR DESTROYED DURING CONSTRUCTION.

UTILITIES

- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL CONTACT DIGSAFE TO LOCATE EXISTING UTILITIES IN AND AROUND THE AREAS OF NEW CONSTRUCTION. THE CONTRACTOR SHALL POTHOLE FOR EXISTING UTILITIES IN THE LOCATIONS IDENTIFIED ON THE DRAWINGS AND FOR POINTS OF CONNECTION, PRIOR TO SUBMITTAL OF SHOP DRAWINGS.
- THE CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES TO REMAIN IN-PLACE.
- LOCATIONS OF UNDERGROUND UTILITIES SHOWN ON THE DRAWINGS WERE OBTAINED FROM AVAILABLE RECORDS. THE CONTRACTOR SHALL VERIFY ALL LOCATIONS AND ELEVATIONS AND SHALL TAKE ALL PRECAUTIONARY MEASURES NECESSARY TO PROTECT UTILITY LINES WHETHER SHOWN OR NOT SHOWN.
- PRIOR TO ANY CONNECTION TO AN EXISTING UTILITY, THE CONTRACTOR SHALL COORDINATE WITH THE UTILITY OWNER.
- PRIOR TO ANY EXCAVATION IN THE VICINITY OF ANY EXISTING UNDERGROUND FACILITIES, INCLUDING ALL WATER, SEWER, STORM DRAIN, GAS, PETROLIUM PRODUCTS, OR OTHER PIPELINES; ALL BURIED ELECTRIC POWER, COMMUNICATIONS, OR TELEVISION CABLES; ALL TRAFFIC SIGNAL AND STREET LIGHTING FACILITIES; AND ALL RIGHTS-OF-WAY, STATE HIGHWAY, AND RAILROAD RIGHTS-OF-WAY, THE CONTRACTOR SHALL NOTIFY THE RESPECTIVE AUTHORITIES REPRESENTING THE OWNERS OR AGENCIES RESPONSIBLE FOR SUCH FACILITIES NOT LESS THAN 3 DAYS NOR MORE THAN 7 DAYS PRIOR TO EXCAVATION SO THAT A REPRESENTATIVE OF SAID OWNERS OR AGENCIES CAN BE PRESENT DURING SUCH WORK IF THEY SO DESIRE. IN THE CASE OF THE UNDERGROUND UTILITY SERVICE ALERT CENTER, THIS NOTICE WILL GIVE THEM TIME TO MARK THE LOCATION OF THE UTILITIES. THE CONTRACTOR SHALL ALSO NOTIFY THE REGIONAL OR LOCAL UNDERGROUND SERVICE ALERT COMPANY AT LEAST 3 DAYS, BUT NO MORE THAN 7 DAYS, PRIOR TO SUCH EXCAVATION.
- REFER TO B-7 FOR INFORMATION RELATED TO PROTECTION OF STRUCTURES.

PIPING

- THE CONTRACTOR SHALL COMPLY WITH THE RHODE ISLAND DEPARTMENT OF ENVIRONMENTAL MANAGEMENT (RIDEM) POLICY CRITERIA FOR THE SEPARATION OF WATER MAINS AND SANITARY SEWERS.
- THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 36 INCHES OF COVER ON ALL PIPELINES UNLESS OTHERWISE SHOWN OR DIRECTED.
- STRAIGHT SLOPES SHALL BE MAINTAINED BETWEEN INVERT ELEVATIONS SHOWN OR SPECIFIED.
- THE CONTRACTOR SHALL ADJUST ALL VALVE BOXES, PULL BOXES AND MANHOLES TO FINISHED GRADE UNLESS OTHERWISE SHOWN OR SPECIFIED. MANHOLES IN OPEN FIELDS SHALL BE SET ONE FOOT ABOVE GRADE. APPROXIMATE RIM ELEVATIONS ARE SHOWN ON DRAWINGS.
- ALL PIPE TRENCHING AND BACKFILL SHALL BE IN ACCORDANCE WITH DETAIL C-602 FOR RIGID PIPE AND C-601 FOR FLEXIBLE PIPE. PIPE INSTALLED BY MICROTUNNELING SHALL BE IN ACCORDANCE WITH SPECIFICATION 02314 AND 02317. PIPING WITHIN THE TIDEWATER PROPERTY, THROUGH AND INCLUDING MH 217-6 SHALL BE LINED IN ACCORDANCE WITH SPECIFICATION SECTION 09907. THE PIPING SHOWN ON THESE PLANS SPECIFIC TO WATER PIPING SHALL BE RESTRAINED JOINT DESIGN AT ALL SLEEVE TYPE COUPLINGS.

EROSION CONTROL

- THE CONTRACTOR SHALL SUBMIT AN EROSION CONTROL PLAN FOR WORK DURING THE CONSTRUCTION, SIGNED AND STAMPED BY A REGISTERED CIVIL ENGINEER PRIOR TO THE START OF CONSTRUCTION.
 - ALL SLOPES SHALL BE PROTECTED FROM EROSION DURING ROUGH GRADING OPERATIONS AND THEREAFTER, UNTIL INSTALLATION OF FINAL GROUND COVER (SEE LANDSCAPE PLANS FOR FINAL GROUND COVER).
 - ALL SLOPE PROTECTION SWALES SHALL BE CONSTRUCTED AT THE SAME TIME AS BANKS ARE GRADED.
 - THE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTATION AND MAINTENANCE OF EROSION CONTROL MEASURES CONTAINED WITHIN THE CONTRACT SPECIFICATIONS OR AS REQUIRED BY THE CITY, DISTRICT, OR OTHER REGULATORY AUTHORITY. THE CONTRACTOR SHALL ALSO PROVIDE ANY ADDITIONAL EROSION CONTROL MEASURES (E.G. HYDROSEEDING, MULCHING OF STRAW, SAND BAGGING, DIVERSION DITCHES, ETC.) DICTATED BY FIELD CONDITIONS TO PREVENT EROSION OR THE INTRODUCTION OF DIRT, MUD, OR DEBRIS INTO EXISTING PUBLIC STREETS, WATERWAYS, OR ONTO ADJACENT PROPERTIES DURING ANY PHASE OF CONSTRUCTION OPERATIONS.

SURVEY AND CONTROL

SURVEY INFORMATION PROVIDED BY BRYANT AND ASSOCIATES INC. NOV 2019. VERTICAL DATUM IS NGVD29 AND HORIZONTAL DATUM IS RI STATE PLANE COORDINATE SYSTEM.

BENCHMARKS / CONTROL POINTS

POINT #	POINT DESCRIPTION	EASTING	NORTHING	ELEVATION
58	CONTROL POINT	359882.95	289468.51	38.06
59	DH SET	359813.36	289172.39	33.06
60	DH SET	359584.63	288961.99	24.31
61	DH SET	359554.63	288759.67	23.65
62	DH SET	359538.45	288626.49	24.52
63	DH SET	359519.32	288450.47	27.21
64	MN SET	359439.99	288229.12	21.28
65	DH SET	359449.71	287998.10	14.51
66	MN FND	359462.93	287548.38	12.30
67	DH SET	359521.61	287348.34	14.49
68	DH SET	359476.83	287125.65	33.42
69	CONTROL POINT	359483.28	286859.80	39.24
79	DH SET	359493.91	286667.59	37.98
70	SPIKE SET	359605.16	286687.46	35.22
71	SPIKE SET	359633.91	286616.36	34.22
72	SPIKE SET	359809.23	286476.37	22.04
73	SPIKE SET	359987.59	286149.73	25.92
74	SPIKE SET	360221.11	286003.10	12.63
75	MN SET	360294.94	286132.76	9.96
76	MN SET	360476.20	286165.27	10.04

PERMITTING

XXXXXX
XXXX
XXXXX
XXXXX

NATIONAL GRID GAS POLICY REQUIREMENTS

NATIONAL GRID GAS POLICY REQUIREMENTS THAT PERTAIN TO THIS PROJECT

GENERAL

- CONTRACTOR SHALL FOLLOW THE GUIDELINES LISTED IN NATIONAL GRID'S "GUIDELINES FOR WORKING AROUND GAS UTILITIES".
- DEPTH OF GAS FACILITIES ARE UNKNOWN AND COULD BE SHALLOW. USE CAUTION WHEN WORKING IN THE VICINITY OF ANY GAS FACILITY, HAND DIGGING ONLY.
- NATIONAL GRID REQUIRES A MINIMUM OF ONE FOOT OF SEPARATION BETWEEN CROSSING UTILITIES AND EXISTING GAS FACILITIES.
- NATIONAL GRID REQUIRES A MINIMUM OF THREE FEET OF SEPARATION BETWEEN THE GAS MAIN AND THE PARALLEL FACILITY FOR STEEL AND PLASTIC GAS MAINS. **FOR CAST IRON GAS MAIN SEE LINE ITEM FOR ENCROACHMENT GUIDELINES.**
- AT A PROPOSED UTILITY AND CRITICAL GAS MAIN CROSSING, A NATIONAL GRID GAS DAMAGE PREVENTION INSPECTOR MUST BE ON SITE WHEN CROSSING. CALL JON MACLEAN AT 781-296-2046 OR ED SOUZA AT 401-283-9159.
- IF A **GAS MAIN IS EXPOSED OR GOING TO BE EXPOSED** CALL NATIONAL DISPATCH OFFICE AT 877-304-1203 FOR AN INSPECTOR TO BE DISPATCHED TO THE SITE TO INSPECT THE LINE BEFORE BACKFILL.
- IF A **GAS MAIN OR GAS MAIN COVER IS DAMAGED** CALL NATIONAL DISPATCH OFFICE AT 877-304-1203 FOR AN INSPECTOR TO BE DISPATCHED TO THE SITE FOR REPAIR BEFORE BACKFILL.
- FOR ANY EXPOSED GAS FACILITY, PROVIDE BACKFILL MATERIALS AND COMPACT THE BACKFILL MATERIALS IN ACCORDANCE WITH NATIONAL GRID'S "GUIDELINES FOR BACKFILL AND COMPACTION AROUND GAS PIPES".
- WHEN CROSSING OR EXPOSING A STEEL OR PLASTIC GAS FACILITY SUPPORT MAY BE REQUIRED. FOLLOW THE GUIDELINES LISTED AND ILLUSTRATED IN NATIONAL GRID'S "SUPPORT REQUIREMENTS FOR EXPOSED & UNDERMINED STEEL OR PLASTIC GAS FACILITIES", DOCUMENT (DWG NO. CNST-6045).
- ALL GAS VALVE BOXES SHALL BE ADJUSTED TO THE NEW ROAD/SIDEWALK SURFACE. VALVE BOXES, IF REQUIRED FOR REPLACEMENT, CAN BE OBTAINED AT NATIONAL GRID'S PROVIDENCE LOCATION, 477 DEXTER STREET, PROVIDENCE, RI OR LINCOLN LOCATION, 642 GEORGE WASHINGTON HIGHWAY (QUANTITIES 5 OR LESS). GAS VALVE BOXES NEED TO BE ACCESSIBLE AT ALL TIMES TO BE OPERATED BY NATIONAL GRID IN THE EVENT OF AN EMERGENCY.
- ALL CATHODIC PROTECTION BOXES (BOXES THAT CONTAIN WIRES THAT GO DOWN TO THE GAS MAIN) SHALL BE ADJUSTED TO THE NEW ROAD/SIDEWALK SURFACE. CARE SHALL BE EXERCISED WHEN ADJUSTING SO AS NOT TO DAMAGE THE WIRES. IF THE WIRES ARE DAMAGED OR IF ASSISTANCE IS NEEDED, CONTACT NATIONAL GRID CORROSION ENGINEER TO VISIT THE SITE. CONTACT RICK LEPAGE 508-948-8432 OR MIKE HARMON 781-953-2545. NEW BOXES, IF REQUIRED, CAN BE OBTAINED AT NATIONAL GRID'S PROVIDENCE FACILITY, 477 DEXTER ST, PROVIDENCE, RI OR NATIONAL GRID'S LINCOLN FACILITY, 642 GEORGE WASHINGTON HIGHWAY, LINCOLN, RI (QUANTITIES 5 OR LESS). CONTRACTOR SHALL FOLLOW THE GUIDELINES LISTED IN NATIONAL GRID'S "GUIDELINES FOR WORKING AROUND CORROSION CONTROL SYSTEM COMPONENTS", DOCUMENT ATTACHED.
- DUE TO SYSTEM RELIABILITY AND PUBLIC SAFETY CONCERNS, IT IS NATIONAL GRID'S PRACTICE TO RESTRICT ALL CONSTRUCTION WORK ON OR NEAR GAS FACILITIES BETWEEN NOVEMBER 15TH AND APRIL 15TH. ALL SCHEDULED WORK SHOULD BE COMPLETED BETWEEN APRIL 15TH AND NOVEMBER 15TH AS GAS USAGE PEAK DURING THE MONTHS OF DECEMBER TO MARCH DRIVEN BY HEATING NEEDS. NATIONAL GRID'S PRIORITY IS TO PROVIDE OUR CUSTOMERS WITH SAFE AND RELIABLE GAS SERVICE. ANY WORK ON OR NEAR THE GAS FACILITY WILL EXPOSE OUR CUSTOMERS TO UNNECESSARY RISK. EXCEPTIONS WILL BE CONSIDERED ON A CASE BY CASE BASIS. APPROVALS FROM GAS CONTROL, OPERATIONAL ENGINEERING, AND PROJECT ENGINEERING WILL BE REQUIRED FOR THESE CASES.
- FOR A GAS LEAK CALL 800-640-1595
- FOR A DAMAGED GAS FACILITY CALL 800-870-1664.

CAST IRON INVOLVEMENT

- IF EXCAVATING PARALLEL TO OR CROSSING A CAST IRON GAS FACILITY THEN ENCROACHMENT OF THE CAST IRON LINE IS A POSSIBILITY AND A CONCERN WHERE REPLACEMENT MAY BE REQUIRED. WHENEVER AN EXCAVATION IS IN THE VICINITY OF A CAST IRON GAS MAIN CONTACT NATIONAL GRID ENCROACHMENT ENGINEER TO BE ON SITE, CALL CHRIS FERRANTI AT 401-465-9064. GUIDELINES IN AVOIDING AN ENCROACHMENT ARE LISTED IN NATIONAL GRID'S "CAST IRON GAS MAIN ENCROACHMENT PREVENTION".
- IF EXCAVATING PARALLEL TO OR CROSSING A CAST IRON FACILITY THAT IS GREATER THAN 8", THIS LINE IS NOT COVERED UNDER THE ENCROACHMENT GUIDELINES AND LAW. NATIONAL GRID DOES NOT ALLOW MORE THAN 10' OF GAS MAIN TO BE EXPOSED AND ONLY ALLOWS (1) BELL & SPIGOT JOINT TO BE EXPOSED. IF A BELL & SPIGOT JOINT IS EXPOSED SAID JOINT MUST BE LEAK CLAMPED BEFORE BACKFILL UNLESS A CLAMP IS ALREADY IN PLACE. PROVIDE BACKFILL MATERIALS AND COMPACT THE BACKFILL MATERIALS IN ACCORDANCE WITH NATIONAL GRID'S "GUIDELINES FOR BACKFILL AND COMPACTION AROUND GAS PIPES". MINIMUM 95% COMPACTION OF THE SOIL BELOW A CAST IRON IS ALWAYS REQUIRED. ALWAYS CALL NATIONAL GRID DAMAGE PREVENTION DEPARTMENT FOR AN INSPECTOR TO BE DISPATCHED TO SITE. CALL JONATHAN MACLEAN AT 781-296-2046 OR ED SOUZA AT 401-283-9159.

REGULATOR STATION

- NATIONAL GRID REQUIRES NOTIFICATION OF CONSTRUCTION WORK WITHIN 200 FT OF A GAS REGULATOR STATION FOR SAFETY MONITORING DURING CONSTRUCTION. PLEASE CALL NATIONAL GRID I&R SUPERVISOR MIKE ROMANO AT 617-910-7854 OR GEORGE MAERKLE AT 401-595-8276 WHEN DIGGING WITHIN 200 FT OF REGULATOR STATION.

ABANDONED GAS MAIN

- NATIONAL GRID WILL PURGE OUR OLD GAS MAIN OF GAS. WIPE TEST SAMPLE THE INSIDE OF THE PIPE, CAP THE ENDS AND ABANDON IN PLACE. PIPE FOUR INCHES AND LESS IN DIAMETER CAN'T BE SAMPLED; THIS PIPE WILL BE ASSUMED TO BE CONTAMINATED. IF THE WIPE TEST RESULTS SHOW PCB CONTAMINATION AND A SECTION OR SECTIONS NEED TO BE REMOVED BY THE CONTRACTOR THEN THERE ARE TWO POSSIBILITIES: IF THE QUANTITY TO BE REMOVED IS SMALL THE CONTRACTOR COULD TRANSPORT THE REMOVED SECTIONS WITH SEALED ENDS TO EITHER OUR ALLENS AVE FACILITY AT 642 ALLENS AVE IN PROVIDENCE OR OUR DEXTER ST FACILITY AT 477 DEXTER ST IN PROVIDENCE AND PLACE THEM IN OUR RED OPEN TOP "PIPE TO BE CLEANED" CONTAINER ON SITE. NATIONAL GRID WOULD THEN HANDLE THE CLEANING AND PROPER DISPOSAL. OR THE CONTRACTOR COULD HIRE CLEAN HARBORS TO DELIVER AN OPEN TOP CONTAINER TO THE SITE, PLACE THE REMOVED SECTION INTO THE DUMPSTER AND THEN ARRANGE TO HAVE CLEAN HARBORS PICK UP THE CONTAINER. THE CHARGES ASSOCIATED WITH DELIVERY, ONSITE RENTAL AND PICK UP OF THE DUMPSTER WOULD BE THE CONTRACTOR'S RESPONSIBILITY AND NATIONAL GRID'S RESPONSIBILITY WILL BE FOR THE CLEANING AND PROPER DISPOSAL. NATIONAL GRID ALSO REQUIRES THAT THE OPEN PIPE ENDS OF THE ABANDONED PIPE REMAINING IN THE GROUND BE CAPPED OR SEALED WITH EXPANDING FOAM.

TIDEWATER SITE ACCESS

TIDEWATER SITE ACCESS

- THE TIDEWATER SITE HAS SOIL AND GROUNDWATER CONTAMINATION. CONTRACTOR SHALL WORK IN STRICT ACCORDANCE WITH THEIR HEALTH AND SAFETY PLAN AND THE REQUIREMENTS OF NATIONAL GRID.
- MULTIPLE CONTRACTORS WILL BE WORKING ON THE SITE CONCURRENTLY AND SOME OF THE WORK SPACE IS SHARED. THE CONTRACTOR SHALL BE REQUIRED TO ATTEND COORDINATION MEETINGS FOR THE MULTIPLE CONTRACTS. PROJECTS INCLUDE: NATIONAL GRID - SITEWIDE REMEDY DESIGN WHICH INCLUDES INSTALLATION OF A MEMBRANE CAP OVER THE SITE. FORTUITOUS PARTNERS: CONSTRUCTION OF A NEW SOCCER STADIUM AND AMENITIES.
- CONTRACTOR SHALL MAINTAIN ACCESS TO NATURAL GAS AND ELECTRICAL SUBSTATION INFRASTRUCTURE BY NATIONAL GRID EMPLOYEES AT ALL TIMES DURING THE PERFORMANCE OF THE WORK. NO SEPARATE PAYMENT WILL BE MADE TO THE CONTRACTOR FOR PROVIDING THIS ACCESS OR FOR DELAYS CAUSED BY ON-GOING SITE OPERATIONS.
- CONTRACTOR SHALL MAINTAIN ACCESS TO THE PAVED AREA ON THE NORTHWEST SIDE OF THE SUBSTATION AT ALL TIMES TO ALLOW MOBILIZATION AND STAGING OF A TRAILER MOUNTED MOBILE SUBSTATION. NO SEPARATE PAYMENT WILL BE MADE TO THE CONTRACTOR FOR PROVIDING THIS ACCESS OR FOR DELAYS CAUSED BY THE PRESENCE OF THE MOBILE SUBSTATION.
- CONTRACTOR SHALL COORDINATE WITH NATIONAL GRID ELECTRIC TO TEMPORARILY RELOCATE DISTRIBUTION AND TRANSMISSION POLES WHEN EXCAVATIONS ARE PERFORMED ADJACENT TO THIS ELECTRICAL INFRASTRUCTURE.
- CONTRACTOR SHALL PERFORM ALL WORK IN A MANNER TO NOT EXCEED THE GROUND VIBRATION LIMITS OUTLINED IN NATIONAL GRID REQUIREMENTS FOR WORK IN VICINITY OF GAS MAINS.
- CONTRACTOR SHALL PROVIDE SIGNAGE, BARRICADES, AND/OR TEMPORARY PROTECTIVE STRUCTURES TO PROTECT EXISTING MONITORING WELLS FROM DAMAGE. CONTRACTOR SHALL IMMEDIATELY NOTIFY ENGINEER IN THE EVENT ANY MONITORING WELL TO REMAIN IS DAMAGED. MONITORING WELLS DAMAGED BY CONTRACTOR SHALL BE REPLACED AT NO COST TO OWNER.

SELECTIVE DEMOLITION & CONSTRUCTION

- DUST SHALL BE STRICTLY CONTROLLED IN ALL AREAS REQUIRING DEMOLITION. CONTRACTOR SHALL PROVIDE AND EMPLOY DUST CONTROL MEASURES TO MITIGATE THE RELEASE OF VISIBLE AIRBORNE PARTICULATE MATTER AND/OR FUGITIVE DUST BEYOND THE LIMITS OF WORK. DUST CONTROL MEASURES SHALL BE IMPLEMENTED CONSISTENT WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- NOISE SHALL BE STRICTLY CONTROLLED IN ALL AREAS. NOISE CONTROL AND MONITORING SHALL BE PERFORMED IN ACCORDANCE WITH CONTRACT DOCUMENTS.
- VIBRATION SHALL BE STRICTLY CONTROLLED IN ALL AREAS. VIBRATION CONTROL AND MONITORING SHALL BE PERFORMED IN ACCORDANCE WITH CONTRACT DOCUMENTS.
- CONTRACTOR SHALL AT ALL TIMES BE SOLELY RESPONSIBLE FOR EXERCISING REASONABLE PRECAUTION TO PROTECT THE HEALTH, SAFETY, AND WELFARE, OF ALL ON-SITE PERSONNEL, THE PUBLIC AND THE ENVIRONMENT DURING PERFORMANCE OF THE WORK DESCRIBED HEREIN AND SHOWN ON THE DRAWINGS. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE PROVISIONS OF FEDERAL, STATE AND LOCAL HEALTH AND SAFETY AND OCCUPATIONAL HEALTH AND SAFETY STATUTES AND CODES.
- CONTRACTOR SHALL ALSO COMPLY WITH CONDITIONS CONTAINED IN SITE-SPECIFIC PERMITS OR LICENSES OBTAINED BY OWNER.
- CONTRACTOR SHALL FOLLOW ALL GUIDELINES AND PROCEDURES LISTED IN THE NATIONAL GRID CONTRACTOR SAFETY REQUIREMENTS DOCUMENTS INCLUDED IN THE CONTRACT DOCUMENTS.
- CONTRACTOR SHALL ESTABLISH AND MAINTAIN SUPPORT, CONTAMINATION REDUCTION AND EXCLUSION ZONES AT THE SITE IN ACCORDANCE WITH OSHA 29 CODE OF FEDERAL REGULATIONS (CFR) 1910.120.
- CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH THE SITE-SPECIFIC AIR MONITORING REQUIREMENTS. THE AIR MONITORING REQUIREMENTS INCLUDE, BUT ARE NOT LIMITED TO, MONITORING FREQUENCY, ACTION LEVELS, MONITORING EQUIPMENT, MONITORING LOCATIONS AND SPECIFIC RESPONSE ACTIONS TO BE TAKEN IN THE EVENT THAT ANY ACTION LEVELS ARE TRIGGERED.
- CONTRACTOR SHALL BE REQUIRED TO CONDUCT THE WORK IN A MANNER THAT PREVENTS VAPOR EMISSIONS AND FUGITIVE DUST THAT MAY IMPACT PUBLIC HEALTH OR RESULT IN NUISANCE CONDITIONS. CONTRACTOR SHALL CONTROL VAPOR EMISSIONS AND DUST SO THAT PERMETER ACTION LEVELS ARE NOT EXCEEDED.
- WORKERS WORKING WITHIN 25-FEET OF THE COASTAL FEATURE INCLUDING, BUT NOT LIMITED TO THE EDGE OF THE CONTAINMENT WALL AND STEEL PILE BULKHEAD SYSTEMS SHALL BE REQUIRED TO WEAR PERSONAL FLOTATION DEVICES (PFDs).

STOP WORK AUTHORITY

- SHOULD ANY UNFORESEEN SAFETY-RELATED FACTOR, HAZARD, OR CONDITION WHICH POSES A POTENTIAL THREAT OF PHYSICAL INJURY OR HARM TO SITE PERSONNEL OR THE ENVIRONMENT BECOME EVIDENT DURING THE PERFORMANCE OF THE WORK, ALL SITE PERSONNEL SHALL HAVE AUTHORITY AS GRANTED BY OSHA REGULATIONS TO ISSUE A STOP WORK DIRECTIVE.
- IF A STOP WORK DIRECTIVE IS ISSUED, CONTRACTOR MUST IMMEDIATELY TAKE PRUDENT CORRECTIVE ACTION TO SECURE THE WORK AND PROVIDE SAFE CONDITIONS FOR SITE PERSONNEL AND THE ENVIRONMENT. THIS CORRECTIVE ACTION SHALL BE FOLLOWED BY AN IMMEDIATE ORAL (AND FOLLOWED UP WITH WRITTEN) INCIDENT REPORT TO PROGRAM MANAGER AND THE PROPERTY OWNER (NATIONAL GRID). THE INCIDENT REPORT SHALL BE PROVIDED AS SOON AS POSSIBLE BUT, AT A MINIMUM, BY 10 A.M. THE NEXT DAY. CONTRACTOR SHALL CONDUCT AN INVESTIGATION AND PROVIDE A WRITTEN REPORT INCORPORATING RESULTS OF THE INVESTIGATION IF DIRECTED TO DO SO BY THE PROGRAM MANAGER OR THE PROPERTY OWNER.
- CONTRACTOR SHALL NOT CHARGE STANDBY TIME DURING STOP WORK DIRECTIVES INITIATED BY OWNER OR ENGINEER. IN ACCORDANCE WITH PUBLISHED NATIONAL GRID SAFETY REQUIREMENTS, IN RESPONSE TO CONTRACTOR'S NEAR MISS, UNSAFE ACTION OR REPORTABLE SAFETY INCIDENT, SHOULD CONTRACTOR REFUSE TO OBEY A STOP WORK DIRECTIVE, CONTRACTOR SHALL IMMEDIATELY BE EXCUSED FROM THE SITE. RETURN COMPLETE AND ACCURATE HEALTH AND SAFETY RECORDS FOR ALL CONTRACTOR AND SUBCONTRACTOR EMPLOYEES ASSIGNED TO THE SITE AT ALL TIMES.
- SAFETY REPRESENTATIVE SHALL MEET AT LEAST MONTHLY WITH THE CONTRACTOR AND PMCM.

EMPLOYEE TRAINING

- PRIOR TO THE INITIATION OF THE WORK, CONTRACTOR AND ALL SUBCONTRACTORS SHALL CERTIFY THAT ALL PERSONNEL ASSIGNED TO PERFORM OR SUPERVISE WORK AT THE SITE HAVE RECEIVED, AND THAT NEW HIRES WILL RECEIVE, PRIOR TO BEING ALLOWED ON THE SITE, APPROPRIATE TRAINING IN COMPLIANCE WITH OSHA 29 CFR 1926.65/1910.120. THE TRAINING FOR PERSONNEL WORKING IN THE VICINITY OF ENVIRONMENTALLY IMPACTED SITE MATERIAL SHALL CONSIST OF A MINIMUM OF FORTY (40) HOURS OF HEALTH AND SAFETY TRAINING, IF THE JOB IS "HOT JOB" TRAINING, AND EIGHT (8) HOURS OF REFRESHER TRAINING ANNUALLY THEREAFTER. TRAINING REQUIREMENTS FOR PERSONNEL OR SUBCONTRACTORS NOT EXPECTED TO ENCOUNTER IMPACTED MATERIALS SHALL BE SPECIFICALLY DESCRIBED IN THE SITE-SPECIFIC HASP. IN ADDITION, THE DESIGNATED SUPERVISORY PERSONNEL SHALL HAVE A MINIMUM OF EIGHT (8) HOURS ADDITIONAL SPECIALIZED TRAINING FOR MANAGING HAZARDOUS WASTE OPERATIONS IN COMPLIANCE WITH OSHA 29 CFR 1926.65/1910.120E.
- ANNUAL MEDICAL MONITORING IN COMPLIANCE WITH OSHA 29 CFR 1926.65

GAS MAIN ENCROACHMENT COORDINATION

- FOR INTRUSIVE OR EARTH DISTURBING WORK 15 FEET OR CLOSER TO STEEL GAS FACILITIES, NATIONAL GRID REQUIRES LEAK SURVEYS BEFORE AND AFTER CONSTRUCTION ACTIVITIES WHICH CREATE VIBRATION ON A DAILY BASIS.
- FOR INTRUSIVE OR EARTH DISTURBING WORK 12 FEET OR CLOSER TO STEEL GAS FACILITIES, NATIONAL GRID REQUIRES DAILY LEAK SURVEYS AS WELL AS VIBRATION MONITORING USING SEISMOGRAPHS. VIBRATION LEVELS SHALL NOT EXCEED 5.0 IN/SEC AS MONITORED BY NATIONAL GRID'S DAMAGE PREVENTION INSPECTORS. WORK CLOSER THAN 10 FEET FROM THE LINE WILL REQUIRE RELAY OF THE LINE.
- FOR INTRUSIVE OR EARTH DISTURBING WORK 25 FEET OR CLOSER TO CAST IRON FACILITIES, NATIONAL GRID REQUIRES DAILY LEAK SURVEYS BEFORE AND AFTER VIBRATION ACTIVITIES, AS WELL AS VIBRATION MONITORING USING SEISMOGRAPHS. VIBRATION LEVELS SHALL NOT EXCEED 5.0 IN/SEC AS MONITORED BY NATIONAL GRID'S DAMAGE PREVENTION INSPECTORS. WORK CLOSER THAN 10 FEET FROM THE LINE WILL REQUIRE RELAY OF THE LINE.

TIDEWATER - SOIL MANAGEMENT

- CONTRACTOR IS DIRECTED TO SPECIFICATION SECTION 02076 - SOIL MANAGEMENT TIDEWATER, FOR INFORMATION RELATIVE TO THE TIDEWATER SITE AND
 - MANAGEMENT AND DISPOSAL OF SOIL
 - EQUIPMENT AND VEHICLE DECONTAMINATION
 - DUST CONTROL

TIDEWATER - HEALTH AND SAFETY REQUIREMENTS

- CONTRACTOR IS DIRECTED TO SPECIFICATION SECTION 01065 - PROJECT SAFETY AND HEALTH, FOR INFORMATION RELATIVE TO THE TIDEWATER SITE.
- TIDEWATER HEALTH AND SAFETY REQUIREMENTS ARE ALSO INCLUDED IN APPENDIX C - NATIONAL GRID HEALTH & SAFETY REQUIREMENTS.

SCALE				WARNING		DESIGNED C. CRONIN		90% DESIGN PHASE - APRIL 2021						NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM		NBC CONTRACT NO 308.05C CIVIL		SHEET	
NO SCALE				IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE		DRAWN J. PAYNE		NOT FOR CONSTRUCTION This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.						OF-217 CONSOLIDATION CONDUIT NOTES		GC-1		195130227	
1	5/13/20	JP	STANTEC COMMENTS																
REV	DATE	BY	DESCRIPTION																

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAWT_III-A-5_GENERAL.dwg
 PLOT DATE: Thursday, April 1, 2021 8:16:19 AM
 BY: JAMIE PAYNE

BY: JAMIE PAYNE

PLOT DATE: Thursday, April 1, 2021 8:16:20 AM

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVVT_IIA-5_GENERAL.dwg

GENERAL CIVIL SYMBOLS

	NEW
	EXISTING
	FUTURE
	EXISTING TO BE REMOVED OR DEMOLISHED
	CENTERLINE
	EARTH (IN SECTION)
	COMPACTED EARTH (IN SECTION)
	SLOPE ON PAVED SURFACE
	BERM SLOPE (HORZ TO VERT)

TOPOGRAPHY AND MAPPING SYMBOLS

	MAJOR CONTOURS
	MINOR CONTOURS
	TOP OF SLOPE
	TOE OF SLOPE
	PROPERTY LINE
	RIGHT-OF-WAY LINE
	EASEMENT LINE
	TEMPORARY EASEMENT LINE
	TRAIL OR DIRT ROAD
	FLOW LINE
	FLOOD HAZARD AREA
	EDGE OF WETLANDS
	GUARDRAIL (PERMANENT)
	GUARDRAIL (REMOVABLE)
	VEGETATION
	WELL

GEOTECHNICAL SYMBOLS

	SOIL BORING LOCATION
	TEST PIT LOCATION
	OBSERVATION HOLE
	MONITORING WELL

PIPING AND UTILITIES

UTILITIES (SINGLE LINE) SEE PIPE SCHEDULE FOR ADDITIONAL PIPING INFO

	UTILITIES (SIZE WHERE NOTED)
	UNDERGROUND
G	NATURAL GAS LINE
W	WATER
PW	POTABLE WATER
FIRE	FIRE SUPPLY WATER LINE
SDR	STORM DRAIN
SS	SANITARY SEWER
TEL	TELEPHONE
COMM	COMMUNICATIONS LINE
FOC	FIBER OPTIC CABLE
CATV	CABLE TV
E	POWER
UNID	UNIDENTIFIED
ABND	ABANDONED UTILITY

	POWER POLE
	BURIED ACCESS MANOLE (IN PLAN) LOCATE ON SIDE SHOWN
	BURIED ACCESS MANHOLE (IN PROFILE)
	BLOWOFF (IN PROFILE) LOCATE ON SIDE SHOWN
	BLOWOFF (IN PLAN)
	BLOWOFF (IN PROFILE)
	FIRE HYDRANT (IN PLAN)
	FIRE HYDRANT (IN PROFILE)
	MANHOLE (IN PLAN)
	MANHOLE (IN PROFILE)
	CLEANOUT TO GRADE OR PRESSURE CLEANOUT TO GRADE (IN PLAN)
	CLEANOUT TO GRADE OR PRESSURE CLEANOUT TO GRADE (IN PROFILE)
	GATE VALVE
	BUTTERFLY VALVE
	ECCENTRIC PLUG VALVE
	LUBRICATED PLUG VALVE

DRAINAGE SYMBOLS

	RIPRAP
	HAY BALE
	SILT FENCE
	COMPOST FILTER SOCK

ROAD AND PAVING SYMBOLS

	ASPHALT CEMENT PAVING
	CONCRETE PAVING (HEAVY DUTY)
	GRAVEL PAVING
	CONCRETE PAVING (LIGHT DUTY) SIDEWALKS ETC...
	CONCRETE CURB
	CONCRETE CURB AND GUTTER
	DROP INLET CATCH BASIN
	CURBSIDE DROP INLET CATCH BASIN WITH LOCAL DEPRESSION
	SIDE INLET CATCH BASIN WITH LOCAL DEPRESSION
	CONCRETE WALK
	DRIVEWAY/ACCESS RAMP

CONTROL SYMBOLS

	BENCH MARK
	SITE COORDINATES (SEE TABLE ON DRAWINGS)
	SITE COORDINATES
	MONUMENT
	HORIZONTAL CONTROL POINT
	VERTICAL CONTROL POINT
	HORZ AND VERT CONTROL POINT
	FINISHED ELEVATION
	EXISTING ELEVATION
	DELTA

STRUCTURES

	SITE OR RETAINING WALL
	FENCE (CHAINLINK)
	FENCE (WOOD)
	STRUCTURE
	STRUCTURE (BELOW GRADE)
	CATCH BASIN

	GAS VALVE
	WATER VALVE
	UNKNOWN VALVE
	HYDRANT
	UTILITY POLE
	UTILITY POLE WITH LIGHT
	GUY WIRE
	CATCH BASIN
	DRAIN MANHOLE
	SANITARY MANHOLE
	TELEPHONE MANHOLE
	SIGNAL HAND HOLE
	ELECTRIC HAND HOLE
	SIGN
	ELECTRIC RISER
	EXISTING CONTOUR
	DECIDUOUS TREE
	CONIFEROUS TREE
	DECIDUOUS SHRUB
	DECIDUOUS SHRUB
	CONIFEROUS SHRUB
	BORING
	LIGHT
	LIGHT POLE
	LANDSCAPED AREA
	CURB RAMP & DETECTABLE WARNING SYSTEM
	TRAFFIC LOOP DETECTOR
	IRRIGATION HANDHOLE
	TEST PIT
	OBSERVATION WELL

REV 050215

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE
NO SCALE

WARNING
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN J. PAYNE
CHECKED J. D'ALESSIO

90% DESIGN PHASE - APRIL 2021
NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT SYMBOLS

SHEET
GC-2
195130227


BY: JAIMIE PAYNE

PLOT DATE: Thursday, April 1, 2021 8:16:21 AM

DWG FILE: J:\6412 NBC CSD Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVW_IIA-5_GENERAL.dwg

UNIFIED SOIL CLASSIFICATION SYSTEM (Based on ASTM D2488 & D2487)						
MAJOR DIVISIONS		GROUP/GRAPHIC SYMBOL	TYPICAL DESCRIPTION			
COARSE-GRAINED SOILS (50% or more retained on No. 200 sieve)	GRAVELS (more than 50% retained on No. 4 sieve)	CLEAN GRAVELS (less than 5% fines)	GW		WELL-GRADED GRAVEL	
			GP		POORLY GRADED GRAVEL	
		GRAVELS (with 5 to 12% fines)	GW-GM		WELL-GRADED GRAVEL WITH SILT	
			GW-GC		WELL-GRADED GRAVEL WITH CLAY	
			GP-GM		POORLY GRADED GRAVEL WITH SILT	
			GP-GC		POORLY GRADED GRAVEL WITH CLAY	
	GRAVELS WITH FINES (more than 12% fines)	GM		SILTY GRAVEL		
		GC		CLAYEY GRAVEL		
		GC-GM		SILTY CLAYEY GRAVEL		
		CLEAN SANDS (less than 5% fines)	SW		WELL-GRADED SAND	
			SP		POORLY GRADED SAND	
			SANDS (less than 50% retained on No. 4 sieve)	SW-SM		WELL-GRADED SAND WITH SILT
	SW-SC			WELL-GRADED SAND WITH CLAY		
	SP-SM			POORLY GRADED SAND WITH SILT		
	SP-SC			POORLY GRADED SAND WITH CLAY		
	SANDS WITH FINES (more than 12% fines)	SM			SILTY SAND	
		SC			CLAYEY SAND	
		SC-SM		CLAYEY SAND WITH SILT		
FINE-GRAINED SOILS (50% or more passes No. 200 sieve)	SILTS & CLAYS (liquid limit less than 50)	INORGANIC	ML		SILT	
			CL		LEAN CLAY	
			CL-ML		CLAY WITH SILT	
	SILTS & CLAYS (liquid limit greater than 50)	ORGANIC	OL		LOW PLASTICTIY ORGANIC CLAY	
			INORGANIC	MH		ELASTIC SILT
				CH		FAT CLAY
OH		HIGH PLASTICTIY ORGANIC CLAY				
HIGHLY ORGANIC SOILS	PRIMARILY ORGANIC MATTER	PT		PEAT		

BORING LEGEND:



NOTES:

1. ALL ELEVATIONS ARE IN FEET AND REFER TO THE NATIONAL GEODETIC VERTICAL DATUM OF 1929 (NVDG29).
2. POSITIVE OFFSET = RIGHT OF CENTERLINE, LOOKING UP STATION.
3. NEGATIVE OFFSET = LEFT OF CENTERLINE, LOOKING UP STATION.
4. THE SOIL STRATIGRAPHY SHOWN IS GENERALIZED INTERPRETATION BASED ON THE SAMPLES COLLECTED WITHIN EACH BORING. NO ATTEMPT WAS MADE TO INTERPOLATE SOIL STRATIGRAPHY BETWEEN BORINGS AS THE DISTRIBUTION OF MATERIALS IS VARIABLE AND NON-UNIFORM IN BOTH VERTICAL AND HORIZONTAL DIRECTIONS.

BEDROCK LEGEND:

GRAPHIC SYMBOL	DESCRIPTION
	SILTSTONE
	SANDSTONE
	CONGLOMERATE

REV	DATE	BY	DESCRIPTION

SCALE	WARNING	DESIGNED C. CRONIN
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DRAWN J. PAYNE
		CHECKED

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec PARE

NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
LEGEND AND NOTES

SHEET
GC-3
195130227



DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_SITE_STAGING_111A-5a.dwg
 PLOT DATE: Thursday, April 1, 2021 8:16:33 AM
 BY: JAMIE PAYNE

PROPOSED GRADING: FROM PLAN ENTITLED TIDEWATER LANDING,
 TIDEWATER SITE - CROSS SECTION, MILONE & MACBROOM, JUNE 2020
 PROPERTY LINE SOURCE: CITY OF PAWTUCKET GIS

REV	DATE	BY	DESCRIPTION
1	10/21/2020	JP	ALIGNMENT UPDATE TO ACCOMMODATE STADIUM

SCALE
 1" = 40'
 WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
 DRAWN R. GREENWAY
 CHECKED C. CRONIN

90% DESIGN PHASE - APRIL 2021
 NOT FOR CONSTRUCTION
 This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.

www.BETA-Inc.com


NARRAGANSETT BAY COMMISSION
 PHASE III COMBINED SEWER OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
 CIVIL
 OF-217 CONSOLIDATION CONDUIT STAGING PLAN - TIDEWATER SITE


SHEET
 C-1
 195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawings\Files\Civil\SheetSet\PAWT_Site_Plan_Plan_Profile_III-A-5_ALT3.dwg PLOT DATE: Monday, April 5, 2021 2:26:27 PM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN



PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- VERTICAL DATUM FOR PROJECT IS NGVD29.

SHEET KEYNOTES

- A. MICROTUNNEL: STATION 1+26 TO STATION 4+00
- B. EXCAVATION FOR MH 217-5 TO BE CONSTRUCTED AS RECEIVING PIT FOR MICROTUNNEL OPERATION. SOLDIER PILE AND LAGGING SOE SYSTEM SHOWN IS CONCEPTUAL. CONTRACTOR IS RESPONSIBLE FOR SELECTING SOE SYSTEM TYPE AND DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
- C. COORDINATE WITH NATIONAL GRID FOR TEMPORARY POWER SHUT OFF FOR OVERHEAD WIRES AND SUPPORT POLES AS REQUIRED TO FACILITATE INSTALLATION OF RECEIVING SHAFT, EQUIPMENT, AND STRUCTURES. PROVIDE TEMPORARY STREET LIGHTING FOR DURATION OF POWER INTERRUPTION AND FOR FULL LENGTH OF STREET WHERE LIGHTING HAS BEEN IMPACTED.
- D. PROVIDE SEALED AND BOLTED MANHOLE COVERS
- E. TYPICAL CATCH BASIN EROSION CONTROL
- F. SEE "GAS MAIN ENCORACHMENT COORDINATION" NOTES ON SHEET GC-1.
- G. PROVIDE PENETRATION IN NORTH FACE OF MANHOLE TO RECEIVE 48" RCP PIPE TO BE INSTALLED BY OTHERS. CONSTRUCT TEMPORARY BRICK BULKHEAD IN PENETRATION. INVERT TO BE CONSTRUCTED BY OTHERS.
- H. MODIFY EXISTING CATCH BASIN TO ACCEPT NEW DISCHARGE PIPE AND ABANDON EXISTING DISCHARGE PIPE
- I. PLUG & ABANDON EXISTING DRAIN PIPE.

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALESIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE I: STA 0+00 - 4+00


SHEET
C-2
195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAWT_SITE_PLAN_&_PROFILE_ILA-5_ALT3.dwg | DATE: Monday, April 5, 2021 2:27:08 PM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN



PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY THE CITY OF PAWTUCKET
- VERTICAL DATUM FOR PROJECT IS NGVD29.

SHEET KEYNOTES

- MICROTUNNEL: STATION 4+00 TO STATION 8+00
- EXCAVATION FOR MH 217-6 TO BE CONSTRUCTED AS WORKING SHAFT AND RECEIVING PIT FOR MICROTUNNEL OPERATION. SUPPORT OF EXCAVATION LIMITS BASED ON SECANT PILE CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
- COORDINATE WITH NATIONAL GRID FOR TEMPORARY POWER SHUT OFF FOR OVERHEAD WIRES AND SUPPORT POLES AS REQUIRED TO FACILITATE INSTALLATION OF RECEIVING SHAFT, EQUIPMENT, AND STRUCTURES. PROVIDE TEMPORARY STREET LIGHTING FOR DURATION OF POWER INTERRUPTION AND FOR FULL LENGTH OF STREET WHERE LIGHTING HAS BEEN IMPACTED.
- TYPICAL CATCH BASIN EROSION CONTROL
- SEE "GAS MAIN ENCORACHMENT COORDINATION" NOTES ON SHEET GC-1.
- FILL EXISTING MONITORING WELL WITH GROUT.

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM


NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE II: STA 4+00 - 8+00


SHEET
C-3
195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\SheetSet\PAWT_Site_Plan_& Profile_III-A-5_ALT3.dwg | LOT DATE: Monday, April 5, 2021 2:27:48 PM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN



PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID/ CITY OF PAWTUCKET.
- VERTICAL DATUM FOR PROJECT IS NGVD29.

SHEET KEYNOTES

- A. MICROTUNNEL: STATION 8+00 TO STATION 12+00
- B. TYPICAL CATCH BASIN EROSION CONTROL
- C. COORDINATE WITH NATIONAL GRID FOR TEMPORARY POWER SHUT OFF FOR OVERHEAD WIRES AND SUPPORT POLES AS REQUIRED TO FACILITATE INSTALLATION OF RECEIVING SHAFT, EQUIPMENT, AND STRUCTURES. PROVIDE TEMPORARY STREET LIGHTING FOR DURATION OF POWER INTERRUPTION AND FOR FULL LENGTH OF STREET WHERE LIGHTING HAS BEEN IMPACTED.
- D. CONCRETE PIPE AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 8+00 TO 12+00
- E. FILL EXISTING MONITORING WELL WITH GROUT, COORDINATE WITH NATIONAL GRID.

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM




NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE III: STA 8+00 - 12+00


SHEET
C-4
195130227

BY: JAMIE PAYNE


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_SITE_PLAN_&_PROFILE.dwg; LOT DATE: Monday, April 5, 2021 2:28:29 PM



PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)



- GENERAL SHEET NOTES**
- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
 - FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
 - WORK IS IN PROPERTY OWNED BY NATIONAL GRID
 - VERTICAL DATUM FOR PROJECT IS NGVD29.

- SHEET KEYNOTES**
- MICROTUNNEL: STATION 12+00 TO STATION 16+00
 - EXCAVATION AT MH 217-7 TO BE CONSTRUCTED AS WORKING SHAFT IN SUPPORT OF MICROTUNNEL OPERATION. SECANT PILE SOE SYSTEM SHOWN. CONTRACTOR IS RESPONSIBLE FOR DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
 - CONCRETE PIPE AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 12+00 TO 16+00
 - FILL EXISTING MONITORING WELL WITH GROUT. COORDINATE WITH NATIONAL GRID.
 - SUPPORT POLE IN COORDINATION WITH NATIONAL GRID IF GUY WIRE IS REMOVED DURING CONSTRUCTION.

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE AS SHOWN

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: C. CRONIN
DRAWN: B. MARINI
CHECKED: J. D'ALESSIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.





NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE IV: STA 12+00 - 16+00


SHEET C-5
195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_SITE_PLAN & PROFILE_ILM-5_ALT3.dwg | DATE: Monday, April 5, 2021 2:29:03 PM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN



PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID
- RELIEF HOLDER 4: APPROX. DEPTH INFORMATION BASED ON TEST PIT PERFORMED BY OTHERS AND INCLUDED IN PROJECT SPECIFICATIONS AS APPENDIX F. INFORMATION BEYOND DEPTH DEPICTED IS UNKNOWN.
- VERTICAL DATUM FOR PROJECT IS NGVD29.

SHEET KEYNOTES

- A. RELOCATE WATER MAIN: STATION 18+88. SEE SHEET C-8.
- B. SOLDIER PILE AND LAGGING SOE SYSTEM SHOWN IS CONCEPTUAL. CONTRACTOR IS RESPONSIBLE FOR SELECTING SOE SYSTEM TYPE AND DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
- C. TYPICAL CATCH BASIN EROSION CONTROL
- D. PAVEMENT SAW-CUT LIMIT
- E. CONCRETE PIPE, STRUCTURES AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 16+00 TO 18+89
- F. CONSTRUCT TEMPORARY BRICK BULKHEAD IN NORTHWEST FACE CONSOLIDATION CONDUIT PENETRATION OF THE DIVERSION STRUCTURE.

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL


OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE V: STA 16+00 - 18+88

SHEET
C-6
195130227

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_Site_Plan_&_Profile_III-A-5_ALT3.dwg PLOT DATE: Monday, April 5, 2021 2:29:36 PM BY: JAMIE PAYNE




PLAN
SCALE: 1" = 20'



- GENERAL SHEET NOTES**
- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
 - FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
 - WORK IS IN PROPERTY OWNED BY NATIONAL GRID
 - VERTICAL DATUM FOR PROJECT IS NGVD29.

- SHEET KEYNOTES**
- A. CONCRETE PIPE AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 0+00 TO 4+46



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALESIO

90% DESIGN PHASE - APRIL 2021


NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Drawings\Civil\Sheet Set\PAWT_Site_Plan_& Profile.dwg LOT DATE: Monday, April 5, 2021 2:30:08 PM



PLAN
SCALE: 1" = 10'

KEY PLAN



PAWTUCKET, RI

GENERAL SHEET NOTES

1. UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
2. FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
3. WORK IS IN PROPERTY OWNED BY NATIONAL GRID
4. VERTICAL DATUM FOR PROJECT IS NGVD29.
5. WATER MAIN RELOCATION WILL REQUIRE NIGHT WORK. ACCESS TO THE SUBSTATION MUST BE MAINTAINED AT ALL TIMES.

SHEET KEYNOTES

- A. RELOCATE WATER MAIN. COORDINATE WATER SHUTDOWNS WITH NATIONAL GRID

REV	DATE	BY	DESCRIPTION

SCALE
AS SHOWN

WARNING
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN R. GREENWAY
CHECKED

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.









www.BETA-Inc.com

NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
WATER RELOCATION PLAN

SHEET
C-8
195130227




SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
DESIGNED	C. CRONIN
DRAWN	C. MARSHALL
CHECKED	

90% DESIGN PHASE - APRIL 2021


NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.







SEWER MANHOLE FRAME AND COVER
NOT TO SCALE REV 000000 C-107




HEAVY-DUTY ROUND FRAME AND COVER
NOT TO SCALE R.I. STANDARD 6.2.1



SQUARE FRAME AND GRATE (BICYCLE SAFE)
NOT TO SCALE R.I. STANDARD 6.3.2




TRENCH SECTION FOR IMPERMEABLE EARTH WATER STOP
NOT TO SCALE REV 000000 C-904




- NOTES:**
- WHERE SEWER CANNOT BE INSTALLED 18" BENEATH WATER, OR WHERE SEWER AND WATER PIPING ARE WITHIN 10 FEET OF EACH OTHER, PROPOSED WATER OR SEWER PIPE SHALL BE SLEEVED INSIDE AN AWWA C-900 PVC PIPE OF APPROPRIATE DIAMETER WITHIN 10 FEET OF THE CROSSING.
 - CONTRACTOR MAY ELECT TO ENCASE PIPE WITHIN CONCRETE INSTEAD OF USING PIPE SLEEVES, AT NO ADDITIONAL EXPENSE TO THE OWNER. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI AFTER 28 DAYS. CONCRETE ENCASEMENT SHALL EXTEND A MINIMUM OF 6" AROUND THE PIPE IN ALL DIRECTIONS.

WATER/SEWER CROSSING DETAIL
NOT TO SCALE REV 000000 C-112



ELEVATION



WATER STOP SEALANT DETAIL

CONCRETE COLLAR DETAIL
NOT TO SCALE REV 000000 C-109

REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS II

SHEET
C-10
195130227



TYPICAL SUPPORTS FOR UTILITIES
NOT TO SCALE REV 000000 C-113


DIAMETER OF PIPE D IN INCHES	MAXIMUM PAYMENT LIMITS					
	TRENCH WIDTH IN FEET		TEMPORARY TRENCH PAVEMENT WIDTH IN FEET		PERMANENT TRENCH PAVEMENT WIDTH IN FEET*	
	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH
12 AND SMALLER	< OR = 10'	> 10' TO 20'	< OR = 10'	> 10' TO 20'	< OR = 10'	> 10' TO 20'
15	5.00	6.00	6.00	7.00	8.00	9.00
18	5.25	6.25	6.25	7.25	8.25	9.25
21	5.50	6.50	6.50	7.50	8.50	9.50
24	5.75	6.75	6.75	7.75	8.75	9.75
27	6.00	7.00	7.00	8.00	9.00	10.00
30	6.25	7.25	7.25	8.25	9.25	10.25
36	6.50	7.50	7.50	8.50	9.50	10.50
42	6.75	7.75	7.75	8.75	9.75	10.75
48	7.00	8.00	8.00	9.00	10.00	11.00
54	7.25	8.25	8.25	9.25	10.25	11.25
60	7.50	8.50	8.50	9.50	10.50	11.50
66	7.75	8.75	8.75	9.75	10.75	11.75
72	8.00	9.00	9.00	10.00	11.00	12.00

TRENCH WIDTH SCHEDULE


NOTES:

- PERMANENT TRENCH PAVEMENT INCLUDES 1' CUT BACK OF TEMPORARY PAVEMENT ALONG EACH SIDE OF THE TRENCH.
- TRENCH DEPTH MEASURED FROM THE EXISTING GROUND SURFACE TO 6" BELOW THE BOTTOM OF THE CONSTRUCTED PIPE.
- QUANTITIES FOR PAYMENT SHALL BE IN ACCORDANCE WITH THE ABOVE LIMITS OR THE ACTUAL WIDTHS, WHICHEVER IS LESS.

TRENCH WIDTH SCHEDULE
NOT TO SCALE REV 000000 C-905




TRENCH SECTION (TO BE USED WHERE UNSUITABLE FOUNDATION MATERIAL EXISTS BELOW NORMAL DEPTH)
NOT TO SCALE REV 000000 C-906



NOTES:

- CONCRETE SIDEWALK SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 905 OF THE R.I. STANDARD SPECIFICATIONS.
- WIRE MESH SHALL BE IN ACCORDANCE WITH SECTION M.05.02 OF THE R.I. STANDARD SPECIFICATIONS.


TYPICAL CEMENT CONCRETE SIDEWALK
NOT TO SCALE REV 000000 C-202





NOTES:

- SHALL BE IN ACCORDANCE WITH SECTION 906 OF THE R.I. STANDARD SPECIFICATIONS.
- PROVIDE CEMENT CONCRETE CURB LOCK ON ALL CURBS.

CURB SETTING DETAIL
NOT TO SCALE REV 000000 C-203



DETECTABLE WARNING PAVER
NOT TO SCALE REV 000000 C-204



DETAIL FOR SIDEWALK AT STONE WALL
NOT TO SCALE REV 000000 C-907

REV	DATE	BY	DESCRIPTION

SCALE AS SHOWN

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN C. MARSHALL
CHECKED

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION



This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS III





ROADWAY PROFILE GRADE	T (FT)
0.00	6.0
0.01	7.0
0.02	8.0
0.03	9.5
0.04	11.5
0.05	15.0

NOTES:

1. SHALL BE IN ACCORDANCE WITH SECTION 905 OF THE RI STANDARD SPECIFICATIONS.
2. WHEN ANY OBSTRUCTION LOCATED IN THE SIDEWALK FALLS WITHIN A CROSSWALK AREA, THE WHEELCHAIR RAMP WILL BE PLACED SUCH THAT THE OBSTRUCTION FALLS OUTSIDE OF THE RAMP.
3. AT NO TIME IS ANY PART OF THE WHEELCHAIR RAMP TO BE LOCATED OUTSIDE OF THE CROSSWALK, AND IT IS TO BE CENTERED WHENEVER POSSIBLE.
4. DRAINAGE FACILITIES ARE TO BE LOCATED UP-GRADE OF ALL WHEELCHAIR RAMPS.
5. LOCATION OF WHEELCHAIR RAMPS IS AS SHOWN ON CONTRACT DRAWINGS.
6. IN NO INSTANCE SHALL THE SIDEWALK CROSS SLOPE EXCEED 1:50 EXCEPT WITHIN THE RAMP AREA.
7. AN UNOBSTRUCTED PATH OF TRAVEL WITH A MINIMUM WIDTH OF 3'-0" SHALL BE MAINTAINED.
8. THE WHEELCHAIR RAMP SLOPE AND SIDE SLOPES (TRANSITIONS), MUST NOT EXCEED 1:12. HOWEVER, THESE SLOPES MAY BE FLATTER THAN 1:12 WHEN WARRANTED BY SURROUNDING CONDITIONS.
9. WHERE THE ROAD PROFILE EXCEEDS 5% THE HIGH SIDE TRANSITION LENGTH (T) SHALL BE EIGHTEEN FEET (18'-0").
10. IN NO CASE, WHERE A STOP LINE IS WARRANTED, SHALL A RAMP BE PLACED BEHIND THE STOP LINE.
11. THE ENTRANCE OF THE WHEELCHAIR RAMP SHALL BE FLUSH WITH THE ROADWAY.
12. THE WHEELCHAIR RAMP SHALL BE CENTERED RADIALLY, OPPOSITE THE RADIUS POINT WHEN POSSIBLE.
13. MINIMUM LENGTH OF STRAIGHT OR CIRCULAR FILLER PIECES TO BE 3'-0" (GREATER LENGTHS PREFERRED).
14. 8" CONCRETE DEPTH FOR RADIUS WHEELCHAIR RAMPS ONLY. USE 4" DEPTH FOR TANGENT (MID-BLOCK) LOCATIONS

WHEELCHAIR RAMP
NOT TO SCALE

R.I. STANDARD
43.3.0





NOTES:

1. SHALL BE IN ACCORDANCE WITH SECTION 905 OF THE R.I. STANDARD SPECIFICATIONS.
2. THIS DETAIL IS TO BE USED ONLY WHEN STATE RIGHT-OF-WAY IS LIMITED TO BACK OF SIDEWALK, AND SIDEWALK IS NARROW WITH NO PEDESTRIAN TRAFFIC FROM SIDE STREET.
3. WHEN ANY OBSTRUCTION LOCATED IN THE SIDEWALK FALLS WITHIN A CROSSWALK AREA, IF POSSIBLE, THE OBSTRUCTION SHALL BE PLACED SUCH THAT IT FALLS OUTSIDE OF THE RAMP.
4. AT NO TIME IS ANY PART OF THE WHEELCHAIR RAMP TO BE LOCATED OUTSIDE OF THE CROSSWALK, AND IT IS TO BE CENTERED WHENEVER POSSIBLE.
5. DRAINAGE FACILITIES ARE TO BE LOCATED UP-GRADE OF ALL WHEELCHAIR RAMPS.
6. LOCATION OF WHEELCHAIR RAMPS IS AS SHOWN ON CONTRACT DRAWINGS.
7. ALL REQUIRED CUTTING OF CURB PIECES TO BE PAID FOR UNDER COST OF CURB.
8. WHERE THE ROAD PROFILE EXCEEDS 5% THE TRANSITION LENGTH (T) SHALL BE EIGHTEEN FEET (18'-0").
9. THE ENTRANCE OF THE WHEELCHAIR RAMP SHALL BE FLUSH WITH THE ROADWAY.
10. MINIMUM LENGTH OF STRAIGHT OR CIRCULAR FILLER PIECES TO BE 3'-0" (GREATER LENGTHS PREFERRED).
11. AN UNOBSTRUCTED PATH OF TRAVEL WITH A MINIMUM WIDTH OF 4'-0" SHALL BE MAINTAINED.

ROADWAY GRADE	T
0.00	6.0
0.01	7.0
0.02	8.0
0.03	9.5
0.04	11.5
0.05	15.0

WHEELCHAIR RAMP FOR LIMITED RIGHT-OF-WAY AREAS
NOT TO SCALE

R.I. STANDARD
43.3.1



NOTES:

1. EXPANSION JOINTS (EJ) 20 FEET OC UNLESS OTHERWISE NOTED.
2. CONTROL JOINTS (CJ) 5 FEET OC UNLESS OTHERWISE NOTED.
3. WHERE EXISTING AND NEW CONCRETE SIDEWALKS MEET, SAWCUT EXISTING WALK AND INSTALL EXPANSION JOINT AND DOWELS AS SHOWN. DRILL EXISTING CONCRETE WALK EDGE TO RECEIVE STEEL DOWELS AT EXPANSION JOINT.

EXPANSION AND CONTROL JOINTS FOR SIDEWALK PAVING
NOT TO SCALE

C-205

REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE








DESIGNED	C. CRONIN
DRAWN	C. MARSHALL
CHECKED	

90% DESIGN PHASE - APRIL 2021
NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM
NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS IV

SHEET
C-12
195130227



REV	DATE	BY	DESCRIPTION



SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
DESIGNED	C. CRONIN
DRAWN	C. MARSHALL
CHECKED	

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION


This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.






NOTES:
1. ACTUAL LOCATIONS OF CUT AND MATCH LINES TO BE DETERMINED IN THE FIELD.

PROJECT LIMITS CUT AND MATCH DETAIL
NOT TO SCALE REV 000000 C-911




NOTES:
1. TRANSVERSE DROP-OFF:
POSTED SPEED < 35 MPH: 5 FEET HORIZONTALLY TO 1 INCH VERTICALLY
POSTED SPEED > 35 MPH: 10 FEET HORIZONTALLY TO 1 INCH VERTICALLY
2. LONGITUDINAL DROP-OFF (OUTSIDE EDGES OF PAVEMENT):
POSTED SPEED < 35 MPH: DROP-OFFS > 3\"/>

PAVEMENT REMOVAL DROP-OFF DETAIL
NOT TO SCALE R.I. STANDARD 47.1.0




NOTES:
1. A BOND BREAKER (TAPERED OR EQUIVALENT) WILL BE PLACED 5'-0\"/>

TRANSVERSE PAVEMENT CUT AND MATCH
NOT TO SCALE R.I. STANDARD 47.1.1



NOTES:
1. CONTRACTOR TO VARY PAVEMENT THICKNESS TO MAINTAIN A MINIMUM CROSS SECTIONAL SLOPE EQUALING 0.02 FT/FT OR %.

TEMPORARY TRENCH-WIDTH PAVEMENT
NOT TO SCALE REV 000000 C-912



NOTES:
1. CONTRACTOR TO VARY PAVEMENT THICKNESS TO MAINTAIN A MINIMUM CROSS SECTIONAL SLOPE EQUALING 0.02 FT/FT OR %.

PERMANENT TRENCH-WIDTH PAVEMENT
NOT TO SCALE REV 000000 C-913

REV	DATE	BY	DESCRIPTION

SCALE
AS SHOWN


WARNING
IF THIS BAR DOES NOT MEASURE 1\"/>

DESIGNED C. CRONIN
DRAWN C. MARSHALL
CHECKED

90% DESIGN PHASE - APRIL 2021
NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS VI




- NOTES:**
- MINIMUM PAVEMENT THICKNESS TO BE 2". CONTRACTOR TO VARY PAVEMENT THICKNESS TO MAINTAIN A MINIMUM CROSS SECTIONAL SLOPE EQUALING 0.02 FT/FT.
 - CUT BACK DISTANCES SHALL BE AS DIRECTED BY THE ENGINEER. HOWEVER, UNDER NO CIRCUMSTANCES SHALL THEY BE LESS THAN THE MINIMUM INDICATED.
 - REFER TO SPECIFICATION 02502 FOR MICROMILLING.

CURB TO CURB PAVEMENT RESTORATION
NOT TO SCALE REV 000000 C-914




- CONTRACTOR TO MATCH EXISTING STRIPING AT THE FOLLOWING LOCATIONS:
- LOCATIONS:**
- INTERSECTION OF MAIN STREET (65 FT WIDE) AND ROOSEVELT AVENUE EXT (34 FT WIDE)
 - 4 CROSSWALKS AND 4 STOPLINES
 - INTERSECTION OF JENKS WAY (44 FT WIDE) AND ROOSEVELT AVENUE EXT (31 FT WIDE)
 - 2 CROSSWALKS AND 1 STOPLINE
 - TAFT STREET (62 FT WIDE) AT APPROXIMATELY 650 FT NORTH OF SPENCER STREET
 - 1 CROSSWALK
 - INTERSECTION OF TOWER STREET (25 FT WIDE) AND TAFT STREET (48 FT WIDE)
 - 2 CROSSWALKS AND 2 STOPLINE
 - INTERSECTION OF TIDEWATER STREET (32 FT WIDE) AND TAFT STREET (30 FT WIDE)
 - 2 CROSSWALKS AND 2 STOPLINES


CROSSWALK AND STOPLINE DETAIL - TYPE 1
NOT TO SCALE REV 000000 C-915



GRAVEL ACCESS ROAD
NOT TO SCALE REV 000000 C-916




GROUND COVER DETAIL
NOT TO SCALE REV 000000 C-917





- NOTES:**
- ALL DEWATERING DISCHARGES SHALL BE THROUGH SEDIMENT CONTROL TRAPS. CONTRACTOR SHALL MAINTAIN AND CLEAN TRAP AS REQUIRED.

SEDIMENT CONTROL TRAP
NOT TO SCALE REV 000000 C-918



- NOTES:**
- ALL DEWATERING DISCHARGES SHALL BE THROUGH DEWATERING BAG, CONTRACTOR SHALL MAINTAIN AND CLEAN AS REQUIRED.
 - CONTRACTOR SHALL SUBMIT DEWATERING PLANS TO THE ENGINEER/OWNER FOR APPROVAL.
 - SIZING OF DEWATERING BAG SHALL BE BASED ON BUT NOT LIMITED TO THE FOLLOWING:
 - 3a. PUMP FLOW RATE
 - 3b. QUALITY AND TYPE OF SEDIMENT
 - 3c. VOLUME OF MATERIALS NEEDING CONTAINMENT

SEDIMENT CONTROL TRAP WITH DEWATERING BAG
NOT TO SCALE REV 000000 C-919



- NOTES:**
- COMPOST/ SOIL/ ROCK/ SEED FILL TO MEET APPLICATION REQUIREMENTS.
 - COMPOST MATERIAL TO BE REMOVED OR DISPERSED ON SITE AS DETERMINED BY ENGINEER.
 - IF SOCK NETTING MUST BE JOINED, FIT BEGINNING OF NEW SOCK OVER END OF OLD SOCK, OVERLAPPING BY 2 FEET AND STACK OVERLAP. IF SOCK NETTING IS NOT JOINED, OVERLAP OLD SOCK WITH NEW ONE BY MINIMUM OF 2 FEET.

COMPOST FILTER SOCK
NOT TO SCALE REV 000000 C-401

REV	DATE	BY	DESCRIPTION

SCALE
AS SHOWN

WARNING
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN C. MARSHALL
CHECKED _____

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION


This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL


OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS VII




NOTES:

1. STOCKPILE AREA SHALL NOT EXCEED SPECIFIED DIMENSIONS WITHOUT APPROVAL FROM ENGINEER.
2. STOCKPILED ERODIBLE MATERIAL THAT WILL NOT BE USED FOR GREATER THAN 14 DAYS SHALL BE STABILIZED WITH TEMPORARY SEED IMMEDIATELY FOLLOWING PLACEMENT. USE RIDOT STD M.18.10.5 SEED MIX.

ERODIBLE MATERIAL STOCKPILE
NOT TO SCALE REV 000000 C-402




TEMPORARY INLET PROTECTION
NOT TO SCALE REV 000000 C-403



NOTES:

1. TREE GROUP PROTECTION SHALL BE INSTALLED AT THE DRIP LINE OF THE TREES TO BE PROTECTED.

TREE GROUP PROTECTION DETAIL
NOT TO SCALE REV 000000 C-404



* NO MINIMUM VERTICAL SEPARATION IS REQUIRED PROVIDED A 10 FOOT HORIZONTAL SEPARATION IS MAINTAINED BETWEEN WATER PIPE AND SEWER LINE.

WHERE IT IS NOT POSSIBLE TO MAINTAIN A 10 FOOT HORIZONTAL SEPARATION, A DEVIATION MAY BE GRANTED ON A CASE BY CASE BASIS. SUCH DEVIATION MAY ALLOW INSTALLATION OF THE SEWER LINE CLOSER TO THE WATER PIPE PROVIDED THAT THE SEWER LINE AND WATER PIPE ARE LAID IN SEPARATE TRENCHES (OR ON AN UNDISTURBED EARTH SHELF LOCATED ON ONE SIDE OF THE SEWER LINE) AT SUCH AN ELEVATION THAT THE CROWN OF THE SEWER LINE SHALL BE AT LEAST 18 INCHES BELOW THE BOTTOM OF THE WATER PIPE.


IF BOTH THE 10 FOOT MINIMUM HORIZONTAL AND 18 INCH MINIMUM VERTICAL SEPARATION CANNOT BE MAINTAINED, ONE OF THE FOLLOWING OPTIONS MUST BE USED FOR A DISTANCE THAT WILL PROVIDE THE REQUIRED 10 FOOT HORIZONTAL OR 18 INCH VERTICAL SEPARATION:

OPTION A: CONSTRUCT SEWER LINE USING AWWA APPROVED WATER MAIN PIPE AND PRESSURE TEST TO 150psi.

OPTION B: ENCASE SEWER LINE IN CONCRETE (MIN. 6 INCHES THICK) OR SLEEVE. (SEE PWSB STD. DETAIL 1.06 FOR SLEEVE DETAIL.)

	PAWTUCKET WATER SUPPLY BOARD	
	WATER AND SEWER SEPARATION DETAIL FOR PARALLEL PLACEMENT	
REVISION DATE: DEC. 2013	NOT TO SCALE	STD. NO. 1.05

WATER AND SEWER SEPARATION DETAIL FOR PARALLEL PLACEMENT
REV 000000 W-105




* IF THE 18 INCH MINIMUM VERTICAL SEPARATION CANNOT BE MAINTAINED, ONE OF THE FOLLOWING OPTIONS MUST BE USED FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE CROSSING, MEASURED PARALLEL TO THE WATER PIPE:

OPTION A: CONSTRUCT SEWER USING AWWA APPROVED WATER MAIN PIPE AND PRESSURE TEST TO 150psi.

OPTION B: ENCASE SEWER PIPE IN CONCRETE (MIN. 6 INCHES THICK) OR SLEEVE.


	PAWTUCKET WATER SUPPLY BOARD	
	WATER AND SEWER SEPARATION DETAIL AT CROSSING	
REVISION DATE: JAN. 2012	NOT TO SCALE	STD. NO. 1.06

WATER AND SEWER SEPARATION DETAIL AT CROSSING
REV 000000 W-106




	PAWTUCKET WATER SUPPLY BOARD	
	1\"/>	
REVISION DATE: FEB. 2006	NOT TO SCALE	STD. NO. 3.05

1\"/>



	PAWTUCKET WATER SUPPLY BOARD	
	2\"/>	
REVISION DATE: MAY 2006	NOT TO SCALE	STD. NO. 3.06

2\"/>



	PAWTUCKET WATER SUPPLY BOARD	
	MAIN CONNECTION AT INTERSECTION (CUT-IN TEE)	
REVISION DATE: FEB. 2006	NOT TO SCALE	STD. NO. 5.02

MAIN CONNECTION AT INTERSECTION (CUT-IN TEE)
NOT TO SCALE REV 000000 W-502


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1\"/>
DESIGNED	C. CRONIN
DRAWN	C. MARSHALL
CHECKED	

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION


This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.





PAWTUCKET WATER SUPPLY BOARD		MAIN CONNECTION AT INTERSECTION (OFFSET)	
REVISION DATE: FEB. 2006	NOT TO SCALE	STD. NO. 5.03	

MAIN CONNECTION AT INTERSECTION (OFFSET) NOT TO SCALE REV 000000 W-503



RESTRAINT AT FITTINGS


MINIMUM SURFACE AREA OF CONCRETE THRUST BLOCK AGAINST UNDISTURBED EARTH - IN S.F. (SQUARE FEET)
 MINIMUM RESTRAINED LENGTH OF PIPE ON EITHER SIDE OF FITTING - IN L.F. (LINEAR FEET)

PIPE SIZE	PLUG LF	TEE LF	90° BEND LF	45° BEND LF	22½° BEND LF	11½° BEND LF
6"	2.8	3.7	2.8	3.2	4.0	1.8
8"	4.8	4.8	4.8	4.3	6.5	2.3
10"	7.3	5.8	7.3	5.3	10.3	2.8
12"	10.3	6.9	10.3	6.3	14.5	3.3
16"	17.8	8.9	17.8	8.3	25.2	4.2
20"	27.5	10.8	27.5	10.2	38.9	5.1
24"	39.2	12.7	39.2	12.1	55.4	5.9

1. ALL CONCRETE TO BE CLASS B (AE)
2. THE "SF" VALUES IN THE ABOVE TABLE ARE BASED ON 3000 p.s.f. SOIL BEARING CAPACITY, 150 p.s.i. TEST PRESSURE AND A 1.5 FACTOR OF SAFETY.
3. THE "LF" VALUES IN THE ABOVE TABLE ARE BASED ON A TYPE 3 LAYING CONDITIONS, A SAND SILT SOIL DESIGNATION, A 5 FOOT RUN LENGTH, 150 P.S.I. TEST PRESSURE AND A 1.5 FACTOR OF SAFETY AS USED IN THE "THRUST RESTRAINT DESIGN FOR DUCTILE IRON PIPE" COMPUTER PROGRAM BY THE DUCTILE IRON PIPE RESEARCH ASSOCIATION.
4. IF SOIL CONDITIONS OR EXCAVATION LIMITS ENCOUNTERED DURING CONSTRUCTION MAKE IT UNFEASIBLE TO PLACE THRUST BLOCKS AGAINST UNDISTURBED EARTH OF THE PROPER BEARING CAPACITY, THE CONTRACTOR SHALL DESIGN AND PLACE SPECIAL REACTION BLOCKS OF SUFFICIENT WEIGHT TO RESIST FULL THRUST UNDER ALL CONDITIONS. THE DESIGN SHALL BE SUBJECT TO PWSB APPROVAL.
5. MINIMUM SURFACE AREAS SHALL BE INCREASED BY 50% IF DEEMED NECESSARY BY THE ENGINEER.
6. A MECHANICAL JOINT RESTRAINT SYSTEM MUST BE USED FOR VERTICAL BENDS.
7. AT THE DISCRETION OF THE ENGINEER, A JOINT RESTRAINT SYSTEM MAY BE SUBSTITUTED FOR OR USED IN COMBINATION WITH PROPER THRUST BLOCKING.
8. A 48 HR. CURING PERIOD MUST BE GIVEN BEFORE FULL LINE PRESSURE CAN BE APPLIED TO NEW CONCRETE THRUST BLOCKS.
9. ANCHOR BLOCK DESIGN FOR PIPE LARGER THAN 24" SHALL BE REVIEWED ON AN INDIVIDUAL BASIS BY THE PWSB.


PAWTUCKET WATER SUPPLY BOARD		RESTRAINT AT FITTINGS	
REVISION DATE: MAY 2006	NOT TO SCALE	STD. NO. 5.04	

RESTRAINT AT FITTINGS NOT TO SCALE REV 000000 W-504




PAWTUCKET WATER SUPPLY BOARD		TYPICAL TRENCH DETAIL	
REVISION DATE: MAY 2006	NOT TO SCALE	STD. NO. 6.01	

TYPICAL TRENCH DETAIL NOT TO SCALE REV 000000 W-601



PAWTUCKET WATER SUPPLY BOARD		TYPICAL "TEMPORARY BYPASS PIPING" INSTALLATION	
REVISION DATE: JAN 2011	NOT TO SCALE	STD. NO. 8.01	


TYPICAL "TEMPORARY BYPASS PIPING" INSTALLATION NOT TO SCALE REV 000000 W-801



- TEMPORARY WATER SERVICE CONNECTION AT HYDRANT - ELEVATION VIEW**
- TESTABLE BACKFLOW PREVENTION DEVICE (SEE NOTE 2)
 METER
 (2) BALL TYPE VALVES (200 P.S.I. PRESSURE RATING)
 METER SUPPORT BY CONTRACTOR
- NOTES:
 1. THE METER SHALL BE INSTALLED HORIZONTALLY.
 2. TEMPORARY WATER SERVICE CONNECTIONS REQUIRE A PWSB APPROVED TESTABLE BACKFLOW PREVENTION DEVICE, ALL IN ACCORDANCE WITH SECTION 10 OF THE PWSB REGULATIONS, LATEST REVISION.
 3. CONTRACTOR MUST NOTIFY THE PWSB METER DEPARTMENT WHEN THE METER INSTALLATION IS COMPLETE.

PAWTUCKET WATER SUPPLY BOARD		TEMPORARY WATER SERVICE CONNECTION AT HYDRANT	
REVISION DATE: JAN. 2011	NOT TO SCALE	STD. NO. 8.02	


TEMPORARY WATER SERVICE CONNECTION AT HYDRANT NOT TO SCALE REV 000000 W-802



- TYPICAL FIRE SERVICE CONNECTION**
- NEW CL52 DI PIPE FIRE SERVICE (4" MIN OR EXISTING SIZE)
 EXISTING WATER MAIN
 EXISTING FIRE SERVICE GATE VALVE
 CAP EXISTING FIRE SERVICE
 SOLID SLEEVE COUPLING
 BENDS AND FITTINGS AS NECESSARY FOR VERTICAL AND HORIZONTAL ALIGNMENT (SEE NOTE 1)
 NEW SERVICE UNDER EXISTING MAIN
 NEW FIRE SERVICE GATE VALVE
 ANCHOR TEE
 NEW WATER MAIN
- NOTES:
 1. ALL FITTINGS SHALL BE RESTRAINED.

PAWTUCKET WATER SUPPLY BOARD		TYPICAL FIRE SERVICE CONNECTION	
REVISION DATE: MAY 2006	NOT TO SCALE	STD. NO. 5.04	


TYPICAL FIRE SERVICE CONNECTION NOT TO SCALE REV 000000 W-901



- NOTES:
 1. DEVICES NEED TO BE PLACED BEYOND THE AREA OF RESTRAINTS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

PAWTUCKET WATER SUPPLY BOARD		TYPICAL THRUST RESTRAINT WEDGE ACTION TYPE JOINTS	
REVISION DATE: MAY 2006	NOT TO SCALE	STD. NO. 6.01	

TYPICAL THRUST RESTRAINT WEDGE ACTION TYPE JOINTS NOT TO SCALE REV 000000 W-902



- NOTES:
 1. ALL Ductile Iron PIPE THAT IS BACKFILLED WITH CONTROLLED DENSITY FILL MUST BE ENCASED WITH 4-MIL HDCL OR 8-MIL LLD POLYETHYLENE IN ACCORDANCE WITH ANS/AWWA C105/A2.5, METHOD OF INSTALLATION.
 2. THE PIPE SHALL BE PROPERLY SECURED AND SUPPORTED TO PREVENT DISPLACEMENT DURING THE POURING OF CONTROLLED DENSITY FILL.

PAWTUCKET WATER SUPPLY BOARD		FLOWABLE FILL BACKFILL OF DUCTILE IRON WATER PIPE	
REVISION DATE: JAN 2011	NOT TO SCALE	STD. NO. 8.01	

FLOWABLE FILL BACKFILL OF DUCTILE IRON WATER PIPE NOT TO SCALE REV 000000 W-903

SCALE	AS SHOWN	WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
DESIGNED	C. CRONIN	DRAWN	C. MARSHALL
CHECKED			

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION


This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




BY: OBRIEN, JANET

PLOT DATE: Wednesday, March 24, 2021 9:33:49 AM

DWG FILE: C:\Users\obrien\Box\19515980.0 NBC - CC IIIA-4 And IIIA-5\CADD\Engr Working\GTGT001.dwg



PLAN
SCALE: 1" = 20'



PLAN
SCALE: 1" = 20'

KEY PLAN



GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- REFER TO SHEET B-4 FOR INSTRUMENTATION DETAILS AND NOTES.
- REFER TO SPECIFICATION SECTION 02295 FOR INSTRUMENTATION REQUIREMENTS.

INSTRUMENTATION LEGEND

SYMBOL	INSTRUMENT TYPE
	OBSERVATION WELL (OW)
	DEFORMATION MONITORING POINT (DMP TYPE 1)
	DEFORMATION MONITORING POINT (DMP TYPE 2)
	DEFORMATION MONITORING POINT (DMP TYPE 3)
	INCLINOMETER (INCL)
	UTILITY MONITORING POINT (UMP)
	SEISMOGRAPH

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	K. OHARA
DRAWN	S. WILBUR
CHECKED	T. MUINDI

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec PARE

NBC CONTRACT NO 308.05C
GEOTECHNICAL


OF-217 CONSOLIDATION CONDUIT
INSTRUMENTATION PLAN STA. 0+00 - 8+00

SHEET
B-1
195130227


BY: OBRIEN, JANET

PLOT DATE: Wednesday, March 24, 2021 9:38:33 AM

DWG FILE: C:\Users\obrien\Box\lob\15980.0 NBC - CC IIIA-4 And IIIA-5\CADD\Engr Working\GTGT002.dwg




PLAN
SCALE: 1" = 20'



PLAN
SCALE: 1" = 20'

KEY PLAN



GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID/ CITY OF PAWTUCKET.
- REFER TO SHEET B-4 FOR INSTRUMENTATION DETAILS AND NOTES.
- REFER TO SPECIFICATION SECTION 02295 FOR INSTRUMENTATION REQUIREMENTS.

INSTRUMENTATION LEGEND	
SYMBOL	INSTRUMENT TYPE
	OBSERVATION WELL (OW)
	DEFORMATION MONITORING POINT (DMP TYPE 1)
	DEFORMATION MONITORING POINT (DMP TYPE 2)
	DEFORMATION MONITORING POINT (DMP TYPE 3)
	INCLINOMETER (INCL)
	UTILITY MONITORING POINT (UMP)
	SEISMOGRAPH

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	K. OHARA
DRAWN	S. WILBUR
CHECKED	T. MUINDI

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.






NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec PARE

NBC CONTRACT NO 308.05C
GEOTECHNICAL

OF-217 CONSOLIDATION CONDUIT
INSTRUMENTATION PLAN STA. 8+00 - 16+00

SHEET
B-2
195130227



- ### GENERAL SHEET NOTES
- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
 - FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
 - WORK IS IN PROPERTY OWNED BY NATIONAL GRID
 - REFER TO SHEET B-4 FOR INSTRUMENTATION DETAILS AND NOTES.
 - REFER TO SPECIFICATION SECTION 02295 FOR INSTRUMENTATION REQUIREMENTS.

INSTRUMENTATION LEGEND	
SYMBOL	INSTRUMENT TYPE
	OBSERVATION WELL (OW)
	DEFORMATION MONITORING POINT (DMP TYPE 1)
	DEFORMATION MONITORING POINT (DMP TYPE 2)
	DEFORMATION MONITORING POINT (DMP TYPE 3)
	INCLINOMETER (INCL)
	UTILITY MONITORING POINT (UMP)
	SEISMOGRAPH

REV	DATE	BY	DESCRIPTION
1			

SCALE AS SHOWN

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: K O'HARA
 DRAWN: S WILBUR
 CHECKED: T MUINDI







90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




BY: OBRIEN, JANET
 PLOT DATE: Wednesday, March 24, 2021 9:56:22 AM
 DWG FILE: C:\Users\obrien\Box\lobs1980.0.NBC - CC IIIA-4 And IIIA-5\CADD\Engr Working\GTGT003.dwg




- NOTES**
1. MATERIAL AND INSTALLATION DETAILS FOR ALL APPLICABLE INSTRUMENTS SHOWN ON THIS DRAWING ARE PROVIDED IN SECTION 02295 OF THE SPECIFICATIONS.
 2. INSTRUMENT LOCATIONS SHOWN ON THE DRAWINGS ARE APPROXIMATE. ACTUAL LOCATIONS SHALL BE ADJUSTED TO ACCOMMODATE FIELD CONDITIONS, AS APPROVED BY PM.
 3. OBTAIN APPROVAL FROM PROPERTY OWNERS BEFORE INSTALLING ANY INSTRUMENTS ON PRIVATE PROPERTY.
 4. OBTAIN PERMITS AND APPROVALS FOR ALL INSTRUMENTATION TO BE INSTALLED IN THE RIGHT-OF-WAY.
 5. REMOVE INSTRUMENTS AND RESTORE LOCATIONS IN ACCORDANCE WITH THE SPECIFICATIONS.

**MINIMUM DESIGN CRITERIA FOR LATERAL EARTH PRESSURES:
SURCHARGE (S)**



**MINIMUM DESIGN CRITERIA FOR LATERAL EARTH PRESSURES:
SOIL (E) AND WATER (W)**



**MINIMUM DESIGN CRITERIA
FOR TEMPORARY EXCAVATION SUPPORT SYSTEM COMPONENTS**

STRUCTURE	VERTICAL LOADS		HORIZONTAL LOADS (E), (S) AND (W)	DESIGN LOADING COMBINATIONS AND ALLOWABLE UNIT STRESSES
	DEAD LOADS (DL)	LIVE LOADS (LL)		
WALL SYSTEM (ELEMENTS IN CONTACT WITH RETAINED EARTH)	WEIGHT OF WALL	REACTIONS FROM ALL LIVE LOADS INCLUDING APPLICABLE CONSTRUCTION EQUIPMENT LOADING, OTHER SURCHARGES, PEDESTRIAN WALKWAY LOADS, AND AASHTO HS20-44 LOADING, SEE NOTES	LOADS FROM LATERAL EARTH AND WATER PRESSURES AND LATERAL SURCHARGE PRESSURES [(E)+(S)+(W)] AXIAL LOADS FROM END WALL BRACING MEMBERS (E)+(S)+(W), WHERE APPLICABLE	100% OF [(DL)+(LL)+(E)+(S)+(W)] CONFORM TO ACI 318 FOR REINFORCED CONCRETE DESIGN
PRIMARY BRACING MEMBERS (MEMBERS CARRYING DIRECT LOADS INCLUDING WALES, STRUTS, CORNER BRACING, AND RAKERS)	WEIGHT OF PRIMARY BRACING MEMBER		LOADS FROM WALL SYSTEM [(E)+(S)+(W)] AXIAL LOADS FROM END WALLS [(E)+(S)+(W)], WHERE APPLICABLE	FOR PRIMARY BRACING MEMBERS: 100% OF [(DL)+(LL)+(E)+(W)+(S)] FOR WALLS: 120% OF ALLOWABLE UNIT STRESSES
SECONDARY BRACING MEMBERS FOR SUPPORT OF INTERNAL BRACING MEMBERS (IF NECESSARY)	WEIGHT OF SECONDARY BRACING MEMBER PLUS WEIGHT OF SUPPORTED PRIMARY BRACING MEMBERS, WHERE APPLICABLE	AXIAL LOAD EQUAL TO 3% OF THE DESIGN AXIAL LOAD IN THE MORE HEAVILY LOADED ADJACENT PRIMARY BRACING MEMBER	AXIAL LOAD EQUAL TO 3% OF THE DESIGN AXIAL LOAD IN THE MORE HEAVILY LOADED ADJACENT PRIMARY BRACING MEMBER	120% OF ALLOWABLE UNIT STRESSES

PROPERTIES OF RETAINED SOIL

MATERIAL	TOTAL UNIT WEIGHT, γ (PCF)	EFFECTIVE UNIT WEIGHT, γ' (PCF)	FRICTION ANGLE	UNDRAINED SHEAR STRENGTH S_u (PSF)	AT-REST PRESSURE COEFFICIENT K_o	ACTIVE PRESSURE COEFFICIENT K_a	PASSIVE PRESSURE COEFFICIENT K_p
FILL	125	58	32°	NA	0.47	0.31	3.26
ALLUVIAL	120	63	30°	NA	0.5	0.33	3.00
GLACIOFLUVIAL	125	63	32°	NA	0.47	0.31	3.26
GLACIAL TILL	135	68	34°	NA	0.44	0.28	3.54

NOTES:

- FOR MINIMUM DESIGN CRITERIA FOR EXCAVATION SUPPORT NOTES, SEE SHEET B-6.
- SEE SHEET B-6, NOTE B10 FOR IMPERMEABLE VERSUS PERMEABLE SUPPORT WALL DESIGN CONSIDERATIONS.

REV	DATE	BY	DESCRIPTION

SCALE	WARNING
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED <u>K. OHARA</u>
DRAWN <u>D. NOWAK</u>
CHECKED <u>T. MUNDI</u>

60% DESIGN PHASE - DECEMBER 2020

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
GEOTECHNICAL

OF-217 CONSOLIDATION CONDUIT
MINIMUM DESIGN CRITERIA FOR EXCAVATION SUPPORT

NOTES FOR ANALYSIS AND DESIGN

A. GENERAL

- A1. DUE TO A VARIETY OF PAST USES IN THE AREA, NUMEROUS OBSTRUCTIONS WILL BE ENCOUNTERED DURING INSTALLATION OF EXCAVATION SUPPORT SYSTEMS. TYPES OF OBSTRUCTIONS ANTICIPATED TO BE ENCOUNTERED INCLUDE: BOULDERS, GRANITE, CONCRETE OR BRICK FOUNDATION WALLS, AND CONCRETE FLOORS FROM PREVIOUS STRUCTURES, ABANDONED WOOD PILES, TANK FOUNDATIONS AND VARIOUS OTHER DEMOLITION AND CONSTRUCTION DEBRIS.
- A2. FLEXIBLE WALL SYSTEMS ARE CONSIDERED TO BE SOLDIER PILE AND LAGGING WALLS AND SIMILAR SUPPORT SYSTEMS. RIGID WALL SYSTEMS ARE CONSIDERED TO BE SECANT PILE WALLS
- A3. METHODS OF PERMITTED ANALYSIS INCLUDE:
 - LIMIT EQUILIBRIUM METHOD SHALL BE USED FOR STRENGTH DESIGN .
 - NONLINEAR ANALYSIS USING ELASTO-PLASTIC WINKLER SPRINGS SHALL BE USED FOR DEFORMATION CONTROLLED DESIGN .
- A4. TEMPORARY EXCAVATION SUPPORT SYSTEMS SHALL BE DESIGNED AND CONSTRUCTED BY THE CONTRACTOR IN ACCORDANCE WITH CURRENT ENGINEERING PRACTICE, THE REQUIREMENTS OF THE CONTRACT DRAWINGS, AND APPLICABLE SPECIFICATIONS.
- A5. CONVENTIONAL CONSTRUCTION METHODS SHALL BE USED TO CONSTRUCT THE BELOW-GRADE SPACE. THE TEMPORARY EXCAVATION SUPPORT SYSTEM WALLS SHALL BE RESTRAINED BY TEMPORARY BRACING, AS NECESSARY, AS THE EXCAVATION IS CONDUCTED, AND THE PERMANENT SUBSTRUCTURE AND FOUNDATIONS SHALL BE CONSTRUCTED WITHIN THE TEMPORARY EXCAVATION SUPPORT SYSTEM.
- A6. DRIVING OR VIBRATING IS NOT PERMITTED TO INSTALL EXCAVATION SUPPORT WALL ELEMENTS.
- A7. THE CRITERIA ON SHEET B-5 AND THIS SHEET ARE MINIMUM CRITERIA. THE CONTRACTOR SHALL UTILIZE ADDITIONAL OR MORE CONSERVATIVE CRITERIA AS REQUIRED, TO COMPLETE THE WORK IN ACCORDANCE WITH THE CONTRACT REQUIREMENTS.
- A8. THE CONTRACTOR SHALL REVIEW THE DESIGN CRITERIA INCLUDED ON DRAWING B-6 AND CONDUCT WORK AS NECESSARY TO COMPLETE THE DESIGN. THE CONTRACTOR'S FINAL DESIGN AND ANY PROPOSED MODIFICATIONS WILL BE REVIEWED BY THE PROGRAM MANAGER/CONSTRUCTION MANAGER (PM/CM) IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONTRACT DRAWINGS AND APPLICABLE SPECIFICATIONS. THE CONTRACTOR SHALL SUBMIT FOR REVIEW BY THE PM/CM, COMPLETE COMPUTATIONS, CROSS-SECTIONS, CONSTRUCTION SCHEDULE AND SEQUENCE, AND WORKING DRAWINGS FOR TEMPORARY EXCAVATION SUPPORT SYSTEMS. THE DESIGN SHALL BE IN ACCORDANCE WITH THE MINIMUM CRITERIA SPECIFIED AND INDICATED ON THIS DRAWING AND GOOD ENGINEERING PRACTICE, AND WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. ALL COMPUTATIONS AND DESIGNS SHALL BE PREPARED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF RHODE ISLAND, RETAINED BY THE CONTRACTOR. THE PM'S/CM'S REVIEW WILL SOLELY BE TO DETERMINE COMPLIANCE WITH THE CONTRACT DOCUMENTS.
- A9. TEMPORARY EXCAVATION SUPPORT SYSTEMS SHALL BE ANALYZED AND DESIGNED FOR ALL CONDITIONS THAT CAN OCCUR DURING THE VARIOUS STAGES OF CONSTRUCTION. THESE CONDITIONS MAY INCLUDE: TEMPORARY OR PERMANENT ALTERATION OF THE SOILS, IN-SITU SOIL PROPERTIES CAUSED BY THE SELECTED METHODS OF CONSTRUCTION, INITIAL CANTILEVER CONDITION, INSTALLATION, RELOCATION, AND REMOVAL OF TEMPORARY BRACING, TIME RELATED EFFECTS, SOIL EXCAVATION BELOW BRACING ALREADY IN PLACE, SHRINKAGE OF CONCRETE, DEWATERING OF EXCAVATION, AND LOAD TRANSFER TO PERMANENT STRUCTURE.
- A10. ALL LATERAL PRESSURES ARE IN POUNDS PER SQUARE FOOT (PSF).
- A11. MAXIMUM LATERAL DEFORMATION ALONG FULL DEPTH OF THE EXCAVATION SHALL NOT EXCEED 0.0025 x EXCAVATION DEPTH OR 1/2", WHICHEVER IS GREATER.
- A12. IF THE LATERAL LOADING CONDITIONS ON OPPOSITE SIDES OF THE EXCAVATION ARE NOT EQUAL, THE TEMPORARY EXCAVATION SUPPORT SYSTEM DESIGN SHALL ACCOUNT FOR THE UNBALANCED LOADING. UNBALANCED LOADING COULD RESULT FROM UNEQUAL EXCAVATION LEVELS OR DIFFERENT LATERAL PRESSURE DISTRIBUTIONS AT THE PERIMETER OF THE SITE.

- A13. EXCAVATION AND BRACING RESTRICTIONS SHALL BE INCORPORATED INTO THE TEMPORARY EXCAVATION SUPPORT SYSTEM DESIGN AS FOLLOWS:
 - THE MAXIMUM VERTICAL DISTANCE BETWEEN THE LOWEST TEMPORARY BRACE AND THE EXCAVATION SUBGRADE SHALL NOT EXCEED 15 FT.
 - EXCAVATION FOR A LOWER SUBGRADE ELEVATION MAY NOT BEGIN UNTIL THE BRACE LEVEL ABOVE HAS BEEN INSTALLED.
- A14. THE MAXIMUM HEIGHT OF EXCAVATION FACE SHALL NOT EXCEED 4 FEET PRIOR TO INSTALLATION OF TEMPORARY LAGGING OR OTHER SHORING SYSTEM.
- A15. THE CONTRACTOR MAY BE REQUIRED TO ADJUST CONSTRUCTION OPERATIONS IF THE ENGINEER CONSIDERS THAT BASED ON INSTRUMENTATION READINGS, EXCESSIVE SETTLEMENTS, DEFORMATION AND/OR DEFLECTIONS OCCUR.

B. LATERAL DESIGN PRESSURES

- B1. MINIMUM DESIGN LOADING CONDITIONS SHALL BE DETERMINED BY ADDING TOGETHER THE LOADING DIAGRAMS SHOWN ON DRAWING B-5 FOR SOIL (E) AND WATER (W), WHERE APPLICABLE, AND THE COMBINATION OF APPLIED SURCHARGES (S). TRAFFIC AND CONSTRUCTION EQUIPMENT LOAD SHALL BE ASSUMED ON ANY SIDE OF THE WALL THAT IS ACCESSIBLE.
- B2. UNLESS INDICATED OTHERWISE, ALL LOADS FOR A GIVEN CONDITION MUST BE ADDED SO AS TO FORMULATE THE MAXIMUM TOTAL DESIGN LOADING.
- B3. LATERAL PRESSURE DUE TO TRAFFIC AND CONSTRUCTION EQUIPMENT IS BASED ON AN ASSUMED SURFACE SURCHARGE OF 600 PSF ACTING OVER A 20-FT. WIDE INFLUENCE AREA. THE CONTRACTOR SHALL DETERMINE IF THE 600 PSF VERTICAL SURCHARGE LOAD IS SUFFICIENT, AND SHALL MAKE ADDITIONAL ANALYSES FOR MORE CRITICAL CONSTRUCTION EQUIPMENT LOADING CONDITIONS, AND ACCOUNT FOR THESE IN THE DESIGN OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM. THE CONTRACTOR SHALL ACCOUNT FOR CRITICAL SURCHARGE LOADINGS OR OTHER LOADING CONDITIONS NOT DESCRIBED HEREIN IN DESIGN AND CONSTRUCTION, SUBJECT TO THE REVIEW OF THE PM, PRIOR TO THE APPLICATION OF THE LOADING.
- B4. FOR UNIFORM VERTICAL SURCHARGE LOADING, LATERAL PRESSURES ARE DETERMINED AT VARIOUS DEPTHS BELOW THE CORNER OF THE LOADED AREA. WHEN THE RECTANGULAR LOADED AREA IS LOCATED AT A DISTANCE BEHIND THE WALL, THE PRINCIPLE OF LOAD SUPERPOSITION SHALL BE USED TO DETERMINE LATERAL PRESSURES AGAINST THE WALL. REFER TO SOIL MECHANICS, BY LAMBE AND WHITMAN, PAGE 104, FOR AN EXAMPLE OF USING THE PRINCIPLE OF SUPERPOSITION OF LOADS.
- B5. PASSIVE EARTH PRESSURES SHALL BE COMPUTED USING RANKINE EARTH PRESSURE THEORY AND THE SOIL PROPERTIES INDICATED ON DRAWING B-5.
- B6. THE TEMPORARY EXCAVATION SUPPORT SYSTEM SHALL BE CONSIDERED TO BE SUBJECTED TO LATERAL SURCHARGE PRESSURES FROM LOADS ASSOCIATED WITH ADJACENT STRUCTURES AND GRADE INCREASES IF LOCATED WITHIN THE INFLUENCE ZONE. THE INFLUENCE ZONE IS DEFINED AS A 1H:1V LINE DRAWN FROM THE BOTTOM OF THE FINAL EXCAVATION LEVEL AT THE OUTSIDE FACE OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM UPWARD AND OUTWARD AWAY FROM THE SITE TOWARD THE ADJACENT STRUCTURE OR GRADE INCREASE.
- B7. VALUES OF P ARE IN POUNDS PER SQUARE FOOT PER LINEAR FOOT OF WALL (PSF/LF).
- B8. THE EXISTING GROUNDWATER LEVEL VARIES AND MUST BE DETERMINED ON A SITE SPECIFIC BASIS FOR EACH TEMPORARY EXCAVATION SUPPORT DESIGN. THE DESIGN MUST ACCOUNT FOR THE MOST CRITICAL LOADING CONDITION, INCLUDING THE MAXIMUM LOWERING OF THE GROUNDWATER TABLE AND THE MAXIMUM WATER INGRESS INTO THE EXCAVATION. REFER TO SPECIFICATIONS FOR GROUNDWATER CONTROL REQUIREMENTS.
- B9. STRESSES DUE TO TEMPERATURE FLUCTUATIONS SHALL BE TAKEN INTO ACCOUNT IN THE DESIGN OF BRACING MEMBERS AND LOADS RESULTING FROM FROZEN SOILS SHALL BE CONSIDERED IF APPROPRIATE.
- B10. IF AN IMPERMEABLE EXCAVATION SUPPORT WALL IS INSTALLED, THEN EFFECTIVE LATERAL EARTH PRESSURES PLUS HYDROSTATIC PRESSURE SHALL BE USED FOR DESIGN. IF A PERMEABLE WALL SYSTEM IS INSTALLED THEN TOTAL LATERAL EARTH PRESSURES MUST BE USED FOR DESIGN.

C. BRACING MEMBERS

- C1. DESIGN OF BRACING MEMBERS SHALL SATISFY THE MOST CRITICAL CONDITIONS ANTICIPATED DURING THE CONSTRUCTION SEQUENCE
- C2. TEMPORARY INTERNAL BRACING MEMBERS (STRUTS, RAKERS, CORNER BRACES, WALES) SHALL BE STRUCTURAL GRADE STEEL, REINFORCED CONCRETE, OR A COMBINATION. NO WOOD SHIMS SHALL BE USED.
- C3. TEMPORARY BRACING MEMBERS SHALL NOT BE EMBEDDED IN PERMANENT STRUCTURES.
- C4. TEMPORARY BRACING MEMBERS SHALL BE REMOVED AT AN APPROPRIATE STAGE OF CONSTRUCTION AND IN SUCH A MANNER AS TO AVOID IMPACT LOADING ON NEW AND EXISTING STRUCTURES AND/OR PIPELINES OR ON OTHER MEMBERS OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM.
- C5. ALL INTERNAL BRACING SHALL BE PRESTRESSED TO AT LEAST 50 PERCENT OF MAXIMUM DESIGN LOADS WHERE PASSIVE SOIL PRESSURE LIMIT PERMITS.


D. TEMPORARY EXCAVATION SUPPORT SYSTEM TOE STABILITY DESIGN

- D1. THE TOE OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM PRIMARY ELEMENTS SHALL EXTEND A SUFFICIENT DISTANCE BELOW THE BOTTOM OF THE EXCAVATION IN ORDER TO LIMIT MOVEMENT AND TO ENSURE BOTTOM STABILITY AND ADEQUATE VERTICAL LOAD CAPACITY.
- D2. THE TOE OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM WALL SHALL EXTEND A SUFFICIENT DISTANCE BELOW THE LOWEST EXCAVATION LEVEL TO PROVIDE VERTICAL LOAD CARRYING CAPACITY AND LIMIT HORIZONTAL MOVEMENT OF THE WALL. LOAD CARRYING CAPACITY OF THE WALL SHALL BE DETERMINED BY CONSIDERING BRACING SYSTEM LOADS. ONLY THE LENGTH OF THE WALL BELOW THE BOTTOM OF THE EXCAVATION SHALL BE CONSIDERED IN SKIN FRICTION AND/OR ADHESION CALCULATIONS.
- D3. EVALUATION OF THE REQUIRED TOE EMBEDMENT BELOW EXCAVATION SUBGRADE SHALL BE BASED ON THE NET RANKINE ACTIVE AND PASSIVE PRESSURES USING THE APPROPRIATE PRESSURE COEFFICIENTS PRESENTED IN THE SOIL PARAMETERS TABLE AND APPLICABLE SURCHARGE LOADING. FOR DETERMINING TOE EMBEDMENT, EITHER A FACTOR OF SAFETY EQUAL TO 1.5 SHALL BE APPLIED TO THE PASSIVE PRESSURE COEFFICIENT OR THE CALCULATED MINIMUM TOE EMBEDMENT SHALL BE INCREASED BY 20%.
- D4. IN SITUATIONS WHERE THE RETAINED SOIL IS NOT DEWATERED, THE DETERMINATION OF TOE PENETRATION MUST CONSIDER THE POTENTIAL FOR SEEPAGE GRADIENTS WHICH COULD CAUSE INSTABILITY AT THE BOTTOM OF THE EXCAVATION AND REDUCE THE STRENGTH OF SOILS AT THE TOE OF THE WALL.

E. CRITERIA FOR PROTECTION OF STRUCTURES

- E1. STRUCTURES INCLUDE EXISTING BUILDINGS, BRIDGES, UTILITIES, PAVEMENTS AND OTHER FACILITIES.
- E2. PROTECTION CRITERIA PRESENTED FOR FLEXIBLE WALL SYSTEMS ASSUME AVERAGE EXCAVATION AND BRACING PROCEDURES ARE UTILIZED.
- E3. EVALUATION OF PROTECTION REQUIREMENTS FOR STRUCTURES IS DEPENDENT ON MANY FACTORS, WHICH INCLUDE IMPLEMENTED CONSTRUCTION PROCEDURES AND DETAILS, MAGNITUDE AND TYPES OF MOVEMENT ANTICIPATED, SUBSURFACE CONDITIONS, AND PROXIMITY OF STRUCTURES TO THE EXCAVATION. AT LOCATIONS WHERE STRUCTURES ARE FOUNDED WITHIN THE ZONE OF INFLUENCE, AN EVALUATION OF PROTECTION REQUIREMENTS SHALL BE CONDUCTED BY THE CONTRACTOR ON A CASE BY CASE BASIS, CONSIDERING ALL RELEVANT FACTORS.
- E4. POSITIVE MEANS OF PROTECTION ARE DEFINED AS MEASURES WHICH MAY BE TAKEN TO CONTROL GROUND MOVEMENTS TO WITHIN ACCEPTABLE LIMITS OR, MEASURES WHICH PROVIDE ADDITIONAL SUPPORT FOR AFFECTED STRUCTURES. EVALUATION OF PROTECTION REQUIREMENTS FOR STRUCTURES GENERALLY BEGINS WITH SELECTING AND IMPLEMENTING EARTH SUPPORT, EXCAVATION AND BRACING TECHNIQUES TO MINIMIZE GROUND MOVEMENTS. IF ANTICIPATED GROUND MOVEMENTS ARE STILL EXPECTED TO EXCEED ACCEPTABLE LIMITS, THEN INDIRECT OR DIRECT STRUCTURE PROTECTION MEASURES SHALL BE IMPLEMENTED BY THE CONTRACTOR ON A CASE BY CASE BASIS. INDIRECT PROTECTION MEASURES INCLUDE SUCH PROCEDURES AS PROVIDING A STIFFER RETAINING SYSTEM, COMPACTION GROUTING OR SLAB/FOOTING JACKING. DIRECT PROTECTION MEASURES INCLUDE SUCH PROCEDURES AS STANDARD UNDERPINNING PITS.
- E5. THE CONTRACTOR SHALL CONSIDER THE EFFECTS OF VIBRATIONS ON ADJACENT STRUCTURES FROM INSTALLATION OF THE TEMPORARY EARTH SUPPORT SYSTEM.
- E6. REFER TO SPECIFICATION SECTION 02295 FOR GEOTECHNICAL INSTRUMENTATION RESPONSE LEVELS AND READING FREQUENCIES.

PROTECTION CRITERIA




LEGEND

- ZONE OF INFLUENCE: DEFINES A ZONE WITHIN WHICH SOIL MOVEMENTS ARE EXPECTED TO OCCUR AS A RESULT OF CONSTRUCTION. PROTECTION OF STRUCTURES FOUNDED OR LOCATED WITHIN THIS ZONE SHALL BE CONSIDERED BY THE CONTRACTOR.
- PROTECTION ZONE A: STRUCTURES WHICH ARE FOUNDED OR LOCATED WITHIN THIS ZONE GENERALLY WILL REQUIRE SOME POSITIVE MEANS OF PROTECTION. REFER TO NOTE E.4 FOR DEFINITION OF POSITIVE MEANS OF PROTECTION.
- PROTECTION ZONE B: STRUCTURES WHICH ARE FOUNDED OR LOCATED WITHIN THIS ZONE GENERALLY WILL NOT REQUIRE PROTECTION, UNLESS THE STRUCTURES ARE PARTICULARLY SENSITIVE TO MOVEMENTS, OR SUBSURFACE SOILS ARE SENSITIVE TO CONSTRUCTION VIBRATION.

SCALE	WARNING	DESIGNED <u>K. OHARA</u>	90% DESIGN PHASE - APRIL 2021			NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM	NBC CONTRACT NO 308.05C GEOTECHNICAL	SHEET B-6
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DRAWN <u>D. NOWAK</u>	NOT FOR CONSTRUCTION This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.					
REV	DATE	BY	DESCRIPTION					


OFFSET REQUIRED
CONSIDERING INSTALLATION
TOLERANCES (SEE NOTE 3)



SECANT PILE SHAFT PLAN AT GROUND LEVEL

SCALE: 1/4" = 1'-0"

OFFSET REQUIRED
CONSIDERING INSTALLATION
TOLERANCES (SEE NOTE 3)




SECANT PILE SHAFT PLAN AT MICROTUNNEL SPRINGLINE

SCALE: 1/4" = 1'-0"

NOTES

- MTBM LAUNCHING SHAFTS AT MH-217-6 AND MH-217-7 SHALL BE CONSTRUCTED USING THE SECANT PILE WALL METHOD AND PROVIDE A MINIMUM 20-FOOT CLEAR OF INSIDE DIAMETER CONSIDERING INSTALLATION TOLERANCES.
- THIS DRAWING DEPICTS A REFERENCE DESIGN FOR WHICH THE CONTRACTOR SHALL DEVELOP TO A FINAL DESIGN. THE CONTRACTOR'S FINAL DESIGN SHALL INCORPORATE DESIGN AND CONSTRUCTION REQUIREMENTS SPECIFIED HERE AND ELSEWHERE IN THE CONTRACT DOCUMENTS.
- REFERENCE DESIGN ASSUMPTIONS:
 - PLAIN CONCRETE DESIGN IN ACCORDANCE WITH ACI-318-19
 - $F'_c = 4000$ PSI
- INSTALLATION TOLERANCES:
 - IN-PLAN LOCATION: 1/2-INCH MAXIMUM
 - OUT-OF-VERTICALITY: 0.5% MAXIMUM
- DESIGN PRESSURES:
 - AT REST EARTH PRESSURES
 - GROUND WATER LEVEL AT EL. 15.0
 - SURCHARGE (BALANCED AND UNBALANCED)
- SHAFT DESIGN DOES NOT CONSIDER MTBM JACKING LOADS OR REINFORCEMENT AT MTBM PENETRATION LOCATIONS
- CONTRACTOR TO DESIGN AND PROVIDE SOFT EYES IN SHAFT WALL AT MTBM PENETRATIONS AND REINFORCEMENT NECESSARY TO SUPPORT SAME PENETRATIONS THROUGH THE SHAFT WALL.
- CONTRACTOR TO DESIGN SHAFT TO ACCOMMODATE ANTICIPATED MTBM JACKING LOADS.
- CONTRACTOR TO DESIGN AND PROVIDE A REINFORCED CONCRETE SHAFT CAPPING BEAM.
- REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- SHAFT AT MH-217-6 TO BE USED FOR TWO MTBM LAUNCHES
- SHAFT AT MH-217-7 TO BE USED FOR ONE MTBM LAUNCH TO RECEIVING PIT NEAR STA. 16+70; AND TO RECEIVE ONE MTBM LAUNCHED FROM SHAFT AT MH-217-6.

SHAFT



BOTTOM OF SECANT WALL TO BE A MINIMUM OF 3 FEET BELOW BOTTOM OF EXCAVATION OR EMBEDDED 3 FEET INTO MODERATELY WEATHERED TO FRESH BEDROCK AS DEFINED BY ISAM WEATHERING CLASSIFICATION SYSTEM WHICHEVER IS DEEPER.

A SECTION
GT-008 SCALE: N.T.S.

REV	DATE	BY	DESCRIPTION


SCALE	WARNING
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	D.NOWAK
DRAWN	D.NOWAK
CHECKED	T.HENNINGS

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM


NBC CONTRACT NO 308.05C
GEOTECHNICAL

OF-217 CONSOLIDATION CONDUIT
SECANT PILE SHAFT REFERENCE DESIGN


BY: JAMIE PAYNE

PLOT DATE: Thursday, April 1, 2021 8:27:07 AM

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Traffic Management\TMP 1.dwg



SIDEWALK CLOSURE DETAIL




GENERAL SHEET NOTES

SHEET KEYNOTES

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE
NO SCALE



DESIGNED H. PERALTA
DRAWN T. JOUBERT
CHECKED J. D'ALELIO

90% DESIGN PHASE - APRIL 2021
NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.





NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM
Stantec **PARE**

NBC CONTRACT NO 308.05C
TRAFFIC
OF-217 CONSOLIDATION CONDUIT
TRAFFIC MANAGEMENT PLAN

SHEET
T-1
195130227

SIDEWALK CLOSURE SIGN LEGEND





SIGN	DIMENSIONS	QUANTITY
	R9-11a 24 in. x 12 in.	2



TEMPORARY TRAFFIC CONTROL GENERAL NOTES:

- ALL MAINTENANCE AND PROTECTION OF TRAFFIC CONTROL SETUPS, SIGNS, CHANNELIZING DEVICES, ETC., SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION.
- ALL SIGN MOUNTINGS FOR TEMPORARY AND CONSTRUCTION SIGNS SHALL BE IN ACCORDANCE WITH THE R.I.D.O.T STANDARD SPECIFICATIONS, LATEST EDITION.
- THE CONTRACTOR SHALL COVER ALL EXISTING AND/OR TEMPORARY SIGNS THAT ARE NOT RELEVANT TO THE TRAFFIC CONTROL REQUIRED DURING ANY PARTICULAR STAGE OF THE CONTRACT.
- ADVANCE FLAGPERSON SIGNS (W20-7A) SHALL BE USED IN ADVANCE OF ANY POINT AT WHICH A FLAGPERSON OR A POLICE OFFICER HAS BEEN STATIONED TO CONTROL TRAFFIC. WHEN NEEDED, AN APPROPRIATE DISTANCE MESSAGE MAY BE DISPLAYED ON A SUPPLEMENTAL PLAQUE (24"x18") BELOW THE FLAGPERSON SYMBOL SIGN. THE SIGN SHALL BE PROMPTLY REMOVED OR COVERED WHENEVER THE FLAGPERSON IS NOT AT THE STATION.
- POLICE OFFICERS (AND NOT FLAGPERSONS) SHALL BE UTILIZED WHEN WORK WILL IMPACT SIGNALIZED INTERSECTIONS AND LIMITED ACCESS HIGHWAYS.
- POLYETHYLENE DRUMS SHALL BE UTILIZED AS A CHANNELIZING DEVICE WHEN A TRAFFIC CONTROL SET-UP IS TO REMAIN BEYOND WORKING HOURS WHEN NO WORKERS ARE PRESENT. CONES SHALL BE UTILIZED WHEN A TRAFFIC CONTROL SET-UP IS TO REMAIN ONLY DURING WORKING HOURS AND IS SUBSEQUENTLY BROKEN DOWN AT THE END OF THE WORKDAY.
- ARROW PANELS SHALL BE SET IN THE FLASHING FOUR CORNERS CAUTION MODE UNLESS UTILIZED FOR A MERGING TAPER. ARROW PANELS SET IN THE FLASHING MODE SHALL NOT BE UTILIZED FOR LANE SHIFTS.
- TEMPORARY CONSTRUCTION SIGNS AND OTHER WORKZONE TRAFFIC CONTROL DEVICES THAT ARE DAMAGED OR REQUIRE RELOCATION SHALL BE REPLACED AND/OR RELOCATED UNDER THE APPROPRIATE PAY ITEM.
- THE PRIVATE VEHICLE OF CONSTRUCTION WORKERS SHALL NOT BE PARKED ON THE TRAVEL LANES OR SHOULDERS. THEY MAY BE PARKED WITHIN THE STATE AND/OR CITY RIGHT-OF-WAY ONLY IN AREAS 30' BEYOND THE OUTSIDE EDGE OF THE TRAVEL LANES AND/OR IN AREAS APPROVED BY THE ENGINEER.
- TEMPORARY CONSTRUCTION SIGNS AND OTHER TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE INSTALLED PRIOR TO THE START OF WORK IN ANY AREA OPEN TO TRAFFIC, AND SHALL BE REMOVED AS SOON AS PRACTICAL WHEN THEY ARE NO LONGER APPROPRIATE.
- THE INTENDED VEHICLE PATHS THROUGH EACH WORK ZONE SHALL BE CLEARLY MARKED AT ALL TIMES. WATERBORNE PAVEMENT MARKINGS SHALL BE INSTALLED BEFORE THE END OF THE WORK SHIFT ON ALL COLD-PLANED AND NEW ROADWAY SURFACES THAT WILL BE OPENED TO TRAFFIC AT THE END OF THE SHIFT.
- THE CONTRACTOR SHALL NOTIFY EACH ABUTTER AT LEAST 48 HOURS IN ADVANCE OF THE START OF ANY WORK THAT WILL REQUIRE TEMPORARY INTERFERENCE WITH OR CLOSURE OF ACCESS.
- ONE SIDEWALK SHALL REMAIN OPEN AT ALL TIMES ALONG ROOSEVELT AVENUE EXTENSION AND TAFT STREET.

KEY PLAN



BY: JAMIE PAYNE

PLOT DATE: Thursday, April 1, 2021 8:27:50 AM

DWG FILE: J:\6412 NBC Consolidation Conduits\Drawing Files\Traffic Management\TMP DETAILS.dwg

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	WARNING
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	H. PERALTA
DRAWN	T. JOUBERT
CHECKED	J. D'ALELIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




BY: JAMIE PAYNE


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet Set\PAWT_III-5_DIVERSION STRUCTURES_PLANS\0561TEDN\kingsday_April 1, 2021 8:30:23 AM

GENERAL SHEET NOTES

1. VERTICAL DATUM FOR PROJECT IS NGVD29.




SITE PLAN VIEW
SCALE: 1" = 4'-0"




PLAN VIEW
SCALE: 1/4" = 1'-0"

NOTE:
THE FULL CIRCUMFERENCE OF THE EXISTING 42" SEWER SHALL BE COATED WITH A MONOLITHIC GEOPOLYMER LINING TO A DISTANCE OF 20 LF FROM THE INTERIOR FACE OF THE PROPOSED STRUCTURE



A SECTION
SCALE: 1/4" = 1'-0"

NOTE:
THE FULL CIRCUMFERENCE OF THE EXISTING 42" SEWER SHALL BE COATED WITH A MONOLITHIC GEOPOLYMER LINING TO A DISTANCE OF 20 LF FROM THE INTERIOR FACE OF THE PROPOSED STRUCTURE



B SECTION
SCALE: 1/4" = 1'-0"

DAMP PROOF COATING ON EXTERIOR. IF WITHIN SEASONAL HIGH GROUNDWATER PROVIDE WATERPROOF COATING ON EXTERIOR.

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 RELOCATION STRUCTURE
PLAN AND SECTIONS


SHEET
S-1
195130227

GENERAL SHEET NOTES


1. VERTICAL DATUM FOR PROJECT IS NGVD29.
2. DETAIL TYPICAL AT PRECAST/C.I.P. WALL INTERFACE. ROUGHEN TO 1/4" MIN.




SITE PLAN VIEW
SCALE: 1" = 4'-0"




PLAN VIEW
SCALE: 1/4" = 1'-0"



A SECTION
S-2 SCALE: 1/4" = 1'-0"



X SECTION
S-2 SCALE: 1/2" = 1'-0"



B SECTION
S-2 SCALE: 1/3" = 1'-0"

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_III-A-5_DIVERSION STRUCTURES_PLAIN\05B6TED\Drawings.dwg, April 1, 2021 8:31:37 AM

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESSIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM




NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 DIVERSION STRUCTURE
PLAN AND SECTIONS

SHEET
S-2
195130227


GENERAL SHEET NOTES

1. VERTICAL DATUM FOR PROJECT IS NGVD29.




SITE PLAN VIEW
SCALE: 1" = 4'-0"

NOTE: THE WORK AT THE OUTFALL IS ABOVE THE MEAN HIGH WATER LINE AND WILL BE IMPACTED BY THE TIDES. CONTRACTOR SHALL PLAN AND PROTECT THE WORK ACCORDINGLY.



A SECTION
S-3 SCALE: 1/2" = 1'-0"



B SECTION
S-3 SCALE: 1/2" = 1'-0"

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawings\Files\Civil\Sheet Set\PAWT_III-A-5_DIVERSION STRUCTURES_PLAIN\05B6TED\Drawings.dwg, April 1, 2021 8:32:32 AM

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALELIO

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM



NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 REVETMENT
PLAN AND SECTION


SHEET
S-3
195130227

BY: JAMIE PAYNE


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\SR\PAVT_JIA-5_DIVERSION STRUCTURE DE FLOUS(DAVE). Thursday, April 1, 2021 8:32:37 AM

GENERAL SHEET NOTES


- 1. VERTICAL DATUM FOR PROJECT IS NGVD29.




FLOATABLES SCREEN
SCALE: 1" = 1'-0"




A X-X DETAIL
SCALE: 3" = 1'-0"



TOP SUPPORT
SCALE: 3" = 1'-0"



A X-X DETAIL
SCALE: 3" = 1'-0"



A X-X DETAIL
SCALE: 3" = 1'-0"

REV	DATE	BY	DESCRIPTION


SCALE	WARNING
SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	L. TSANG
DRAWN	B. NELSON
CHECKED	T. WARZECKI

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.













NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 DIVERSION STRUCTURE
FLOATABLE SCREEN DETAILS

SINGLE LINE DIAGRAM, SCHEMATIC DIAGRAM SYMBOLOLOGY AND PLAN SYMBOLOLOGY

GENERAL ELECTRICAL NOTES



- ALL RACEWAYS AND EQUIPMENT SHALL BE INSTALLED AND GROUNDED IN ACCORDANCE WITH THE 2020 EDITION OF THE NATIONAL ELECTRICAL CODE AND APPLICABLE LOCAL CODES.
- THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF CONDUIT ENTRANCES OF ALL EQUIPMENT AGAINST APPROVED SHOP DRAWINGS BEFORE STUBBING UP CONDUITS.
- CONDUIT RUNS ARE SHOWN DIAGRAMMATICALLY ONLY AND SHALL BE INSTALLED IN A MANNER TO PREVENT CONFLICTS WITH EQUIPMENT OR STRUCTURAL CONDITIONS. EXPOSED CONDUIT SHALL BE INSTALLED PARALLEL OR PERPENDICULAR TO BEAMS AND WALLS. REFER TO SPECIFICATION SECTION 16130.
- IN THE EVENT OF INTERFERENCE BETWEEN ELECTRICAL EQUIPMENT SHOWN ON THE DRAWINGS AND OTHER EQUIPMENT, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN WRITING AND THE ENGINEER SHALL APPROVE PROPOSED CHANGES BEFORE THEY ARE MADE.
- THE WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE DETAILS WHETHER OR NOT THEY ARE REFERENCED ON THE DRAWINGS.
- ALL CONDUIT RUNS CROSSING EXPANSION JOINTS SHALL HAVE EXPANSION OR EXPANSION AND DEFLECTION TYPE FITTINGS. FOR LOCATIONS OF EXPANSION JOINTS, REFER TO THE STRUCTURAL DWGS.
- CONDUITS SHALL BE TERMINATED SO AS TO PERMIT NEAT CONNECTION TO MOTORS AND OTHER EQUIPMENT.
- CONDUITS FOR FUTURE EQUIPMENT OR EXTENSIONS SHALL BE TERMINATED AS INDICATED OR AS SPECIFIED.
- ELECTRICAL CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING THE PROJECT TO VERIFY THE SCOPE OF WORK WITH FIELD CONDITIONS.


BY: MICHAEL COTTIER

PLOT DATE: Thursday, March 18, 2021 3:09:42 PM

DWG FILE: C:\pwworkdir\052096\052096\DWG\217 Electrical - 2015.dwg

REV	DATE	BY	DESCRIPTION

SCALE
NO SCALE



DESIGNED M.COTTIER
DRAWN R.BEAUVAIS
CHECKED

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NBC CONTRACT NO 308.05C
GENERAL ELECTRICAL

NOTES & SYMBOLS

SHEET
GE-1
195130227

ELECTRICAL ABBREVIATIONS

A AMPERE, AUTOMATIC
 AC ALTERNATING CURRENT
 AF CIRCUIT BREAKER FRAME SIZE
 AM AMMETER
 ANN ANNUNCIATOR
 AS ADJUSTABLE SPEED
 AT AMPERE TRIP
 ATS AUTOMATIC TRANSFER SWITCH
 AUTO AUTOMATIC
 AWG AMERICAN WIRE GAUGE

BATT BATTERY
 BC BARE COPPER
 BKR BREAKER

C CONDUIT, NUMBERS FOLLOWING INDICATE WIRE QUANTITIES AND WIRE GAUGE SIZES
 CAP CAPACITOR
 CB CIRCUIT BREAKER
 CKT CIRCUIT
 CLF CURRENT LIMITING FUSE
 COM COMMON
 COMM COMMUNICATIONS
 COMP COMPARTMENT
 CP CONTROL PANEL
 CPT CONTROL POWER TRANSFORMER
 CR CONTROL RELAY, CARD READER
 CT CURRENT TRANSFORMER

DCS DISTRIBUTED CONTROL SYSTEM
 DISC DISCONNECT
 DISTR DISTRIBUTION
 DPDT DOUBLE POLE DOUBLE THROW
 DPST DOUBLE POLE SINGLE THROW

E EMERGENCY
 EMT ELECTRICAL METALLIC TUBING
 ENCL ENCLOSURE
 ETM ELAPSED TIME METER

F FREQUENCY, FUSE, FIXED
 FDR FEEDER
 FLA FULL LOAD AMPS
 FLUOR FLUORESCENT
 FM FREQUENCY METER
 FO FIBER OPTIC
 FVR FULL VOLTAGE REVERSING
 FVNR FULL VOLTAGE NON-REVERSING

GEN GENERATOR
 GFCI GROUND FAULT CIRCUIT INTERRUPTER
 GND GROUND

H HAND
 HD HEAT DETECTOR
 HH HAND HOLE
 HID HIGH INTENSITY DISCHARGE
 HOA HAND-OFF-AUTOMATIC
 HPS HIGH PRESSURE SODIUM
 HS HAND SWITCH
 HZ HERTZ

IMC INTERMEDIATE METALLIC CONDUIT
 INCAND INCANDESCENT
 IND INDICATION
 INST INSTANTANEOUS
 I/O INPUT/OUTPUT
 IS INTRINSICALLY SAFE
 Isc SHORT CIRCUIT CURRENT, AMPS
 ISO ISOLATION

J,JB JUNCTION BOX

KA KILO AMPERES
 KAIC KILO AMP INTERRUPTING CURRENT
 KCML KILO CIRCULAR MILS
 KVA KILOVOLT AMPERE

L LOCAL
 LCP LOCAL CONTROL PANEL
 LCS LOCAL CONTROL STATION
 LIT LEVEL INDICATING TRANSMITTER
 LOC LOCAL
 LOR LOCAL-OFF-REMOTE
 LOS LOCKOUT STOP PUSHBUTTON
 LP LIGHTING PANEL
 LRA LOCKED ROTOR AMPS
 LS LEVEL SWITCH
 LTG LIGHTING
 LTS LIGHTS

M MOTOR CONTACTOR COIL
 mA MILLIAMPERE
 MAINT MAINTENANCE
 MCP MOTOR CIRCUIT PROTECTOR
 MLO MAIN LUGS ONLY
 MOV MOTOR OPERATED VALVE
 MS MANUAL MOTOR STARTER
 MTS MANUAL TRANSFER SWITCH

NEUT NEUTRAL
 NP NAMEPLATE

O OPEN, OFF
 OL OVERLOAD

PA PUBLIC ADDRESS
 PB PUSHBUTTON, PULLBOX
 PC PHOTOCCELL
 PCM PROCESS CONTROL MODULE
 PF POWER FACTOR
 PFM POWER FACTOR METER
 PH PHASE
 PL PILOT LIGHT
 PNLBD PANELBOARD
 PP POWER PANELBOARD
 POS POSITION
 POT POTENTIOMETER
 PRI PRIMARY
 PT POTENTIAL TRANSFORMER
 PTZ PAN-TILT-ZOOM
 PWR POWER

R REMOTE
 RECPT RECEPTACLE
 RGS RIGID GALVANIZED STEEL
 RMS ROOT MEAN SQUARE
 RTU REMOTE TERMINAL UNIT
 RVSS REDUCED VOLTAGE SOLID STATE

SEL SW SELECTOR SWITCH
 SEQ SEQUENCE
 SHLD SHIELDED
 SIG SIGNAL
 SP SPARE
 SP HTR SPACE HEATER
 SPDT SINGLE POLE DOUBLE THROW
 SPST SINGLE POLE SINGLE THROW
 SS 316 STAINLESS STEEL
 SSM SOLID STATE METER
 SSMP SOLID STATE MOTOR PROTECTOR
 ST, SH SHUNT TRIP
 STR STARTER
 SSTU SOLID STATE TRIP UNIT
 SW SWITCH
 SWBD SWITCHBOARD
 SWGR SWITCHGEAR

TACH TACHOMETER
 TB TERMINAL BOX
 TERM TERMINAL
 TM REPEAT CYCLE TIMER
 TD TIME DELAY RELAY
 TS TEMPERATURE SWITCH
 TSP TWISTED SHIELDED PAIR

UPS UNINTERRUPTIBLE POWER SUPPLY

V VOLTAGE, VOLTS
 VA VOLT AMPERE
 VAR VOLT AMPERE REACTIVE
 VFD VARIABLE FREQUENCY DRIVE
 VM VOLTMETER
 VP VAPOR PROOF

W WATTS, WIRE
 WM WATT METER
 WP WEATHERPROOF

XFMR TRANSFORMER
 XMTR TRANSMITTER
 XP EXPLOSION PROOF

BY: MICHAEL COTTER

PLOT DATE: Thursday, March 18, 2021 3:09:59 PM

DWG FILE: C:\pwworkdir\05209686\OF-217\Electrical - 2013.dwg

REV	DATE	BY	DESCRIPTION

SCALE
NO SCALE

WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED M.COTTER
 DRAWN R.BEAUVAIS
 CHECKED


90% DESIGN PHASE - APRIL 2021
 NOT FOR CONSTRUCTION
 This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NBC CONTRACT NO 308.05C
 ELECTRICAL
 ABBREVIATIONS

SHEET
 GE-2
 195130227

DWG FILE: C:\pwworkdir\05209686\OF-217 Electrical - 2013.dwg
 PLOT DATE: Tuesday, March 23, 2021 1:11:54 PM
 BY: MICHAEL COTTIER




SITE PLAN
SCALE: 1" = 20'



OF-217 DIVERSION STRUCTURE
SCALE: 1/4" = 1'-0"

DUCT / CABLE SCHEDULE				
DUCT NO.	SIZE	CONDUCTORS	FROM	TO
D1	2"	PULL STRING - SERVICE WIRING PROVIDED BY OTHERS	UTILITY POLE	STUB UP NEXT TO ELECTRICAL ENCLOSURE
D2	2"	PULL STRING - SPARE CONDUIT	UTILITY POLE	STUB UP NEXT TO ELECTRICAL ENCLOSURE
D3	3"	PULL STRING - CABLE BY VENDER PROVIDED BY OTHERS	ELECTRICAL ENCLOSURE	OF-217 DIVERSION STRUCTURE LEVEL TRANSMITTER LOCATION




SECTION A-A

SECTION B-B

- NOTES:**
- BACKFILL DUCT BANK IN LAYERS AND MANUALLY TAMP OR "PUDDLE" CONCRETE FILL. PROVIDE RED DUCT BANK MARKER TAPES, READING "CAUTION - ELECTRICAL LINES BELOW", OVER ENTIRE LENGTH OF DUCTLINE. LOCATE TAPES 12 INCHES BELOW GRADE. PROVIDE A TAPE FOR EVERY 12 INCHES OF WIDTH OF DUCTLINE.
 - A MINIMUM OF 12' SEPARATION SHALL BE KEPT BETWEEN DUCT BANK SECTIONS WITHIN SAME TRENCH.
 - FOR REINFORCING REQUIREMENTS SEE CONCRETE SPECIFICATIONS.

DUCTBANK SECTIONS
NO SCALE



GENERAL SHEET NOTES

- NONE

SHEET KEYNOTES

- 60"x36"x18", NEMA 3R STAINLESS STEEL TRAFFIC BOX ELECTRICAL ENCLOSURE MOUNTED ON CONCRETE BASE, REFER TO DRAWING E-2 DETAIL 3.
- ELECTRIC HANDHOLE, REFER DRAWING E-2 DETAIL 6.

REV	DATE	BY	DESCRIPTION

SCALE: AS SHOWN

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: M. COTTIER
DRAWN: R. BEAUVAIS
CHECKED: _____

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.




NBC CONTRACT NO 308.05C
ELECTRICAL

SITE PLAN, DUCTBANK SECTIONS, AND OF-217 DIVERSION STRUCTURE PLAN


BY: MICHAEL COTTER

PLOT DATE: Thursday, March 18, 2021 3:26:22 PM


DWG FILE: C:\pwworkdir\05209686\OF-217 Electrical - 2013.dwg




1 CONDUIT RISER DIAGRAM
NOT TO SCALE




4 CONDUIT THROUGH STRUCTURE WALL DETAIL
NOT TO SCALE



2 ELECTRICAL ENCLOSURE INTERIOR LAYOUT
SCALE: 1" = 1'-0"




5 SERVICE RISER POLE
NOT TO SCALE




- NOTES:
- FOR REINFORCING REQUIREMENTS SEE CONCRETE SPECIFICATIONS.
 - EYS SEAL FITTINGS ARE NOT TO BE FILLED, INSTALLATION OF CABLE AND SEALANT WILL BE BY OTHERS.
 - SEAL AND CAP THE ENDS OF CONDUITS.

3 ELECTRICAL ENCLOSURE BASE DETAIL
NOT TO SCALE



PLAN VIEW



SECTION A-A

- NOTES:
- CHIMNEY HEIGHT IS KEPT TO MINIMUM TO FACILITATE WIRE PULLING IN HANDHOLE FROM ABOVE GRADE
 - CONCRETE TO HAVE MINIMUM STRENGTH OF 5,000 PSI AT 28 DAYS
 - PROVIDE HANDHOLE FRAME, RING AND COVER.
 - REFER TO DUCTBANK SECTIONS FOR THE REQUIRED NUMBER OF CONDUIT ENTRANCES. PROVIDE CONDUIT ENTRY SPACE ON NON-USED SIDES FOR A MINIMUM (4) 4" FUTURE CONDUITS.
 - REFER TO SITE PLAN FOR HANDHOLE SIDES CONDUITS ARE ENTERING.

6 ELECTRIC HANDHOLE DETAIL
NOT TO SCALE

REV	DATE	BY	DESCRIPTION

SCALE	WARNING
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED M. COTTER
DRAWN R. BEAUVAIS
CHECKED

90% DESIGN PHASE - APRIL 2021

NOT FOR CONSTRUCTION

This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec PARE

NBC CONTRACT NO 308.05C
ELECTRICAL
CONDUIT RISER DIAGRAM
AND DETAILS

SHEET
E-2
195130227