


NARRAGANSETT BAY COMMISSION

PHASE III COMBINED SEWER OVERFLOW PROGRAM
OF-217 CONSOLIDATION CONDUIT

CONTRACT NO. 308.05C

CONFORMED DOCUMENTS
OCTOBER 2021



STATE OF RHODE ISLAND

DANIEL J. MCKEE _____ GOVERNOR



RHODE ISLAND
INFRASTRUCTURE BANK

VAHID OWNJAZAYERI _____ CHAIRMAN

JEFFREY R. DIEHL _____ EXECUTIVE DIRECTOR
AND CEO




VINCENT J. MESOLELLA JR. _____ CHAIRMAN

LAURIE A. HORRIDGE _____ EXECUTIVE DIRECTOR

KATHRYN KELLY, P.E. _____ CSO PROGRAM MANAGER

DAVID C. BOWEN, P.E. _____ ENGINEERING
MANAGER


PROGRAM MANAGEMENT TEAM



DESIGN TEAM



www.BETA-Inc.com



LIST OF DRAWINGS

GENERAL

- G-1 LIST OF DRAWINGS
- G-2 LOCATION AND VICINITY MAP
- G-3 SYMBOLS
- G-4 ABBREVIATIONS

CIVIL

- GC-1 NOTES
- GC-2 SYMBOLS
- C-1 LIMITS OF WORK - TOWN LANDING SITE
- C-2 LIMITS OF WORK - TIDEWATER SITE
- C-3 CONSOLIDATION CONDUIT PLAN AND PROFILE I: STA 0+00 - 4+00
- C-4 CONSOLIDATION CONDUIT PLAN AND PROFILE II: STA 4+00 - 7+50
- C-5 CONSOLIDATION CONDUIT PLAN AND PROFILE III: STA 7+50 - 12+00
- C-6 CONSOLIDATION CONDUIT PLAN AND PROFILE IV: STA 12+00 - 16+00
- C-7 CONSOLIDATION CONDUIT PLAN AND PROFILE V: STA 16+00 - 18+88
- C-8 OF-217 OUTFALL PLAN AND PROFILE VI: STA 0+00 - 4+46
- C-9 WATER RELOCATION PLAN
- C-10 CIVIL DETAILS I
- C-11 CIVIL DETAILS II
- C-12 CIVIL DETAILS III
- C-13 CIVIL DETAILS IV
- C-14 CIVIL DETAILS V
- C-15 CIVIL DETAILS VI
- C-16 CIVIL DETAILS VII
- C-17 CIVIL DETAILS VIII
- C-18 CIVIL DETAILS IX
- C-19 CIVIL DETAILS X

GEOTECHNICAL

- B-1 INSTRUMENTATION PLAN STA. 0+00 - 8+00
- B-2 INSTRUMENTATION PLAN STA. 8+00 - 16+00
- B-3 INSTRUMENTATION PLAN STA. 16+00 - 18+88, STA. 0+00 - 4+46
- B-4 INSTRUMENTATION DETAILS
- B-5 MINIMUM DESIGN CRITERIA FOR EXCAVATION SUPPORT
- B-6 NOTES FOR ANALYSIS AND DESIGN
- B-7 SECANT PILE SHAFT REFERENCE DESIGN

TRAFFIC

- T-1 TEMPORARY TRAFFIC CONTROL PLAN
- T-2 TEMPORARY TRAFFIC CONTROL PLAN
- T-3 TEMPORARY TRAFFIC CONTROL DETAILS


STRUCTURAL

- S-1 OF-217 RELOCATION STRUCTURE PLAN AND SECTIONS
- S-2 OF-217 DIVERSION STRUCTURE PLAN AND SECTIONS
- S-3 OF-217 REVETMENT PLAN AND SECTION
- S-4 OF-217 DIVERSION STRUCTURE FLOATABLE SCREEN DETAILS
- S-5 STRUCTURAL DETAILS I

ELECTRICAL


- GE-1 NOTES & SYMBOLS
- GE-2 ABBREVIATIONS
- E-1 SITE PLAN, DUCTBANK SECTIONS, AND OF-217 DIVERSION STRUCTURE PLAN
- E-2 CONDUIT RISER DIAGRAM AND DETAILS

DWG FILE: J:\6412 NBC CSD Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVVT_IIA-4_IIA-5_LIST_OF_DRAWINGS.dwg PLOT DATE: Tuesday, July 27, 2021 9:49:49 AM BY: JAMIE PAYNE




REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE
NO SCALE



DESIGNED C. CRONIN
DRAWN J. PAYNE
CHECKED J. D'ALELIO

FINAL DESIGN - JULY 2021




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
GENERAL
OF-217 CONSOLIDATION CONDUIT
LIST OF DRAWINGS


SHEET
G-1
195130227

DWG FILE: J:\6412 NBC Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAWT_IIA-4_IIA-5_LOCATION_MAP.dwg PLOT DATE: Tuesday, July 27, 2021 9:49:54 AM BY: JAMIE PAYNE


KEY PLAN



PAWTUCKET, RI



LOCATION MAP



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS


SCALE
NO SCALE

WARNING
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN J. PAYNE
CHECKED J. D'ALELIO

FINAL DESIGN PHASE - JULY 2021

NOT FOR CONSTRUCTION
This document is an interim document and not suitable for construction. As an interim document, it may contain data that is potentially inaccurate or incomplete and is not to be relied upon without the express written consent of the preparer.



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
GENERAL

OF-217 CONSOLIDATION CONDUIT
LOCATION AND VICINITY MAP

SHEET
G-2
195130227

BY: JAMIE PAYNE

PLOT DATE: Tuesday, July 27, 2021 9:50:11 AM

DWG FILE: J:\6412 NBC CSD Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVWT_IIA-5_GENERAL.dwg




GENERAL SYMBOLOGY	
	NEW CONSTRUCTION
	EXISTING (SCREENED)
	FUTURE (PHANTOM)
	EXISTING TO BE REMOVED OR DEMOLISHED

MATERIAL SYMBOLOGY

	CONCRETE (PLAN AND SECTION)
	GROUT OR SAND (PLAN AND SECTION)
	BRICK (PLAN AND SECTION)
	STEEL/METAL/FRP (SMALL SCALE SECTION)
	GRATING OR SOLID FRP GRATING (SECTION)
	FINISHED GRADE
	GRAVEL/DRAINROCK/AGGREGATE BASE

PIPING ENDS (SINGLE-LINE)	
	PIPE MATERIAL CHANGE
	PUSH-ON JOINT - BELL AND SPIGOT
	PUSH-ON JOINT - RESTRAINED

	SLEEVE TYPE COUPLING
	SLEEVE TYPE COUPLING - RESTRAINED



STANDARD DETAILS ARE LOCATED ON DISCIPLINE GENERAL SHEETS, IN NUMERICAL ORDER

MISCELLANEOUS

	SHEET KEY NOTES
	CENTERLINE
	COORDINATE POINT
	ROUND OR DIAMETER

DISCIPLINE SPECIFIC SYMBOLS ARE SHOWN ON THE DISCIPLINE GENERAL DRAWINGS.
FOR WELDING SYMBOLS USE AMERICAN WELDING SOCIETY STANDARD SYMBOLS.

REV 012216

MISCELLANEOUS	
	WATER LEVEL

CONTROL SYMBOLS	
	BM-XX BENCH MARK
	SITE COORDINATES (SEE TABLE ON DRAWINGS)
	SITE COORDINATES
	MONUMENT
	HORIZONTAL CONTROL POINT
	VERTICAL CONTROL POINT
	HORZ AND VERT CONTROL POINT
	FINISHED ELEVATION
	EXISTING ELEVATION
	DELTA


REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	WARNING	DESIGNED
NO SCALE	 IF THIS BAR DOES NOT MEASURE 1' THEN DRAWING IS NOT TO SCALE	C. CRONIN
		DRAWN J. PAYNE
		CHECKED J. D'ALELIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM	NBC CONTRACT NO 308.05C GENERAL	SHEET G-3
	OF-217 CONSOLIDATION CONDUIT SYMBOLS	195130227



BY: JAIMIE PAYNE

PLOT DATE: Tuesday, July 27, 2021 9:50:14 AM

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAVVT_IIA-5_GENERAL.dwg

GENERAL CIVIL SYMBOLS

	NEW
	EXISTING
	FUTURE
	EXISTING TO BE REMOVED OR DEMOLISHED
	CENTERLINE
	EARTH (IN SECTION)
	COMPACTED EARTH (IN SECTION)
	S=0.0123 SLOPE ON PAVED SURFACE
	3:1 BERM SLOPE (HORZ TO VERT)

TOPOGRAPHY AND MAPPING SYMBOLS

	125 MAJOR CONTOURS
	MINOR CONTOURS
	TOP OF SLOPE
	TOE OF SLOPE
	PROPERTY LINE
	RIGHT-OF-WAY LINE
	EASEMENT LINE
	TEMPORARY EASEMENT LINE
	LIMIT OF DISTURBANCE LINE
	TRAIL OR DIRT ROAD
	FLOW LINE
	FLOOD HAZARD AREA
	EDGE OF WETLANDS
	GUARDRAIL (PERMANENT)
	GUARDRAIL (REMOVABLE)
	VEGETATION
	WELL

GEOTECHNICAL SYMBOLS

	B-X SOIL BORING LOCATION
	TEST PIT LOCATION
	XX OBSERVATION HOLE
	MW MONITORING WELL

PIPING AND UTILITIES

UTILITIES (SINGLE LINE) SEE PIPE SCHEDULE FOR ADDITIONAL PIPING INFO

	G UTILITIES (SIZE WHERE NOTED)
	G UNDERGROUND
	NATURAL GAS LINE WATER POTABLE WATER FIRE SUPPLY WATER LINE STORM DRAIN SANITARY SEWER TELEPHONE COMMUNICATIONS LINE FIBER OPTIC CABLE CABLE TV POWER UNIDENTIFIED ABANDONED UTILITY
	PP POWER POLE
	BURIED ACCESS MANOLE (IN PLAN) LOCATE ON SIDE SHOWN
	BURIED ACCESS MANHOLE (IN PROFILE)
	BLOWOFF (IN PROFILE) LOCATE ON SIDE SHOWN
	BLOWOFF (IN PLAN)
	BLOWOFF (IN PROFILE)
	FH FIRE HYDRANT (IN PLAN)
	FH FIRE HYDRANT (IN PROFILE)
	MH MANHOLE (IN PLAN)
	MH MANHOLE (IN PROFILE)
	COTG PCOTG CLEANOUT TO GRADE OR PRESSURE CLEANOUT TO GRADE (IN PLAN)
	COTG PCOTG CLEANOUT TO GRADE OR PRESSURE CLEANOUT TO GRADE (IN PROFILE)
	GATE VALVE
	BUTTERFLY VALVE
	ECCENTRIC PLUG VALVE
	LUBRICATED PLUG VALVE

DRAINAGE SYMBOLS

	RIPRAP
	HAY BALE
	COMPOST FILTER SOCK

ROAD AND PAVING SYMBOLS

	ASPHALT CEMENT PAVING
	CONCRETE PAVING (HEAVY DUTY)
	GRAVEL PAVING
	CONCRETE PAVING (LIGHT DUTY) SIDEWALKS ETC...
	CONCRETE CURB
	CONCRETE CURB AND GUTTER
	DROP INLET CATCH BASIN
	CURBSIDE DROP INLET CATCH BASIN WITH LOCAL DEPRESSION
	SIDE INLET CATCH BASIN WITH LOCAL DEPRESSION
	CONCRETE WALK
	DRIVEWAY/ACCESS RAMP

CONTROL SYMBOLS


	BM-XX BENCH MARK
	### SITE COORDINATES (SEE TABLE ON DRAWINGS)
	N XXXXXXXX E XXXXXXXX SITE COORDINATES
	EL XXXX.XX MONUMENT
	HORIZONTAL CONTROL POINT
	VERTICAL CONTROL POINT
	HORZ AND VERT CONTROL POINT
	XXX.XX FINISHED ELEVATION
	(XXX.XX) EXISTING ELEVATION
	DELTA

STRUCTURES

	SITE OR RETAINING WALL
	x-x FENCE (CHAINLINK)
	FENCE (WOOD)
	STRUCTURE
	STRUCTURE (BELOW GRADE)
	CB CATCH BASIN

SURVEY SYMBOLS

	GAS VALVE
	WATER VALVE
	UNKNOWN VALVE
	HYDRANT
	UTILITY POLE
	UTILITY POLE WITH LIGHT
	GUY WIRE
	CATCH BASIN
	DMH DRAIN MANHOLE
	SMH SANITARY MANHOLE
	TMH TELEPHONE MANHOLE
	SHH SIGNAL HAND HOLE
	EHH ELECTRIC HAND HOLE
	SIGN
	ER ELECTRIC RISER
	-49- EXISTING CONTOUR
	DECIDUOUS TREE
	CONIFEROUS TREE
	DECIDUOUS SHRUB
	DECIDUOUS SHRUB
	CONIFEROUS SHRUB
	BORING
	LIGHT
	LIGHT POLE
	LA LANDSCAPED AREA
	CR & DWS CURB RAMP & DETECTABLE WARNING SYSTEM
	TLD TRAFFIC LOOP DETECTOR
	IHH IRRIGATION HANDHOLE
	TEST PIT
	OW OBSERVATION WELL



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE: NO SCALE

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: C. CRONIN
DRAWN: J. PAYNE
CHECKED: J. D'ALESSIO


FINAL DESIGN - JULY 2021



BY: JAMIE PAYNE

PLOT DATE: Tuesday, July 27, 2021 9:50:58 AM

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_SITE_STAGING_III\A-5a_ait.dwg



WHERE COMPOST FILTER SOCK IS LOCATED ON EXISTING PAVEMENT, SUPPORT SOCK WITH CONCRETE BLOCKS OR SANDBAGS. COMPOST FILTER SOCKS SHALL REMAIN IN PLACE UNTIL TEMPORARY PAVEMENT IS INSTALLED.

PROVIDE COMPOST FILTER SOCK

CONSTRUCTION ACCESS PAD (60'x12')

TEMPORARY FENCING (TYP.)

LIMIT OF WORK

CONCRETE WASHOUT AREA

CONNECT TEMPORARY FENCING TO EXISTING FENCING

REMOVE GUARDRAIL AND 10' CLF

REMOVE 7' CLF

SEEKONK RIVER
 FLOOD ←
 → EBB

TOWN LANDING
(CITY OF PAWTUCKET)

FEMA FLOOD ZONE VE


TIDEWATER PROPERTY
(NATIONAL GRID)

GENERAL SHEET NOTES

- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- PORTION OF WORK IS IN PROPERTY OWNED BY NATIONAL GRID. TIDEWATER PROPERTY IS CLEARED OF VEGETATION.
- VERTICAL DATUM FOR PROJECT IS NGVD29.
- EXISTING GRADING ON TIDEWATER SITE IS FROM PLAN ENTITLED "FORMER TIDEWATER FACILITY PAWTUCKET, RHODE ISLAND CONTRACT DOCUMENTS PHASE 4 & 5" PROVIDED BY GZA GEOENVIRONMENTAL, INC. GRADING ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929.
- PROPERTY LINE SOURCE: CITY OF PAWTUCKET GIS
- EXISTING GRADING ON CITY LANDING AND WITHIN RIGHT OF WAY IS FROM SURVEY INFORMATION PROVIDED BY BRYANT ASSOCIATES, INC.

SHEET KEYNOTES

- LIMITS OF CONCRETE BARRIERS WITHIN ROADWAY. BARRIERS SHALL CONFORM TO RIDOT STANDARD 40.5.0




REV	DATE	BY	DESCRIPTION
1	10/21/2020	JP	ALIGNMENT UPDATE TO ACCOMMODATE STADIUM

SCALE
1" = 40'

WARNING
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
 DRAWN J. PAYNE
 CHECKED C. CRONIN

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
 PHASE III COMBINED SEWER
 OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
 CIVIL
 OF-217 CONSOLIDATION CONDUIT
 LIMITS OF WORK - TOWN LANDING SITE

SHEET
C-1
195130227

GENERAL SHEET NOTES

- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID. TIDEWATER PROPERTY IS CLEARED OF VEGETATION.
- VERTICAL DATUM FOR PROJECT IS NGVD29.


GENERAL SHEET NOTES CONT.

- EXISTING GRADING ON TIDEWATER SITE IS FROM PLANS ENTITLED "FORMER TIDEWATER FACILITY PAWTUCKET, RHODE ISLAND CONTRACT DOCUMENTS PHASE 4 & 5" PROVIDED BY GZA GEOENVIRONMENTAL, INC AND "TIDEWATER STADIUM PAWTUCKET, RHODE ISLAND" PROVIDED BY FORTUITOUS PARTNERS. GRADING ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929.
- PROPERTY LINE SOURCE: CITY OF PAWTUCKET GIS
- EXISTING GRADING ON CITY LANDING AND WITHIN RIGHT OF WAY IS FROM SURVEY INFORMATION PROVIDED BY BRYANT ASSOCIATES, INC.



SHEET KEYNOTES

- COORDINATE WITH NATIONAL GRID FOR ABANDONMENT OF GAS SERVICE INCLUDING VENT & GATE VALVE.
- COORDINATE WITH CITY AND NATIONAL GRID TO ISOLATE, REMOVE/REPLACE ELECTRIC LIGHT POLE
- LIMITS OF CONCRETE BARRIERS WITHIN ROADWAY. BARRIERS SHALL CONFORM TO RIDOT STANDARD 40.5.0

SEEKONK RIVER



DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawings\Files\Civil\Sheet\Set\PAWT_SITE_STAGING_11A-5a_ait.dwg
 PLOT DATE: Tuesday, July 27, 2021 9:51:09 AM
 BY: JAMIE PAYNE



REV	DATE	BY	DESCRIPTION
1	10/21/2020	JP	ALIGNMENT UPDATE TO ACCOMMODATE STADIUM

SCALE
1" = 40'

WARNING
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN J. PAYNE
CHECKED C. CRONIN

FINAL DESIGN - JULY 2021






NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
LIMITS OF WORK - TIDEWATER SITE


BY: JAIMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet Set\PAWT_Site_Plan_&_Profile_IIIa-5_AL13.dwg; OT DATE: Tuesday, August 17, 2021 11:31:49 AM



- GENERAL SHEET NOTES**
- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC. SEWER AND DRAIN INFORMATION PROVIDED BY BRYANT AND ASSOCIATES.
 - FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
 - VERTICAL DATUM FOR PROJECT IS NGVD29.
 - WORK IN PROPERTY OWNED BY CITY OF PAWTUCKET.

- SHEET KEYNOTES**
- MICROTUNNEL: STATION 1+26 TO STATION 4+00
 - EXCAVATION FOR MH 217-5 TO BE CONSTRUCTED AS RECEIVING PIT FOR MICROTUNNEL OPERATION. CONTRACTOR IS FULLY RESPONSIBLE FOR SELECTING SPECIFIC SOE SYSTEM TYPE AND DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
 - COORDINATE WITH NATIONAL GRID FOR TEMPORARY POWER SHUT OFF FOR OVERHEAD WIRES AND SUPPORT POLES AS REQUIRED TO FACILITATE INSTALLATION OF RECEIVING SHAFT, EQUIPMENT, AND STRUCTURES. PROVIDE TEMPORARY STREET LIGHTING FOR DURATION OF POWER INTERRUPTION AND FOR FULL LENGTH OF STREET WHERE LIGHTING HAS BEEN IMPACTED.
 - PROVIDE SEALED AND BOLTED MANHOLE COVERS
 - TYPICAL CATCH BASIN EROSION CONTROL
 - SEE "GAS MAIN ENCROACHMENT COORDINATION" NOTES ON SHEET GC-1.
 - PROVIDE PENETRATION IN NORTH FACE OF MANHOLE TO RECEIVE 48" RCP PIPE TO BE INSTALLED BY OTHERS. CONSTRUCT TEMPORARY BRICK BULKHEAD IN PENETRATION SEE DETAIL C-903. INVERT TO BE CONSTRUCTED BY OTHERS.
 - REMOVE AND REPLACE EXISTING CATCH BASIN TO ACCEPT NEW DISCHARGE PIPE.
 - PLUG & ABANDON EXISTING DRAIN PIPE AND FILL ABANDONED PIPE WITH CLSM. REMOVE TO FACILITATE INSTALLATION OF NEW WORK AS REQUIRED.



REV	DATE	BY	DESCRIPTION
2	8/19/21	JP	ADDENDUM #1
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALESSIO

FINAL DESIGN - JULY 2021




NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE I: STA 0+00 - 4+00


SHEET
C-3
195130227

BY: JAMIE PAYNE


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet Set\PAWT_SITE_PLAN & PROFILE.dwg PLOT DATE: Tuesday, July 27, 2021 9:52:40 AM



PLAN
SCALE: 1" = 20'




PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)



- GENERAL SHEET NOTES**
- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC. SEWER AND DRAIN INFORMATION PROVIDED BY BRYANT AND ASSOCIATES.
 - FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
 - WORK IS IN PROPERTY OWNED BY THE CITY OF PAWTUCKET
 - VERTICAL DATUM FOR PROJECT IS NGVD29.

- SHEET KEYNOTES**
- MICROTUNNEL: STATION 4+00 TO STATION 7+50
 - EXCAVATION FOR MH 217-6 TO BE CONSTRUCTED AS WORKING SHAFT AND RECEIVING PIT FOR MICROTUNNEL OPERATION. SUPPORT OF EXCAVATION LIMITS BASED ON SECANT PILE CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
 - COORDINATE WITH NATIONAL GRID FOR TEMPORARY POWER SHUT OFF FOR OVERHEAD WIRES AND SUPPORT POLES AS REQUIRED TO FACILITATE INSTALLATION OF RECEIVING SHAFT, EQUIPMENT, AND STRUCTURES. PROVIDE TEMPORARY STREET LIGHTING FOR DURATION OF POWER INTERRUPTION AND FOR FULL LENGTH OF STREET WHERE LIGHTING HAS BEEN IMPACTED.
 - TYPICAL CATCH BASIN EROSION CONTROL
 - PRIOR TO MICROTUNNEL OPERATIONS FILL EXISTING MONITORING WELL WITH GROUT.
 - REPLACE CONCRETE SIDEWALK AND MICROMILL AND OVERLAY PAVEMENT WITHIN LIMITS OF WORK AFTER COMPLETION OF ACTIVITIES.



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN	WARNING 0 1/2 1 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DESIGNED C. CRONIN DRAWN B. MARINI CHECKED J. D'ALELIO
-------	----------	--	--

FINAL DESIGN - JULY 2021




NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE II: STA 4+00 - 7+50


SHEET
C-4
195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_SITE_PLAN_&_PROFILE_III-A-5_ALT3.dwg; LOT DATE: Tuesday, July 27, 2021 9:53:25 AM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN




PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC. SEWER AND DRAIN INFORMATION PROVIDED BY BRYANT AND ASSOCIATES.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID/ CITY OF PAWTUCKET.
- VERTICAL DATUM FOR PROJECT IS NGVD29.
- EXISTING CONTOURS ARE APPROXIMATE AND BASED ON INFORMATION PROVIDED BY FORTUITOUS PARTNERS.

SHEET KEYNOTES

- MICROTUNNEL: STATION 7+50 TO STATION 12+00
- TYPICAL CATCH BASIN EROSION CONTROL
- COORDINATE WITH NATIONAL GRID FOR TEMPORARY POWER SHUT OFF FOR OVERHEAD WIRES AND SUPPORT POLES AS REQUIRED TO FACILITATE INSTALLATION OF RECEIVING SHAFT, EQUIPMENT, AND STRUCTURES. PROVIDE TEMPORARY STREET LIGHTING FOR DURATION OF POWER INTERRUPTION AND FOR FULL LENGTH OF STREET WHERE LIGHTING HAS BEEN IMPACTED.
- CONCRETE PIPE AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 8+00 TO 12+00. MH 217-6 IS NOT TO BE LINED.
- PRIOR TO MICROTUNNEL OPERATIONS FILL EXISTING MONITORING WELL WITH GROUT, COORDINATE WITH NATIONAL GRID.
- EXCAVATION FOR MH 217-6 TO BE CONSTRUCTED AS WORKING SHAFT AND RECEIVING PIT FOR MICROTUNNEL OPERATION. SUPPORT OF EXCAVATION LIMITS BASED ON SECANT PILE CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
- SEE "GAS MAIN ENCROACHMENT COORDINATION" NOTES ON SHEET GC-1.
- REPLACE CONCRETE SIDEWALK AND MICROMILL AND OVERLAY PAYMENT WITHIN LIMIT OF WORK AFTER COMPLETION OF ACTIVITIES.



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

FINAL DESIGN - JULY 2021




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE III: STA 7+50 - 12+00


SHEET
C-5
195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawings\Files\Civil\Sheet\Set\PAWT_SITE_PLAN_&_PROFILE.dwg; LOT DATE: Tuesday, July 27, 2021 9:54:12 AM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN




PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED PROVIDED BY NATIONAL GRID. SEWER AND DRAIN INFORMATION PROVIDED BY BRYANT AND ASSOCIATES.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID
- VERTICAL DATUM FOR PROJECT IS NGVD29.
- EXISTING CONTOURS ARE APPROXIMATE AND BASED ON INFORMATION PROVIDED BY FORTUITOUS PARTNERS.
- TANK HOLDER NO. 7 & 8 FOUNDATION MATERIALS AND CONFIGURATION ARE APPROXIMATE BASED ON INFORMATION OBTAINED FROM THE OWNER. DRAWINGS NOT AVAILABLE

SHEET KEYNOTES

- MICROTUNNEL: STATION 12+00 TO STATION 16+00
- EXCAVATION AT MH 217-7 TO BE CONSTRUCTED AS WORKING SHAFT IN SUPPORT OF MICROTUNNEL OPERATION. SECANT PILE SOE SYSTEM SHOWN. CONTRACTOR IS RESPONSIBLE FOR DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS. EXISTING SOIL CAP DISTURBED BY THE EXCAVATION SHALL BE RESTORED IN ACCORDANCE WITH DETAILS C-918 AND C-922.
- CONCRETE PIPE AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 12+00 TO 16+00
- PRIOR TO MICROTUNNEL OPERATIONS FILL EXISTING MONITORING WELL WITH GROUT. COORDINATE WITH NATIONAL GRID.
- SUPPORT POLE IN COORDINATION WITH NATIONAL GRID IF GUY WIRE IS REMOVED DURING CONSTRUCTION.
- COORDINATE WITH NATIONAL GRID FOR ABANDONMENT OF GAS SERVICE INCLUDING VENT & GATE VALVE.
- DEMO EXISTING CONCRETE TANK HOLDER FOR INSTALLATION OF SECANT PILES AND WORKING SHAFT.



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE AS SHOWN	WARNING 0 1/2 1 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DESIGNED C. CRONIN DRAWN B. MARINI CHECKED J. D'ALESIO
-------------------	--	--

FINAL DESIGN - JULY 2021




NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE IV: STA 12+00 - 16+00


SHEET
C-6
195130227

BY: JAMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Drawing Files\Civil\Sheet\Set\PAWT_Site_Plan_& Profile.dwg LOT DATE: Tuesday, July 27, 2021 9:54:53 AM




PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)

KEY PLAN




PAWTUCKET, RI

GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID. SEWER AND DRAIN INFORMATION PROVIDED BY BRYANT AND ASSOCIATES.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID
- RELIEF HOLDER 4: APPROX. DEPTH INFORMATION BASED ON TEST PIT PERFORMED BY OTHERS AND INCLUDED IN PROJECT SPECIFICATIONS AS APPENDIX F. INFORMATION BEYOND DEPTH DEPICTED IS UNKNOWN.
- VERTICAL DATUM FOR PROJECT IS NGVD29.
- EXISTING CONTOURS ARE APPROXIMATE AND BASED ON PROPOSED GRADES PROVIDED BY NATIONAL GRID AND FORTUITOUS PARTNERS.
- EXISTING SOIL CAP DISTURBED BY OPEN CUT PIPELINE CONSTRUCTION EXCAVATION SHALL BE RESTORED IN ACCORDANCE WITH CAP DETAILS.

SHEET KEYNOTES

- RELOCATE WATER MAIN: STATION 18+88. SEE SHEET C-9 FOR WATER MAIN REPLACEMENT.
- APPROXIMATE LOCATION OF MICROTUNNEL RECEIVING SHAFT. CONTRACTOR IS RESPONSIBLE FOR SELECTING SOE SYSTEM TYPE AND DESIGNING SOE IN ACCORDANCE WITH CRITERIA IN THE CONTRACT DOCUMENTS.
- TYPICAL CATCH BASIN EROSION CONTROL
- PAVEMENT SAW-CUT LIMIT
- CONCRETE PIPE, STRUCTURES AND MANHOLES ON TIDEWATER SITE ARE TO BE LINED WITH GEOPOLYMER LINING SYSTEM: STATION 16+00 TO 18+88
- CONSTRUCT TEMPORARY BRICK BULKHEAD IN NORTHWEST FACE CONSOLIDATION CONDUIT PENETRATION OF THE DIVERSION STRUCTURE. SEE DETAIL SHEET S-2.
- FOR CAP CONSTRUCTION FROM STATION 16+52 TO 17+37 SEE DETAIL C-918. FOR CAP CONSTRUCTION FROM STATION 17+37 TO 18+88 SEE DETAIL C-920.
- FOR CAP CONSTRUCTION RELATED TO ELECTRICAL CONDUIT INSTALLATION SEE DETAIL C-919. SEE SHEET E-1.




REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM




NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
PLAN AND PROFILE V: STA 16+00 - 18+88


SHEET
C-7

195130227


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet Set\PAWT SITE_PLAN_AND_PROFILE_IIIa-5_ALT3.dwg, OT DATE: Thursday, August 19, 2021 11:05:59 AM BY: JAIME PAYNE



PLAN
SCALE: 1" = 20'



PROFILE
SCALE: 1" = 20' (H)
1" = 5' (V)



GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID
- VERTICAL DATUM FOR PROJECT IS NGVD29.
- EXISTING CONTOURS ARE APPROXIMATE AND BASED ON PROPOSED GRADES PROVIDED BY NATIONAL GRID AND FORTUITOUS PARTNERS.
- CAP RESTORATION WORK FROM STATION 0+00 TO 0+51 TO BE COMPLETED BY OTHERS AFTER OUTFALL PIPE IS INSTALLED THROUGH STATION 0+80. FOR CAP RESTORATION FROM STATION 0+51 TO 4+46 SEE DETAIL C-920.

SHEET KEYNOTES

Keynote symbols and their corresponding notes are listed here, including a triangle symbol for 'APPROX. LOCATION OF EX. 6" PW (ABD)' and a circle symbol for 'DIVERSION STRUCTURE 217'.

REV	DATE	BY	DESCRIPTION
2	8/19/21	JP	ADDENDUM #1
1	5/13/20	JP	STANTEC COMMENTS

SCALE AS SHOWN	WARNING IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DESIGNED C. CRONIN DRAWN J. PAYNE CHECKED J. D'ALELIO
-------------------	---	---

FINAL DESIGN - JULY 2021




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL


OF-217 CONSOLIDATION CONDUIT
OF-217 OUTFALL PLAN AND PROFILE VI: STA 0+00 - 4+46

SHEET
C-8
195130227




BY: JAIMIE PAYNE

DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet Set\PAWT SITE_PLAN_&_PROFILE_IIIa-5_ALT3.dwg, LOT DATE: Tuesday, July 27, 2021 1:50:53 PM




PLAN
SCALE: 1" = 10'



- GENERAL SHEET NOTES**
- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
 - FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
 - WORK IS IN PROPERTY OWNED BY NATIONAL GRID
 - VERTICAL DATUM FOR PROJECT IS NGVD29.
 - WATER MAIN RELOCATION WILL REQUIRE NIGHT WORK. ACCESS TO THE SUBSTATION MUST BE MAINTAINED AT ALL TIMES.

- PROPOSED SEQUENCE OF WATER RELOCATION**
- CLOSE EXISTING 12" VALVE & (2) 8" VALVES TO ISOLATE WATER MAIN.
 - INSTALL (2) 12" DI CAPS DOWNSTREAM OF EXISTING HYDRANT.
 - INSTALL NEW 12" X 8" TEE & 12" DI CAP AND RECONNECT TO EXISTING 12" WATER MAIN. INSTALL 6" DI CAP.
 - INSTALL NEW 8" PIPE.
 - INSTALL NEW 8" TEE & 8" DI CAP AND RECONNECT TO EXISTING 8" WATER MAIN.
 - OPEN EXISTING 12" VALVE & (2) 8" VALVES TO REACTIVATE WATER MAINS.
 - REMOVE & DISPOSE EXISTING WATER MAIN WITHIN OF-217 RELOCATION STRUCTURE EXCAVATION.
 - INSTALL 12" DI CAP & ABANDON EXISTING 12" WATER MAIN SECTION WITH CLSM.



REV	DATE	BY	DESCRIPTION

SCALE AS SHOWN	WARNING IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
-------------------	---









DESIGNED C. CRONIN	CHECKED J. D'ALESEO
DRAWN R. GREENWAY	

FINAL DESIGN - JULY 2021




NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM	NBC CONTRACT NO 308.05C CIVIL
OF-217 CONSOLIDATION CONDUIT WATER RELOCATION PLAN	


SHEET C-9 195130227




REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN	DESIGNED C. CRONIN	FINAL DESIGN - JULY 2021
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DRAWN C. MARSHALL	
		CHECKED J. D'ALESSIO	







SEWER MANHOLE FRAME AND COVER
NOT TO SCALE REV 000000 C-107




HEAVY-DUTY ROUND FRAME AND COVER
NOT TO SCALE R.I. STANDARD 6.2.1



SQUARE FRAME AND GRATE (BICYCLE SAFE)
NOT TO SCALE R.I. STANDARD 6.3.2




TRENCH SECTION FOR IMPERMEABLE EARTH WATER STOP
NOT TO SCALE REV 000000 C-904




- NOTES:**
- WHERE SEWER CANNOT BE INSTALLED 18" BENEATH WATER, OR WHERE SEWER AND WATER PIPING ARE WITHIN 10 FEET OF EACH OTHER, PROPOSED WATER OR SEWER PIPE SHALL BE SLEEVED INSIDE AN AWWA C-900 PVC PIPE OF APPROPRIATE DIAMETER WITHIN 10 FEET OF THE CROSSING.
 - CONTRACTOR MAY ELECT TO ENCASE PIPE WITHIN CONCRETE INSTEAD OF USING PIPE SLEEVES, AT NO ADDITIONAL EXPENSE TO THE OWNER. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI AFTER 28 DAYS. CONCRETE ENCASEMENT SHALL EXTEND A MINIMUM OF 6" AROUND THE PIPE IN ALL DIRECTIONS.


WATER/SEWER CROSSING DETAIL
NOT TO SCALE REV 000000 C-112



C-905 CONCRETE COLLAR DETAIL
NOT TO SCALE



WATER STOP SEALANT DETAIL



REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALELIO

FINAL DESIGN - JULY 2021



NARRAGANETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM
NBC CONTRACT NO 308.05C CIVIL
OF-217 CONSOLIDATION CONDUIT CIVIL DETAILS II

SHEET	C-11
195130227	



TYPICAL SUPPORTS FOR UTILITIES
NOT TO SCALE REV 000000 C-113


DIAMETER OF PIPE D IN INCHES	MAXIMUM PAYMENT LIMITS					
	TRENCH WIDTH IN FEET		TEMPORARY TRENCH PAVEMENT WIDTH IN FEET		PERMANENT TRENCH PAVEMENT WIDTH IN FEET*	
	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH	TRENCH DEPTH
12 AND SMALLER	< OR = 10'	> 10' TO 20'	< OR = 10'	> 10' TO 20'	< OR = 10'	> 10' TO 20'
15	5.00	6.00	7.00	8.00	9.00	10.00
18	5.25	6.25	7.25	8.25	9.25	10.25
21	5.75	6.75	7.75	8.75	9.75	10.75
24	6.00	7.00	8.00	9.00	10.00	11.00
27	6.25	7.25	8.25	9.25	10.25	11.25
30	6.50	7.50	8.50	9.50	10.50	11.50
36	7.00	8.00	9.00	10.00	11.00	12.00
42	7.50	8.50	9.50	10.50	11.50	12.50
48	8.00	9.00	10.00	11.00	12.00	13.00
54	8.50	9.50	10.50	11.50	12.50	13.50
60	9.00	10.00	11.00	12.00	13.00	14.00
66	9.50	10.50	11.50	12.50	13.50	14.50
72	10.00	11.00	12.00	13.00	14.00	15.00

TRENCH WIDTH SCHEDULE


NOTES:

- PERMANENT TRENCH PAVEMENT INCLUDES 1' CUT BACK OF TEMPORARY PAVEMENT ALONG EACH SIDE OF THE TRENCH.
- TRENCH DEPTH MEASURED FROM THE EXISTING GROUND SURFACE TO 6" BELOW THE BOTTOM OF THE CONSTRUCTED PIPE.
- QUANTITIES FOR PAYMENT SHALL BE IN ACCORDANCE WITH THE ABOVE LIMITS OR THE ACTUAL WIDTHS, WHICHEVER IS LESS.


TRENCH WIDTH SCHEDULE
NOT TO SCALE REV 000000 C-906



TRENCH SECTION (TO BE USED WHERE UNSUITABLE FOUNDATION MATERIAL EXISTS BELOW NORMAL DEPTH)
NOT TO SCALE REV 000000 C-907




FLAP GATE DETAIL
NOT TO SCALE REV 000000 C-908



NOTES:

- CONCRETE SIDEWALK SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 905 OF THE R.I. STANDARD SPECIFICATIONS.
- WIRE MESH SHALL BE IN ACCORDANCE WITH SECTION M.05.02 OF THE R.I. STANDARD SPECIFICATIONS.


TYPICAL CEMENT CONCRETE SIDEWALK
NOT TO SCALE REV 000000 C-202




NOTES:

- SHALL BE IN ACCORDANCE WITH SECTION 906 OF THE R.I. STANDARD SPECIFICATIONS.
- PROVIDE CEMENT CONCRETE CURB LOCK ON ALL CURBS.

CURB SETTING DETAIL
NOT TO SCALE REV 000000 C-203



DETECTABLE WARNING PAVER
NOT TO SCALE C-204



REV	DATE	BY	DESCRIPTION

SCALE	WARNING
AS SHOWN	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE



DESIGNED C. CRONIN	FINAL DESIGN - JULY 2021
DRAWN C. MARSHALL	
CHECKED J. D'ALELIO	

--	--



NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM	NBC CONTRACT NO 308.05C CIVIL

SHEET	C-12




ROADWAY PROFILE GRADE	T (FT)
0.00	6.0
0.01	7.0
0.02	8.0
0.03	9.5
0.04	11.5
0.05	15.0

NOTES:


1. SHALL BE IN ACCORDANCE WITH SECTION 905 OF THE RI STANDARD SPECIFICATIONS.
2. WHEN ANY OBSTRUCTION LOCATED IN THE SIDEWALK FALLS WITHIN A CROSSWALK AREA, THE WHEELCHAIR RAMP WILL BE PLACED SUCH THAT THE OBSTRUCTION FALLS OUTSIDE OF THE RAMP.
3. AT NO TIME IS ANY PART OF THE WHEELCHAIR RAMP TO BE LOCATED OUTSIDE OF THE CROSSWALK, AND IT IS TO BE CENTERED WHENEVER POSSIBLE.
4. DRAINAGE FACILITIES ARE TO BE LOCATED UP-GRADE OF ALL WHEELCHAIR RAMPS.
5. LOCATION OF WHEELCHAIR RAMPS IS AS SHOWN ON CONTRACT DRAWINGS.
6. IN NO INSTANCE SHALL THE SIDEWALK CROSS SLOPE EXCEED 1:50 EXCEPT WITHIN THE RAMP AREA.
7. AN UNOBSTRUCTED PATH OF TRAVEL WITH A MINIMUM WIDTH OF 3'-0" SHALL BE MAINTAINED.
8. THE WHEELCHAIR RAMP SLOPE AND SIDE SLOPES (TRANSITIONS), MUST NOT EXCEED 1:12. HOWEVER, THESE SLOPES MAY BE FLATTER THAN 1:12 WHEN WARRANTED BY SURROUNDING CONDITIONS.
9. WHERE THE ROAD PROFILE EXCEEDS 5% THE HIGH SIDE TRANSITION LENGTH (T) SHALL BE EIGHTEEN FEET (18'-0").
10. IN NO CASE, WHERE A STOP LINE IS WARRANTED, SHALL A RAMP BE PLACED BEHIND THE STOP LINE.
11. THE ENTRANCE OF THE WHEELCHAIR RAMP SHALL BE FLUSH WITH THE ROADWAY.
12. THE WHEELCHAIR RAMP SHALL BE CENTERED RADIALLY, OPPOSITE THE RADIUS POINT WHEN POSSIBLE.
13. MINIMUM LENGTH OF STRAIGHT OR CIRCULAR FILLER PIECES TO BE 3'-0" (GREATER LENGTHS PREFERRED).
14. 8" CONCRETE DEPTH FOR RADIUS WHEELCHAIR RAMPS ONLY. USE 4" DEPTH FOR TANGENT (MID-BLOCK) LOCATIONS

WHEELCHAIR RAMP
NOT TO SCALE

RI STANDARD
43.3.0





DETAIL FOR SIDEWALK AT STONE WALL (NOT TO SCALE)




DETAIL FOR PREFORMED JOINT FILLER AND SEALER (NOT TO SCALE)

DETAIL FOR SIDEWALK AT STONE WALL
NOT TO SCALE

REV 000000



EXPANSION JOINT AT 20' OC (TYP)




CONTROL JOINT AT 5' OC (TYP)

NOTES:


1. EXPANSION JOINTS (EJ) 20 FEET OC UNLESS OTHERWISE NOTED.
2. CONTROL JOINTS (CJ) 5 FEET OC UNLESS OTHERWISE NOTED.
3. WHERE EXISTING AND NEW CONCRETE SIDEWALKS MEET, SAWCUT EXISTING WALK AND INSTALL EXPANSION JOINT AND DOWELS AS SHOWN. DRILL EXISTING CONCRETE WALK EDGE TO RECEIVE STEEL DOWELS AT EXPANSION JOINT.

EXPANSION & CONTROL JOINTS FOR SIDEWALK PAVING
NOT TO SCALE

REV 000000



ROADWAY GRADE	T
0.00	6.0
0.01	7.0
0.02	8.0
0.03	9.5
0.04	11.5
0.05	15.0




SECTION A-A

NOTES:

1. SHALL BE IN ACCORDANCE WITH SECTION 905 OF THE R.I. STANDARD SPECIFICATIONS.
2. THIS DETAIL IS TO BE USED ONLY WHEN STATE RIGHT-OF-WAY IS LIMITED TO BACK OF SIDEWALK, AND SIDEWALK IS NARROW WITH NO PEDESTRIAN TRAFFIC FROM SIDE STREET.
3. WHEN ANY OBSTRUCTION LOCATED IN THE SIDEWALK FALLS WITHIN A CROSSWALK AREA, IF POSSIBLE, THE OBSTRUCTION SHALL BE PLACED SUCH THAT IT FALLS OUTSIDE OF THE RAMP.
4. AT NO TIME IS ANY PART OF THE WHEELCHAIR RAMP TO BE LOCATED OUTSIDE OF THE CROSSWALK, AND IT IS TO BE CENTERED WHENEVER POSSIBLE.
5. DRAINAGE FACILITIES ARE TO BE LOCATED UP-GRADE OF ALL WHEELCHAIR RAMPS.
6. LOCATION OF WHEELCHAIR RAMPS IS AS SHOWN ON CONTRACT DRAWINGS.
7. ALL REQUIRED CUTTING OF CURB PIECES TO BE PAID FOR UNDER COST OF CURB.
8. WHERE THE ROAD PROFILE EXCEEDS 5% THE TRANSITION LENGTH (T) SHALL BE EIGHTEEN FEET (18'-0").
9. THE ENTRANCE OF THE WHEELCHAIR RAMP SHALL BE FLUSH WITH THE ROADWAY.
10. MINIMUM LENGTH OF STRAIGHT OR CIRCULAR FILLER PIECES TO BE 3'-0" (GREATER LENGTHS PREFERRED).
11. AN UNOBSTRUCTED PATH OF TRAVEL WITH A MINIMUM WIDTH OF 4'-0" SHALL BE MAINTAINED.



WHEELCHAIR RAMP FOR LIMITED RIGHT-OF-WAY AREAS
NOT TO SCALE




REV	DATE	BY	DESCRIPTION









SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	C. MARSHALL
CHECKED	J. D'ALESSIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM	NBC CONTRACT NO 308.05C CIVIL
OF-217 CONSOLIDATION CONDUIT CIVIL DETAILS IV	SHEET C-13





REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN	DESIGNED C. CRONIN	FINAL DESIGN - JULY 2021
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DRAWN C. MARSHALL	
		CHECKED J. D'ALESSIO	




NBC CONTRACT NO 308.05C	SHEET
CIVIL	C-14
OF-217 CONSOLIDATION CONDUIT CIVIL DETAILS V	195130227





PLAN

PLAN




SECTION

NOTES:

1. ACTUAL LOCATIONS OF CUT AND MATCH LINES TO BE DETERMINED IN THE FIELD.

PROJECT LIMITS CUT AND MATCH DETAIL
NOT TO SCALE

C-910
REV 000000




NOTES:

1. TRANSVERSE DROP-OFF:
POSTED SPEED \leq 35 MPH: 5 FEET HORIZONTALLY TO 1 INCH VERTICALLY
POSTED SPEED $>$ 35 MPH: 10 FEET HORIZONTALLY TO 1 INCH VERTICALLY
2. LONGITUDINAL DROP-OFF (OUTSIDE EDGES OF PAVEMENT):
POSTED SPEED \leq 35 MPH: DROP-OFFS $>$ 3" BUT $<$ 5" SHALL BE TAPERED TO A 1:1 OR FLATTER SLOPE TO EXISTING GROUND ALL DROP-OFFS \geq 5" SHALL BE TAPERED TO A 4:1 OR FLATTER SLOPE TO EXISTING GROUND.
POSTED SPEED $>$ 35 MPH: LONGITUDINAL DROP-OFFS WILL NOT BE PERMITTED WITHIN 2'-0" OF A TRAVEL LANE. THIS AREA MUST BE AT GRADE WITH THE TRAVEL LANE. HOWEVER, SHOULD THE CONTRACTOR'S APPROVED SEQUENCE OF OPERATIONS RESULT IN OVERNIGHT DROP-OFFS GREATER THAN THREE INCHES OCCURRING BETWEEN 2'-0" TO 6'-0" FROM A TRAVEL LANE, THEN THE DROP-OFFS SHALL BE TAPERED TO A 4:1 OR FLATTER SLOPE TO EXISTING GROUND.

PAVEMENT REMOVAL DROP-OFF DETAIL
NOT TO SCALE

R.I. STANDARD
47.1.0




NOTES:

1. A BOND BREAKER (TAPERED OR EQUIVALENT) WILL BE PLACED 5'-0" FROM THE JOINT AND COVERED WITH THE BINDER COURSE AS THE TEMPORARY RAMP. PRIOR TO PLACING THE SURFACE COURSE, THE BINDER COURSE AND BOND BREAKER WILL BE REMOVED.

TRANSVERSE PAVEMENT CUT AND MATCH
NOT TO SCALE

R.I. STANDARD
47.1.1




NOTES:

1. CONTRACTOR TO VARY PAVEMENT THICKNESS TO MAINTAIN A MINIMUM CROSS SECTIONAL SLOPE EQUALING 0.02 FT/FT OR %.

TEMPORARY TRENCH-WIDTH PAVEMENT
NOT TO SCALE

C-911
REV 000000




NOTES:

1. CONTRACTOR TO VARY PAVEMENT THICKNESS TO MAINTAIN A MINIMUM CROSS SECTIONAL SLOPE EQUALING 0.02 FT/FT OR %.

PERMANENT TRENCH-WIDTH PAVEMENT
NOT TO SCALE

C-912



REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


DESIGNED	C. CRONIN
DRAWN	C. MARSHALL
CHECKED	J. D'ALESSIO

FINAL DESIGN - JULY 2021



NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS VI


SHEET	C-15
195130227	



CONTRACTOR TO MATCH EXISTING STRIPING AT THE FOLLOWING LOCATIONS:


- LOCATIONS:**
- INTERSECTION OF MAIN STREET (65 FT WIDE) AND ROOSEVELT AVENUE EXT (34 FT WIDE)
 - 4 CROSSWALKS AND 4 STOPLINES
 - INTERSECTION OF JENKS WAY (44 FT WIDE) AND ROOSEVELT AVENUE EXT (31 FT WIDE)
 - 2 CROSSWALKS AND 1 STOPLINE
 - TAFT STREET (62 FT WIDE) AT APPROXIMATELY 650 FT NORTH OF SPENCER STREET
 - 1 CROSSWALK
 - INTERSECTION OF TOWER STREET (25 FT WIDE) AND TAFT STREET (48 FT WIDE)
 - 2 CROSSWALKS AND 2 STOPLINE
 - INTERSECTION OF TIDEWATER STREET (32 FT WIDE) AND TAFT STREET (30 FT WIDE)
 - 2 CROSSWALKS AND 2 STOPLINES

CROSSWALK AND STOPLINE DETAIL - TYPE 1
NOT TO SCALE REV 000000 C-913




- NOTES:**
- CONTRACTOR TO INSTALL TEMPORARY GRAVEL ACCESS IN AREAS WHERE CONTRACTOR INTENDS TO DRIVE AND/OR STORE EQUIPMENT.
 - TEMPORARY GRAVEL ACCESS SHALL BE REMOVED WHEN NO LONGER REQUIRED BY THE CONTRACTOR.

GRAVEL ACCESS ROAD
NOT TO SCALE REV 000000 C-914




NOTE: SHALL BE IN ACCORDANCE WITH SECTION 211 OF THE R.I. STANDARD SPECIFICATIONS.

CONSTRUCTION ACCESS
NOT TO SCALE R.I. STANDARD 9.9.0




GROUND COVER DETAIL
NOT TO SCALE REV 000000 C-915




- NOTES:**
- COMPOST/ SOIL/ ROCK/ SEED FILL TO MEET APPLICATION REQUIREMENTS.
 - COMPOST MATERIAL TO BE REMOVED OR DISPERSED ON SITE AS DETERMINED BY ENGINEER.
 - IF SOCK NETTING MUST BE JOINED, FIT BEGINNING OF NEW SOCK OVER END OF OLD SOCK, OVERLAPPING BY 2 FEET AND STACK OVERLAP. IF SOCK NETTING IS NOT JOINED, OVERLAP OLD SOCK WITH NEW ONE BY MINIMUM OF 2 FEET.
 - WHERE COMPOST FILTER SOCK IS LOCATED ON EXISTING PAVEMENT, SUPPORT SOCK WITH CONCRETE BLOCK OR SANDBAG. COMPOST FILTER SOCKS SHALL REMAIN IN PLACE UNTIL TEMPORARY PAVEMENT IS INSTALLED.

COMPOST FILTER SOCK
NOT TO SCALE REV 000000 C-401



CONCRETE WASHOUT AREA DETAIL
NOT TO SCALE C-916




REV	DATE	BY	DESCRIPTION

SCALE
AS SHOWN

WARNING
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED C. CRONIN
DRAWN C. MARSHALL
CHECKED J. D'ALELIO

FINAL DESIGN - JULY 2021











NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec PARE

NBC CONTRACT NO 308.05C
CIVIL
OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS VII

SHEET
C-16
195130227



REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN	WARNING 0 1/2 1 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
DESIGNED	C. CRONIN	FINAL DESIGN - JULY 2021
DRAWN	J. PAYNE	
CHECKED	J. D'ALESSIO	

BETA
www.BETA-Inc.com


Stantec

NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
CIVIL



OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS VIII

SHEET
C-17
195130227





LOW PERMEABILITY SOIL FENCE LINE CAP
TRANSITION
NOT TO SCALE

REV 000000





BOOT TYPE #2 - TYPICAL CYLINDRICAL STRUCTURE
GEOTEXTILE BOOT DETAIL
NOT TO SCALE

REV 000000





CAP TYPE-18 RIP RAP SLOPE
TRANSITION
NOT TO SCALE





- NOTES:
1. THE PIPE SHALL BE PROPERLY SECURED TO PREVENT DISPLACEMENT DURING THE INSTALLATION OF CONCRETE.
 2. CONCRETE SHALL EXTEND ALONG THE LENGTH OF THE PIPE IN BOTH DIRECTIONS A MINIMUM OF ONE FOOT BEYOND THE LIMITS OF THE MODIFIED BELL.

RCP TO RCP CONNECTION DETAIL
NOT TO SCALE

REV 000000



MAIN CONNECTION AT INTERSECTION (CUT-IN TEE)
NOT TO SCALE



SCALE	WARNING
AS SHOWN	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALESSIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM




NBC CONTRACT NO 308.05C
CIVIL

OF-217 CONSOLIDATION CONDUIT
CIVIL DETAILS IX

SHEET
C-18
195130227

REV	DATE	BY	DESCRIPTION



RESTRAINT AT FITTINGS

MINIMUM SURFACE AREA OF CONCRETE THRUST BLOCK AGAINST UNDISTURBED EARTH - IN S.F. (SQ. FEET)
 MINIMUM RESTRAINED LENGTH OF PIPE ON EITHER SIDE OF FITTING - IN L.F. (LINEAR FEET)

PIPE SIZE	PLUG SF	TEE SF	90° BEND LF	45° BEND LF	22 1/2° BEND SF	11 1/4° BEND LF
6"	2.8	37	2.8	3.2	4.0	1.8
8"	4.8	48	4.8	5.3	6.8	3.2
10"	7.3	58	7.3	8.3	10.3	4.8
12"	10.3	69	10.3	11.5	14.5	6.8
16"	17.8	89	17.8	20.2	25.2	11.2
20"	27.5	108	27.5	30.8	38.8	17.2
24"	39.2	127	39.2	43.4	53.4	23.2


- ALL CONCRETE TO BE CLASS B (A2)
- THE "SF" VALUES IN THE ABOVE TABLE ARE BASED ON 3000 p.s.f. SOIL BEARING CAPACITY, 150 p.s.i. TEST PRESSURE AND A 1.5 FACTOR OF SAFETY.
- THE "LF" VALUES IN THE ABOVE TABLE ARE BASED ON A TYPE 3 LAYING CONDITIONS, A SAND SILT SOIL DESIGNATION, A 5 FOOT RUN LENGTH, 150 P.S.I. TEST PRESSURE AND A 1.5 FACTOR OF SAFETY AS USED IN THE "THRUST RESTRAINT DESIGN FOR DUCTILE IRON PIPE" COMPUTER PROGRAM BY THE DUCTILE IRON PIPE RESEARCH ASSOCIATION.
- IF SOIL CONDITIONS OR EXCAVATION LIMITS ENCOUNTERED DURING CONSTRUCTION MAKE IT UNFEASIBLE TO PLACE THRUST BLOCKS AGAINST UNDISTURBED EARTH OF THE PROPER BEARING CAPACITY, THE CONTRACTOR SHALL DESIGN AND PLACE SPECIAL REACTION BLOCKS OF SUFFICIENT WEIGHT TO RESIST FULL THRUST UNDER ALL CONDITIONS. THE DESIGN SHALL BE SUBJECT TO PWSB APPROVAL.
- MINIMUM SURFACE AREAS SHALL BE INCREASED BY 50% IF DEEMED NECESSARY BY THE ENGINEER.
- A MECHANICAL JOINT RESTRAINT SYSTEM MUST BE USED FOR VERTICAL BENDS.
- AT THE DISCRETION OF THE ENGINEER, A JOINT RESTRAINT SYSTEM MAY BE SUBSTITUTED FOR OR USED IN COMBINATION WITH PROPER THRUST BLOCKING.
- A 48 HR. CURING PERIOD MUST BE GIVEN BEFORE FULL LINE PRESSURE CAN BE APPLIED TO NEW CONCRETE THRUST BLOCKS.
- ANCHOR BLOCK DESIGN FOR PIPE LARGER THAN 24" SHALL BE REVIEWED ON AN INDIVIDUAL BASIS BY THE PWSB.

Pawtucket WATER SUPPLY BOARD

RESTRAINT AT FITTINGS

REVISION DATE: MAY 2006 NOT TO SCALE STD. NO. **5.04**

RESTRAINT AT FITTINGS
 NOT TO SCALE REV 000000 W-504




NOTE: SUITABLE BACKFILL SHALL BE SELECTED FROM EXCAVATED MATERIALS AND IS SUBJECT TO THE APPROVAL OF THE PWSB ENGINEER.

Pawtucket WATER SUPPLY BOARD

TYPICAL TRENCH DETAIL

REVISION DATE: MAY 2006 NOT TO SCALE STD. NO. **6.01**

TYPICAL TRENCH DETAIL
 NOT TO SCALE REV 000000 W-601




- NOTES:**
- THE METER SHALL BE INSTALLED HORIZONTALLY.
 - TEMPORARY WATER SERVICE CONNECTIONS REQUIRE A PWSB APPROVED TESTABLE BACKFLOW PREVENTION DEVICE. ALL IN ACCORDANCE WITH SECTION 10 OF THE PWSB REGULATIONS, LATEST REVISION.
 - CONTRACTOR MUST NOTIFY THE PWSB METER DEPARTMENT WHEN THE METER INSTALLATION IS COMPLETE.

Pawtucket WATER SUPPLY BOARD

TEMPORARY WATER SERVICE CONNECTION AT HYDRANT


REVISION DATE: JAN. 2011 NOT TO SCALE STD. NO. **8.02**

TEMPORARY WATER SERVICE CONNECTION AT HYDRANT
 REV 000000 W-802



- NOTES:**
- DEVICES NEED TO BE PLACED BEYOND THE AREA OF RESTRAINTS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

TYPICAL THRUST RESTRAINT WEDGE ACTION TYPE JOINTS
 REV 000000 W-902



- NOTES:**
- ALL DUCTILE IRON WATER PIPE THAT IS BACKFILLED WITH CONTROLLED DENSITY FILL MUST BE ENCASED WITH 4-MIL HDCL OR 8-MIL LLD POLYETHYLENE IN ACCORDANCE WITH ANS/AWWA C105/A2.5, METHOD OF INSTALLATION.
 - THE PIPE SHALL BE PROPERLY SECURED AND SUPPORTED TO PREVENT DISPLACEMENT DURING THE POURING OF CONTROLLED DENSITY FILL.

FLOWABLE FILL BACKFILL OF DUCTILE IRON WATER PIPE
 REV 000000 W-903

REV	DATE	BY	DESCRIPTION

SCALE: AS SHOWN

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: C. CRONIN	FINAL DESIGN - JULY 2021
DRAWN: C. MARSHALL	
CHECKED: J. D'ALESSIO	

BETA
 www.BETA-Inc.com

NARRAGANSETT BAY COMMISSION
 PHASE III COMBINED SEWER OVERFLOW PROGRAM

Stantec

NBC CONTRACT NO 308.05C
 CIVIL

OF-217 CONSOLIDATION CONDUIT
 CIVIL DETAILS X


SHEET C-19
 195130227

CHRISTOPHER R. CRONIN
 No. 8509
 REGISTERED PROFESSIONAL ENGINEER (CIVIL)


BY: SARNO, WENDY

PLOT DATE: Friday, July 23, 2021 4:43:28 PM

DWG FILE: C:\Users\Sarno\Box\Jobs\15960.0 NBC - CC IIIA-4 And IIIA-5\CADD\Drawings\CONTRACT IIIA-5\Geotech\B001.dwg



PLAN
SCALE: 1" = 20'



PLAN
SCALE: 1" = 20'

KEY PLAN




GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- REFER TO SHEET B-4 FOR INSTRUMENTATION DETAILS AND NOTES.
- REFER TO SPECIFICATION SECTION 02295 FOR INSTRUMENTATION REQUIREMENTS.

INSTRUMENTATION LEGEND

SYMBOL	INSTRUMENT TYPE
	OBSERVATION WELL (OW)
	DEFORMATION MONITORING POINT (DMP TYPE 1)
	DEFORMATION MONITORING POINT (DMP TYPE 2)
	DEFORMATION MONITORING POINT (DMP TYPE 3)
	INCLINOMETER (INCL)
	UTILITY MONITORING POINT (UMP)
	SEISMOGRAPH

Tennyson M. Muindi
7/23/2021




REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	K. OHARA
DRAWN	S. WILBUR
CHECKED	T. MUINDI

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM


NBC CONTRACT NO. 308.05C
GEOTECHNICAL
OF-217 CONSOLIDATION CONDUIT
INSTRUMENTATION PLAN
STA. 0+00 TO STA. 8+00

SHEET
B-1
195130227


BY: SARNO, WENDY

PLOT DATE: Friday, July 23, 2021 4:43:56 PM

DWG FILE: C:\Users\Sarno\Box\Jobs\15960.0 NBC - CC IIIA-4 And IIIA-5\CADD\Drawings\CONTRACT\IIIA-5\Geotech\15902.dwg




PLAN
SCALE: 1" = 20'



PLAN
SCALE: 1" = 20'

KEY PLAN




GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY BSI ENGINEERING INC.
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID/ CITY OF PAWTUCKET.
- REFER TO SHEET B-4 FOR INSTRUMENTATION DETAILS AND NOTES.
- REFER TO SPECIFICATION SECTION 02295 FOR INSTRUMENTATION REQUIREMENTS.

INSTRUMENTATION LEGEND


SYMBOL	INSTRUMENT TYPE
	OBSERVATION WELL (OW)
	DEFORMATION MONITORING POINT (DMP TYPE 1)
	DEFORMATION MONITORING POINT (DMP TYPE 2)
	DEFORMATION MONITORING POINT (DMP TYPE 3)
	INCLINOMETER (INCL)
	UTILITY MONITORING POINT (UMP)
	SEISMOGRAPH

Tennyson M. Muindi
7/23/2021



FINAL DESIGN - JULY 2021

SCALE	AS SHOWN	WARNING	DESIGNED_K OHARA
		IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DRAWN_S WILBUR
			CHECKED_T MUINDI



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM



NBC CONTRACT NO 308.05C
GEOTECHNICAL
OF-217 CONSOLIDATION CONDUIT
INSTRUMENTATION PLAN
STA. 8+00 TO STA.16+00

SHEET


B-2

195130227


BY: SARNO, WENDY

PLOT DATE: Friday, July 23, 2021 4:44:27 PM

DWG FILE: C:\Users\Sarno\Box\Jobs\15960.0 NBC - CC IIIA-4 And IIIA-5\CADD\Drawings\CONTRACT\IIIA-5\Geotech\15960.0.dwg




KEY PLAN




GENERAL SHEET NOTES

- UTILITY INFORMATION DEPICTED, PROVIDED BY NATIONAL GRID
- FLOOD PLAIN INFORMATION IS FROM FEMA, PANEL NO. 44007C0307J. FLOOD PLAIN ELEVATIONS CONVERTED FROM VERTICAL DATUM NAVD 1988 TO NGVD 1929 AND ARE APPROXIMATELY:
 - NORTH OF DIVISION STREET BRIDGE: AE ELEVATION 12.8
 - SOUTH OF DIVISION STREET BRIDGE: VE ELEVATION 13.8
- WORK IS IN PROPERTY OWNED BY NATIONAL GRID
- REFER TO SHEET B-4 FOR INSTRUMENTATION DETAILS AND NOTES.
- REFER TO SPECIFICATION SECTION 02295 FOR INSTRUMENTATION REQUIREMENTS.



INSTRUMENTATION LEGEND	
SYMBOL	INSTRUMENT TYPE
	OBSERVATION WELL (OW)
	DEFORMATION MONITORING POINT (DMP TYPE 1)
	DEFORMATION MONITORING POINT (DMP TYPE 2)
	DEFORMATION MONITORING POINT (DMP TYPE 3)
	INCLINOMETER (INCL)
	UTILITY MONITORING POINT (UMP)
	SEISMOGRAPH

Tennyson M. Muindi
7/23/2021




REV	DATE	BY	DESCRIPTION

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	K O'HARA
DRAWN	S WILBUR
CHECKED	T MUINDI




FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM




NBC CONTRACT NO 308.05C
GEOTECHNICAL
OF-217 CONSOLIDATION CONDUIT
INSTRUMENTATION PLAN
STA. 16+00 TO STA. 18+88 AND STA. 0+00 TO STA. 4+48

SHEET
B-3
195130227



NOTES

1. MATERIAL AND INSTALLATION DETAILS FOR ALL APPLICABLE INSTRUMENTS SHOWN ON THIS DRAWING ARE PROVIDED IN SECTION 02295 OF THE SPECIFICATIONS.
2. INSTRUMENT LOCATIONS SHOWN ON THE DRAWINGS ARE APPROXIMATE. ACTUAL LOCATIONS SHALL BE ADJUSTED TO ACCOMMODATE FIELD CONDITIONS, AS APPROVED BY PM.
3. OBTAIN APPROVAL FROM PROPERTY OWNERS BEFORE INSTALLING ANY INSTRUMENTS ON PRIVATE PROPERTY.
4. OBTAIN PERMITS AND APPROVALS FOR ALL INSTRUMENTATION TO BE INSTALLED IN THE RIGHT-OF-WAY.
5. REMOVE INSTRUMENTS AND RESTORE LOCATIONS IN ACCORDANCE WITH THE SPECIFICATIONS.



REV	DATE	BY	DESCRIPTION

SCALE: NO SCALE

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: K. OHARA
 DRAWN: S. WILBUR
 CHECKED: T. MUNDI

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
 PHASE III COMBINED SEWER
 OVERFLOW PROGRAM


NBC CONTRACT NO 308.05C
 GEOTECHNICAL
 OF-217 CONSOLIDATION CONDUIT
 INSTRUMENTATION DETAILS

SHEET
 B-4
 195130227

Tennyson M. Mundi
 7/25/2021

TENNYSON M. MUNDI
 No. 12788
 REGISTERED PROFESSIONAL ENGINEER
 CIVIL


**MINIMUM DESIGN CRITERIA FOR LATERAL EARTH PRESSURES:
SURCHARGE (S)**



NOTES:

- FOR MINIMUM DESIGN CRITERIA FOR EXCAVATION SUPPORT NOTES, SEE SHEET B-6.
- SEE SHEET B-6, NOTE B10 FOR IMPERMEABLE VERSUS PERMEABLE SUPPORT WALL DESIGN CONSIDERATIONS.

**MINIMUM DESIGN CRITERIA FOR LATERAL EARTH PRESSURES:
SOIL (E) AND WATER (W)**




**MINIMUM DESIGN CRITERIA
FOR TEMPORARY EXCAVATION SUPPORT SYSTEM COMPONENTS**

STRUCTURE	VERTICAL LOADS		HORIZONTAL LOADS (E), (S) AND (W)	DESIGN LOADING COMBINATIONS AND ALLOWABLE UNIT STRESSES
	DEAD LOADS (DL)	LIVE LOADS (LL)		
WALL SYSTEM (ELEMENTS IN CONTACT WITH RETAINED EARTH)	WEIGHT OF WALL WEIGHT OF DECKING SYSTEM TO SUPPORT AASHTO AND CONSTRUCTION EQUIPMENT LOADING	REACTIONS FROM ALL LIVE LOADS INCLUDING APPLICABLE CONSTRUCTION EQUIPMENT LOADING, OTHER SURCHARGES, PEDESTRIAN WALKWAY LOADS, AND AASHTO HS20-44 LOADING, SEE NOTES	LOADS FROM LATERAL EARTH AND WATER PRESSURES AND LATERAL SURCHARGE PRESSURES [(E)+(S)+(W)] AXIAL LOADS FROM END WALL BRACING MEMBERS (E)+(S)+(W), WHERE APPLICABLE	100% OF [(DL)+(LL)+(E)+(S)+(W)] CONFORM TO ACI 318 FOR REINFORCED CONCRETE DESIGN
PRIMARY BRACING MEMBERS (MEMBERS CARRYING DIRECT LOADS INCLUDING WALES, STRUTS, CORNER BRACING, AND RAKERS)	WEIGHT OF PRIMARY BRACING MEMBER		LOADS FROM WALL SYSTEM [(E)+(S)+(W)] AXIAL LOADS FROM END WALLS [(E)+(S)+(W)], WHERE APPLICABLE	FOR PRIMARY BRACING MEMBERS: 100% OF [(DL)+(LL)+(E)+(W)+(S)] FOR WALLS: 120% OF ALLOWABLE UNIT STRESSES
SECONDARY BRACING MEMBERS FOR SUPPORT OF INTERNAL BRACING MEMBERS (IF NECESSARY)	WEIGHT OF SECONDARY BRACING MEMBER PLUS WEIGHT OF SUPPORTED PRIMARY BRACING MEMBERS, WHERE APPLICABLE	AXIAL LOAD EQUAL TO 3% OF THE DESIGN AXIAL LOAD IN THE MORE HEAVILY LOADED ADJACENT PRIMARY BRACING MEMBER	AXIAL LOAD EQUAL TO 3% OF THE DESIGN AXIAL LOAD IN THE MORE HEAVILY LOADED ADJACENT PRIMARY BRACING MEMBER	120% OF ALLOWABLE UNIT STRESSES

PROPERTIES OF RETAINED SOIL

MATERIAL	TOTAL UNIT WEIGHT, γ (PCF)	EFFECTIVE UNIT WEIGHT, γ' (PCF)	FRICTION ANGLE	UNDRAINED SHEAR STRENGTH S_u (PSF)	AT-REST PRESSURE COEFFICIENT K_o	ACTIVE PRESSURE COEFFICIENT K_a	PASSIVE PRESSURE COEFFICIENT K_p
FILL	125	63	32°	NA	0.47	0.31	3.26
ALLUVIAL	120	58	30°	NA	0.5	0.33	3.00
GLACIOFLUVIAL	125	63	32°	NA	0.47	0.31	3.26
GLACIAL TILL AND COMPLETELY TO HIGHLY WEATHERED BEDROCK	135	73	34°	NA	0.44	0.28	3.54

Tennyson M. Muindi
7/25/2021



REV	DATE	BY	DESCRIPTION

SCALE	WARNING	DESIGNED
NO SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	K. OHARA
		DRAWN
		A. SMITH
		CHECKED
		T. MUINDI

FINAL DESIGN - JULY 2021



NBC CONTRACT NO 308.05C
GEOTECHNICAL
OF-217 CONSOLIDATION CONDUIT
MINIMUM DESIGN CRITERIA FOR EXCAVATION SUPPORT

NOTES FOR ANALYSIS AND DESIGN

A. GENERAL

- A1. DUE TO A VARIETY OF PAST USES IN THE AREA, NUMEROUS OBSTRUCTIONS WILL BE ENCOUNTERED DURING INSTALLATION OF EXCAVATION SUPPORT SYSTEMS. TYPES OF OBSTRUCTIONS ANTICIPATED TO BE ENCOUNTERED INCLUDE: BOULDERS, GRANITE, CONCRETE OR BRICK FOUNDATION WALLS, AND CONCRETE FLOORS FROM PREVIOUS STRUCTURES, ABANDONED WOOD PILES, TANK FOUNDATIONS AND VARIOUS OTHER DEMOLITION AND CONSTRUCTION DEBRIS.
- A2. FLEXIBLE WALL SYSTEMS ARE CONSIDERED TO BE SOLDIER PILE AND LAGGING WALLS AND SIMILAR SUPPORT SYSTEMS. RIGID WALL SYSTEMS ARE CONSIDERED TO BE SECANT PILE WALLS. WALL SYSTEM TO BE USED FOR INSTALLATION OF APPROACH CHANNEL, GATE AND SCREENING STRUCTURE, GSS-2 AND JUNCTION CHAMBER SHALL UTILIZE SECANT PILES TO PROVIDE AN IMPERMEABLE EXCAVATION.
- A3. METHODS OF PERMITTED ANALYSIS INCLUDE:
 - LIMIT EQUILIBRIUM METHOD SHALL BE USED FOR STRENGTH DESIGN .
 - NONLINEAR ANALYSIS USING ELASTO-PLASTIC WINKLER SPRINGS SHALL BE USED FOR DEFORMATION CONTROLLED DESIGN .
- A4. TEMPORARY EXCAVATION SUPPORT SYSTEMS SHALL BE DESIGNED AND CONSTRUCTED BY THE CONTRACTOR IN ACCORDANCE WITH CURRENT ENGINEERING PRACTICE, THE REQUIREMENTS OF THE CONTRACT DRAWINGS, AND APPLICABLE SPECIFICATIONS.
- A5. CONVENTIONAL CONSTRUCTION METHODS SHALL BE USED TO CONSTRUCT THE BELOW-GRADE SPACE. THE TEMPORARY EXCAVATION SUPPORT SYSTEM WALLS SHALL BE RESTRAINED BY TEMPORARY BRACING, AS NECESSARY, AS THE EXCAVATION IS CONDUCTED, AND THE PERMANENT SUBSTRUCTURE AND FOUNDATIONS SHALL BE CONSTRUCTED WITHIN THE TEMPORARY EXCAVATION SUPPORT SYSTEM.
- A6. DRIVING OR VIBRATING IS NOT PERMITTED TO INSTALL EXCAVATION SUPPORT WALL ELEMENTS.
- A7. THE CRITERIA ON SHEET B-5 AND THIS SHEET ARE MINIMUM CRITERIA. THE CONTRACTOR SHALL UTILIZE ADDITIONAL OR MORE CONSERVATIVE CRITERIA AS REQUIRED, TO COMPLETE THE WORK IN ACCORDANCE WITH THE CONTRACT REQUIREMENTS.
- A8. THE CONTRACTOR SHALL REVIEW THE DESIGN CRITERIA INCLUDED ON DRAWING B-6 AND CONDUCT WORK AS NECESSARY TO COMPLETE THE DESIGN. THE CONTRACTOR'S FINAL DESIGN AND ANY PROPOSED MODIFICATIONS WILL BE REVIEWED BY THE PROGRAM MANAGER/CONSTRUCTION MANAGER (PM/CM) IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONTRACT DRAWINGS AND APPLICABLE SPECIFICATIONS. THE CONTRACTOR SHALL SUBMIT FOR REVIEW BY THE PM/CM, COMPLETE COMPUTATIONS, CROSS-SECTIONS, CONSTRUCTION SCHEDULE AND SEQUENCE, AND WORKING DRAWINGS FOR TEMPORARY EXCAVATION SUPPORT SYSTEMS. THE DESIGN SHALL BE IN ACCORDANCE WITH THE MINIMUM CRITERIA SPECIFIED AND INDICATED ON THIS DRAWING AND GOOD ENGINEERING PRACTICE, AND WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. ALL COMPUTATIONS AND DESIGNS SHALL BE PREPARED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF RHODE ISLAND, RETAINED BY THE CONTRACTOR. THE PM'S/CM'S REVIEW WILL SOLELY BE TO DETERMINE COMPLIANCE WITH THE CONTRACT DOCUMENTS.
- A9. TEMPORARY EXCAVATION SUPPORT SYSTEMS SHALL BE ANALYZED AND DESIGNED FOR ALL CONDITIONS THAT CAN OCCUR DURING THE VARIOUS STAGES OF CONSTRUCTION. THESE CONDITIONS MAY INCLUDE: TEMPORARY OR PERMANENT ALTERATION OF THE SOILS, IN-SITU SOIL PROPERTIES CAUSED BY THE SELECTED METHODS OF CONSTRUCTION, INITIAL CANTILEVER CONDITION, INSTALLATION, RELOCATION, AND REMOVAL OF TEMPORARY BRACING, TIME RELATED EFFECTS, SOIL EXCAVATION BELOW BRACING ALREADY IN PLACE, SHRINKAGE OF CONCRETE, DEWATERING OF EXCAVATION, AND LOAD TRANSFER TO PERMANENT STRUCTURE.
- A10. ALL LATERAL PRESSURES ARE IN POUNDS PER SQUARE FOOT (PSF).
- A11. MAXIMUM LATERAL DEFORMATION ALONG FULL DEPTH OF THE EXCAVATION SHALL NOT EXCEED $0.0025 \times$ EXCAVATION DEPTH OR 1/2", WHICHEVER IS GREATER.
- A12. IF THE LATERAL LOADING CONDITIONS ON OPPOSITE SIDES OF THE EXCAVATION ARE NOT EQUAL, THE TEMPORARY EXCAVATION SUPPORT SYSTEM DESIGN SHALL ACCOUNT FOR THE UNBALANCED LOADING. UNBALANCED LOADING COULD RESULT FROM UNEQUAL EXCAVATION LEVELS OR DIFFERENT LATERAL PRESSURE DISTRIBUTIONS AT THE PERIMETER OF THE SITE.

- A13. EXCAVATION AND BRACING RESTRICTIONS SHALL BE INCORPORATED INTO THE TEMPORARY EXCAVATION SUPPORT SYSTEM DESIGN AS FOLLOWS:
 - THE MAXIMUM VERTICAL DISTANCE BETWEEN THE LOWEST TEMPORARY BRACE AND THE EXCAVATION SUBGRADE SHALL NOT EXCEED 15 FT.
 - EXCAVATION FOR A LOWER SUBGRADE ELEVATION MAY NOT BEGIN UNTIL THE BRACE LEVEL ABOVE HAS BEEN INSTALLED.
- A14. THE MAXIMUM HEIGHT OF EXCAVATION FACE SHALL NOT EXCEED 4 FEET PRIOR TO INSTALLATION OF TEMPORARY LAGGING OR OTHER SHORING SYSTEM.
- A15. THE CONTRACTOR MAY BE REQUIRED TO ADJUST CONSTRUCTION OPERATIONS IF THE ENGINEER CONSIDERS THAT BASED ON INSTRUMENTATION READINGS, EXCESSIVE SETTLEMENTS, DEFORMATION AND/OR DEFLECTIONS OCCUR.

B. LATERAL DESIGN PRESSURES

- B1. MINIMUM DESIGN LOADING CONDITIONS SHALL BE DETERMINED BY ADDING TOGETHER THE LOADING DIAGRAMS SHOWN ON DRAWING B-5 FOR SOIL (E) AND WATER (W), WHERE APPLICABLE, AND THE COMBINATION OF APPLIED SURCHARGES (S). TRAFFIC AND CONSTRUCTION EQUIPMENT LOAD SHALL BE ASSUMED ON ANY SIDE OF THE WALL THAT IS ACCESSIBLE.
- B2. UNLESS INDICATED OTHERWISE, ALL LOADS FOR A GIVEN CONDITION MUST BE ADDED SO AS TO FORMULATE THE MAXIMUM TOTAL DESIGN LOADING.
- B3. LATERAL PRESSURE DUE TO TRAFFIC AND CONSTRUCTION EQUIPMENT IS BASED ON AN ASSUMED SURFACE SURCHARGE OF 600 PSF ACTING OVER A 20-FT. WIDE INFLUENCE AREA. THE CONTRACTOR SHALL DETERMINE IF THE 600 PSF VERTICAL SURCHARGE LOAD IS SUFFICIENT, AND SHALL MAKE ADDITIONAL ANALYSES FOR MORE CRITICAL CONSTRUCTION EQUIPMENT LOADING CONDITIONS, AND ACCOUNT FOR THESE IN THE DESIGN OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM. THE CONTRACTOR SHALL ACCOUNT FOR CRITICAL SURCHARGE LOADINGS OR OTHER LOADING CONDITIONS NOT DESCRIBED HEREIN IN DESIGN AND CONSTRUCTION, SUBJECT TO THE REVIEW OF THE PM, PRIOR TO THE APPLICATION OF THE LOADING.
- B4. FOR UNIFORM VERTICAL SURCHARGE LOADING, LATERAL PRESSURES ARE DETERMINED AT VARIOUS DEPTHS BELOW THE CORNER OF THE LOADED AREA. WHEN THE RECTANGULAR LOADED AREA IS LOCATED AT A DISTANCE BEHIND THE WALL, THE PRINCIPLE OF LOAD SUPERPOSITION SHALL BE USED TO DETERMINE LATERAL PRESSURES AGAINST THE WALL. REFER TO SOIL MECHANICS, BY LAMBE AND WHITMAN, PAGE 104, FOR AN EXAMPLE OF USING THE PRINCIPLE OF SUPERPOSITION OF LOADS.
- B5. PASSIVE EARTH PRESSURES SHALL BE COMPUTED USING RANKINE EARTH PRESSURE THEORY AND THE SOIL PROPERTIES INDICATED ON DRAWING B-5.
- B6. THE TEMPORARY EXCAVATION SUPPORT SYSTEM SHALL BE CONSIDERED TO BE SUBJECTED TO LATERAL SURCHARGE PRESSURES FROM LOADS ASSOCIATED WITH ADJACENT STRUCTURES AND GRADE INCREASES IF LOCATED WITHIN THE INFLUENCE ZONE. THE INFLUENCE ZONE IS DEFINED AS A 1H:1V LINE DRAWN FROM THE BOTTOM OF THE FINAL EXCAVATION LEVEL AT THE OUTSIDE FACE OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM UPWARD AND OUTWARD AWAY FROM THE SITE TOWARD THE ADJACENT STRUCTURE OR GRADE INCREASE.
- B7. VALUES OF P ARE IN POUNDS PER SQUARE FOOT PER LINEAR FOOT OF WALL (PSF/LF).
- B8. THE EXISTING GROUNDWATER LEVEL VARIES AND MUST BE DETERMINED ON A SITE SPECIFIC BASIS FOR EACH TEMPORARY EXCAVATION SUPPORT DESIGN. THE DESIGN MUST ACCOUNT FOR THE MOST CRITICAL LOADING CONDITION, INCLUDING THE MAXIMUM LOWERING OF THE GROUNDWATER TABLE AND THE MAXIMUM WATER INGRESS INTO THE EXCAVATION. REFER TO SPECIFICATIONS FOR GROUNDWATER CONTROL REQUIREMENTS.
- B9. STRESSES DUE TO TEMPERATURE FLUCTUATIONS SHALL BE TAKEN INTO ACCOUNT IN THE DESIGN OF BRACING MEMBERS AND LOADS RESULTING FROM FROZEN SOILS SHALL BE CONSIDERED IF APPROPRIATE.
- B10. IF AN IMPERMEABLE EXCAVATION SUPPORT WALL IS INSTALLED, THEN EFFECTIVE LATERAL EARTH PRESSURES PLUS HYDROSTATIC PRESSURE SHALL BE USED FOR DESIGN. IF A PERMEABLE WALL SYSTEM IS INSTALLED THEN TOTAL LATERAL EARTH PRESSURES MUST BE USED FOR DESIGN.

C. BRACING MEMBERS

- C1. DESIGN OF BRACING MEMBERS SHALL SATISFY THE MOST CRITICAL CONDITIONS ANTICIPATED DURING THE CONSTRUCTION SEQUENCE
- C2. TEMPORARY INTERNAL BRACING MEMBERS (STRUTS, RAKERS, CORNER BRACES, WALES) SHALL BE STRUCTURAL GRADE STEEL, REINFORCED CONCRETE, OR A COMBINATION. NO WOOD SHIMS SHALL BE USED.
- C3. TEMPORARY BRACING MEMBERS SHALL NOT BE EMBEDDED IN PERMANENT STRUCTURES.
- C4. TEMPORARY BRACING MEMBERS SHALL BE REMOVED AT AN APPROPRIATE STAGE OF CONSTRUCTION AND IN SUCH A MANNER AS TO AVOID IMPACT LOADING ON NEW AND EXISTING STRUCTURES AND/OR PIPELINES OR ON OTHER MEMBERS OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM.
- C5. ALL INTERNAL BRACING SHALL BE PRESTRESSED TO AT LEAST 50 PERCENT OF MAXIMUM DESIGN LOADS WHERE PASSIVE SOIL PRESSURE LIMIT PERMITS.


D. TEMPORARY EXCAVATION SUPPORT SYSTEM TOE STABILITY DESIGN

- D1. THE TOE OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM PRIMARY ELEMENTS SHALL EXTEND A SUFFICIENT DISTANCE BELOW THE BOTTOM OF THE EXCAVATION IN ORDER TO LIMIT MOVEMENT AND TO ENSURE BOTTOM STABILITY AND ADEQUATE VERTICAL LOAD CAPACITY.
- D2. THE TOE OF THE TEMPORARY EXCAVATION SUPPORT SYSTEM WALL SHALL EXTEND A SUFFICIENT DISTANCE BELOW THE LOWEST EXCAVATION LEVEL TO PROVIDE VERTICAL LOAD CARRYING CAPACITY AND LIMIT HORIZONTAL MOVEMENT OF THE WALL. LOAD CARRYING CAPACITY OF THE WALL SHALL BE DETERMINED BY CONSIDERING BRACING SYSTEM LOADS. ONLY THE LENGTH OF THE WALL BELOW THE BOTTOM OF THE EXCAVATION SHALL BE CONSIDERED IN SKIN FRICTION AND/OR ADHESION CALCULATIONS.
- D3. EVALUATION OF THE REQUIRED TOE EMBEDMENT BELOW EXCAVATION SUBGRADE SHALL BE BASED ON THE NET RANKINE ACTIVE AND PASSIVE PRESSURES USING THE APPROPRIATE PRESSURE COEFFICIENTS PRESENTED IN THE SOIL PARAMETERS TABLE AND APPLICABLE SURCHARGE LOADING. FOR DETERMINING TOE EMBEDMENT, EITHER A FACTOR OF SAFETY EQUAL TO 1.5 SHALL BE APPLIED TO THE PASSIVE PRESSURE COEFFICIENT OR THE CALCULATED MINIMUM TOE EMBEDMENT SHALL BE INCREASED BY 20%.
- D4. IN SITUATIONS WHERE THE RETAINED SOIL IS NOT DEWATERED, THE DETERMINATION OF TOE PENETRATION MUST CONSIDER THE POTENTIAL FOR SEEPAGE GRADIENTS WHICH COULD CAUSE INSTABILITY AT THE BOTTOM OF THE EXCAVATION AND REDUCE THE STRENGTH OF SOILS AT THE TOE OF THE WALL.

E. CRITERIA FOR PROTECTION OF STRUCTURES

- E1. STRUCTURES INCLUDE EXISTING BUILDINGS, BRIDGES, UTILITIES, PAVEMENTS AND OTHER FACILITIES.
- E2. PROTECTION CRITERIA PRESENTED FOR FLEXIBLE WALL SYSTEMS ASSUME AVERAGE EXCAVATION AND BRACING PROCEDURES ARE UTILIZED.
- E3. EVALUATION OF PROTECTION REQUIREMENTS FOR STRUCTURES IS DEPENDENT ON MANY FACTORS, WHICH INCLUDE IMPLEMENTED CONSTRUCTION PROCEDURES AND DETAILS, MAGNITUDE AND TYPES OF MOVEMENT ANTICIPATED, SUBSURFACE CONDITIONS, AND PROXIMITY OF STRUCTURES TO THE EXCAVATION. AT LOCATIONS WHERE STRUCTURES ARE FOUNDED WITHIN THE ZONE OF INFLUENCE, AN EVALUATION OF PROTECTION REQUIREMENTS SHALL BE CONDUCTED BY THE CONTRACTOR ON A CASE BY CASE BASIS, CONSIDERING ALL RELEVANT FACTORS.
- E4. POSITIVE MEANS OF PROTECTION ARE DEFINED AS MEASURES WHICH MAY BE TAKEN TO CONTROL GROUND MOVEMENTS TO WITHIN ACCEPTABLE LIMITS OR, MEASURES WHICH PROVIDE ADDITIONAL SUPPORT FOR AFFECTED STRUCTURES. EVALUATION OF PROTECTION REQUIREMENTS FOR STRUCTURES GENERALLY BEGINS WITH SELECTING AND IMPLEMENTING EARTH SUPPORT, EXCAVATION AND BRACING TECHNIQUES TO MINIMIZE GROUND MOVEMENTS. IF ANTICIPATED GROUND MOVEMENTS ARE STILL EXPECTED TO EXCEED ACCEPTABLE LIMITS, THEN INDIRECT OR DIRECT STRUCTURE PROTECTION MEASURES SHALL BE IMPLEMENTED BY THE CONTRACTOR ON A CASE BY CASE BASIS. INDIRECT PROTECTION MEASURES INCLUDE SUCH PROCEDURES AS PROVIDING A STIFFER RETAINING SYSTEM, COMPACTION GROUTING OR SLAB/FOOTING JACKING. DIRECT PROTECTION MEASURES INCLUDE SUCH PROCEDURES AS STANDARD UNDERPINNING PITS.
- E5. THE CONTRACTOR SHALL CONSIDER THE EFFECTS OF VIBRATIONS ON ADJACENT STRUCTURES FROM INSTALLATION OF THE TEMPORARY EARTH SUPPORT SYSTEM.
- E6. REFER TO SPECIFICATION SECTION 02295 FOR GEOTECHNICAL INSTRUMENTATION RESPONSE LEVELS AND READING FREQUENCIES.


PROTECTION CRITERIA



LEGEND


- ZONE OF INFLUENCE: DEFINES A ZONE WITHIN WHICH SOIL MOVEMENTS ARE EXPECTED TO OCCUR AS A RESULT OF CONSTRUCTION. PROTECTION OF STRUCTURES FOUNDED OR LOCATED WITHIN THIS ZONE SHALL BE CONSIDERED BY THE CONTRACTOR.
- PROTECTION ZONE A: STRUCTURES WHICH ARE FOUNDED OR LOCATED WITHIN THIS ZONE GENERALLY WILL REQUIRE SOME POSITIVE MEANS OF PROTECTION. REFER TO NOTE E.4 FOR DEFINITION OF POSITIVE MEANS OF PROTECTION.
- PROTECTION ZONE B: STRUCTURES WHICH ARE FOUNDED OR LOCATED WITHIN THIS ZONE GENERALLY WILL NOT REQUIRE PROTECTION, UNLESS THE STRUCTURES ARE PARTICULARLY SENSITIVE TO MOVEMENTS, OR SUBSURFACE SOILS ARE SENSITIVE TO CONSTRUCTION VIBRATION.

Tennyson M. Mundi
7/25/2021




REV	DATE	BY	DESCRIPTION

SCALE
NO SCALE



DESIGNED K. OHARA
DRAWN D. NOWAK
CHECKED T. HENNINGS

FINAL DESIGN - JULY 2021




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
GEOTECHNICAL
OF-217 CONSOLIDATION CONDUIT
NOTES FOR ANALYSIS AND DESIGN

SHEET
B-6
195130227


OFFSET REQUIRED
CONSIDERING INSTALLATION
TOLERANCES (SEE NOTE 1)



SECANT PILE SHAFT PLAN AT GROUND LEVEL

SCALE: NO SCALE

OFFSET REQUIRED
CONSIDERING INSTALLATION
TOLERANCES (SEE NOTE 1)




SECANT PILE SHAFT PLAN AT MICROTUNNEL SPRINGLINE

SCALE: NO SCALE

NOTES


1. MTBM LAUNCHING SHAFTS AT MH-217-6 AND MH-217-7 SHALL BE CONSTRUCTED USING THE SECANT PILE WALL METHOD AND PROVIDE A MINIMUM 20-FOOT CLEAR OF INSIDE DIAMETER CONSIDERING INSTALLATION TOLERANCES.
2. THIS DRAWING DEPICTS A REFERENCE DESIGN FOR WHICH THE CONTRACTOR SHALL DEVELOP TO A FINAL DESIGN. THE CONTRACTOR'S FINAL DESIGN SHALL INCORPORATE DESIGN AND CONSTRUCTION REQUIREMENTS SPECIFIED HERE AND ELSEWHERE IN THE CONTRACT DOCUMENTS.
3. REFERENCE DESIGN ASSUMPTIONS:
 - a. PLAIN CONCRETE DESIGN IN ACCORDANCE WITH ACI-318-19
 - b. $F_c = 4000$ PSI
 - c. INSTALLATION TOLERANCES:
 - i. IN-PLAN LOCATION: 1/2-INCH MAXIMUM
 - ii. OUT-OF-VERTICALITY: 0.5% MAXIMUM
 - d. DESIGN PRESSURES:
 - i. AT REST EARTH PRESSURES
 - ii. GROUND WATER LEVEL AT EL. 15.0
 - iii. SURCHARGE (BALANCED AND UNBALANCED)
 - e. SHAFT DESIGN DOES NOT CONSIDER MTBM JACKING LOADS OR REINFORCEMENT AT MTBM PENETRATION LOCATIONS
3. CONTRACTOR TO DESIGN AND PROVIDE SOFT EYES IN SHAFT WALL AT MTBM PENETRATIONS AND REINFORCEMENT NECESSARY TO SUPPORT SAME PENETRATIONS THROUGH THE SHAFT WALL.
4. CONTRACTOR TO DESIGN SHAFT TO ACCOMMODATE ANTICIPATED MTBM JACKING LOADS.
5. CONTRACTOR TO DESIGN AND PROVIDE A REINFORCED CONCRETE SHAFT CAPPING BEAM.
6. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
7. SHAFT AT MH-217-6 TO BE USED FOR TWO MTBM LAUNCHES
8. SHAFT AT MH-217-7 TO BE USED FOR ONE MTBM LAUNCH TO RECEIVING PIT NEAR STA. 16+70; AND TO RECEIVE ONE MTBM LAUNCHED FROM SHAFT AT MH-217-6.

BOTTOM OF SECANT WALL TO BE A MINIMUM OF 5 FEET BELOW BOTTOM OF EXCAVATION OR EMBEDDED 5 FEET INTO MODERATELY WEATHERED TO FRESH BEDROCK AS DEFINED BY ISRM WEATHERING CLASSIFICATION SYSTEM WHICHEVER IS DEEPER.



A SECTION
GT-008 SCALE: NO SCALE

Tennyson M. Muindi
7/23/2021




REV	DATE	BY	DESCRIPTION

SCALE
NO SCALE

WARNING
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED D.NOWAK
DRAWN D.NOWAK
CHECKED T.HENNINGS

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec PARE

NBC CONTRACT NO 308.05C
GEOTECHNICAL
OF-217 CONSOLIDATION CONDUIT
SECANT PILE SHAFT REFERENCE DESIGN

SHEET

B-7


195130227

BY: JAMIE PAYNE

PLOT DATE: Tuesday, July 27, 2021 10:15:05 AM


DWG FILE: J:\6412 NBC CSD Consolidation Conduits\Drawing Files\Traffic Management\TMP 1A.dwg

KEY PLAN




GENERAL SHEET NOTES

SHEET KEYNOTES




TAFT STREET NORTHBOUND SIDEWALK AND BIKE LANE CLOSURE DETAIL



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE
NO SCALE



DESIGNED H. PERALTA
DRAWN T. JOUBERT
CHECKED J. D'ALELIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM


NBC CONTRACT NO 308.05C
TRAFFIC
OF-217 CONSOLIDATION CONDUIT
TEMPORARY TRAFFIC CONTROL PLAN

SHEET
T-1
195130227


BY: JAMIE PAYNE

PLOT DATE: Tuesday, July 27, 2021 10:15:22 AM

DWG FILE: J:\6412 NBC Consolidation Conduits\Drawing Files\Traffic Management\TMP_1B.dwg




SIDEWALK CLOSURE DETAIL



TAFT STREET NORTHBOUND LANE CLOSURE WITH LANE SHIFT DETAIL

KEY PLAN



GENERAL SHEET NOTES

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS, 2019 EDITION, AS APPLICABLE.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES.

3. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AND UTILITIES AT ALL TIMES.

4. ALL TRAFFIC CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE DURATION OF THE WORK.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES AND STRUCTURES.

6. ALL MATERIALS AND METHODS SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

7. THE CONTRACTOR SHALL MAINTAIN ADEQUATE COMMUNICATIONS WITH THE PUBLIC AND ADJACENT PROPERTIES.

8. ALL WORK SHALL BE COMPLETED WITHIN THE SPECIFIED TIME FRAME.

9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL TEMPORARY TRAFFIC CONTROL DEVICES AT THE END OF THE PROJECT.

10. ALL WORK SHALL BE SUBJECT TO THE SUPERVISION AND INSPECTION OF THE ENGINEER.

SHEET KEYNOTES

1. SIDEWALK CLOSED (24"x12")

2. TEMP. PEDESTRIAN CROSSING (12" WHITE WATERBORNE PAINT PAVEMENT MARKINGS)

3. END ROAD WORK (36"x18")

4. ROAD WORK AHEAD (36"x36")

5. BIKE LANE CLOSED AHEAD (36"x36")

6. MAY USE FULL LANE (30"x30")


7. 11.0' MINIMUM TRAVEL LANES

8. DRUM BARRELS AT 20' SPACING (TYP.) RI STD. 26.2.0

9. WORK ZONE

10. 100' SHIFTING TAPER

11. 100' SHOULDER TAPER



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	NO SCALE
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	H. PERALTA
DRAWN	T. JOUBERT
CHECKED	J. D'ALELIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
TRAFFIC

OF-217 CONSOLIDATION CONDUIT
TEMPORARY TRAFFIC CONTROL PLAN

SHEET T-2
195130227

BY: JAIME PAYNE

PLOT DATE: Tuesday, July 27, 2021 10:15:33 AM

DWG FILE: J:\6412 NBC Consolidation Conduits\Drawing Files\Traffic Management\TMP DETAILS.dwg

Meaning of Symbols on Typical Application Diagrams

	Arrow board		Shadow vehicle
	Arrow board support or trailer (shown facing down)		Sign (shown facing left)
	Changeable message sign or support trailer		Surveyor
	Channelizing device		Temporary barrier
	Crash cushion		Temporary barrier with warning light
	Direction of temporary traffic detour		Traffic or pedestrian signal
	Direction of traffic		Truck-mounted attenuator
	Flagger		Type 3 barricade
	High-level warning device (Flag tree)		Warning light
	Longitudinal channelizing device		Work space
	Luminaire		Work vehicle
	Pavement markings that should be removed for a long-term project		

Meaning of Letter Codes on Typical Application Diagrams


Road Type	Distance Between Signs**		
	A	B	C
Urban (low speed)*	100 feet	100 feet	100 feet
Urban (high speed)*	350 feet	350 feet	350 feet
Rural	500 feet	500 feet	500 feet
Expressway / Freeway	1,000 feet	1,500 feet	2,640 feet

* Speed category to be determined by highway agency
 ** The column headings A, B, and C are the dimensions shown in Figures 6H-1 through 6H-3. The A dimension is the distance from the transition or point of restriction to the first sign. The B dimension is the distance between the first and second signs. The C dimension is the distance between the second and third signs. (The "first sign" is the sign in a three-sign series that is closest to the TTC zone. The "third sign" is the sign that is furthest upstream from the TTC zone.)





Formulas for Determining Taper Length

Speed (S)	Taper Length (L) in feet
40 mph or less	$L = \frac{WS^2}{60}$
45 mph or more	$L = WS$

Where: L = taper length in feet
 W = width of offset in feet
 S = posted speed limit, or off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in mph



- ### TEMPORARY TRAFFIC CONTROL GENERAL NOTES:
- ALL MAINTENANCE AND PROTECTION OF TRAFFIC CONTROL SETUPS, SIGNS, CHANNELIZING DEVICES, ETC., SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION.
 - ALL SIGN MOUNTINGS FOR TEMPORARY AND CONSTRUCTION SIGNS SHALL BE IN ACCORDANCE WITH THE R.I.D.O.T STANDARD SPECIFICATIONS, LATEST EDITION.
 - THE CONTRACTOR SHALL COVER ALL EXISTING AND/OR TEMPORARY SIGNS THAT ARE NOT RELEVANT TO THE TRAFFIC CONTROL REQUIRED DURING ANY PARTICULAR STAGE OF THE CONTRACT.
 - ADVANCE FLAGPERSON SIGNS (W20-7A) SHALL BE USED IN ADVANCE OF ANY POINT AT WHICH A FLAGPERSON OR A POLICE OFFICER HAS BEEN STATIONED TO CONTROL TRAFFIC. WHEN NEEDED, AN APPROPRIATE DISTANCE MESSAGE MAY BE DISPLAYED ON A SUPPLEMENTAL PLAQUE (24"x18") BELOW THE FLAGPERSON SYMBOL SIGN. THE SIGN SHALL BE PROMPTLY REMOVED OR COVERED WHENEVER THE FLAGPERSON IS NOT AT THE STATION.
 - POLICE OFFICERS (AND NOT FLAGPERSONS) SHALL BE UTILIZED WHEN WORK WILL IMPACT SIGNALIZED INTERSECTIONS AND LIMITED ACCESS HIGHWAYS.
 - POLYETHYLENE DRUMS SHALL BE UTILIZED AS A CHANNELIZING DEVICE WHEN A TRAFFIC CONTROL SET-UP IS TO REMAIN BEYOND WORKING HOURS WHEN NO WORKERS ARE PRESENT. CONES SHALL BE UTILIZED WHEN A TRAFFIC CONTROL SET-UP IS TO REMAIN ONLY DURING WORKING HOURS AND IS SUBSEQUENTLY BROKEN DOWN AT THE END OF THE WORKDAY.
 - ARROW PANELS SHALL BE SET IN THE FLASHING FOUR CORNERS CAUTION MODE UNLESS UTILIZED FOR A MERGING TAPER. ARROW PANELS SET IN THE FLASHING MODE SHALL NOT BE UTILIZED FOR LANE SHIFTS.
 - TEMPORARY CONSTRUCTION SIGNS AND OTHER WORKZONE TRAFFIC CONTROL DEVICES THAT ARE DAMAGED OR REQUIRE RELOCATION SHALL BE REPLACED AND/OR RELOCATED UNDER THE APPROPRIATE PAY ITEM.
 - THE PRIVATE VEHICLE OF CONSTRUCTION WORKERS SHALL NOT BE PARKED ON THE TRAVEL LANES OR SHOULDERS. THEY MAY BE PARKED WITHIN THE STATE AND/OR CITY RIGHT-OF-WAY ONLY IN AREAS 30' BEYOND THE OUTSIDE EDGE OF THE TRAVEL LANES AND/OR IN AREAS APPROVED BY THE ENGINEER.
 - TEMPORARY CONSTRUCTION SIGNS AND OTHER TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE INSTALLED PRIOR TO THE START OF WORK IN ANY AREA OPEN TO TRAFFIC, AND SHALL BE REMOVED AS SOON AS PRACTICAL WHEN THEY ARE NO LONGER APPROPRIATE.
 - THE INTENDED VEHICLE PATHS THROUGH EACH WORK ZONE SHALL BE CLEARLY MARKED AT ALL TIMES. WATERBORNE PAVEMENT MARKINGS SHALL BE INSTALLED BEFORE THE END OF THE WORK SHIFT ON ALL COLD-PLANNED AND NEW ROADWAY SURFACES THAT WILL BE OPENED TO TRAFFIC AT THE END OF THE SHIFT.
 - THE CONTRACTOR SHALL NOTIFY EACH ABUTTER AT LEAST 48 HOURS IN ADVANCE OF THE START OF ANY WORK THAT WILL REQUIRE TEMPORARY INTERFERENCE WITH OR CLOSURE OF ACCESS.
 - ONE SIDEWALK SHALL REMAIN OPEN AT ALL TIMES ALONG ROOSEVELT AVENUE EXTENSION AND TAFT STREET.




CHRISTOPHER R. CRONIN
 No. 8509
 REGISTERED PROFESSIONAL ENGINEER (CIVIL)


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_III-5_DIVERSION STRUCTURES_PLAIN\05B6TEDN\Kingday July 27, 2021 10:17:56 AM
 BY: JAMIE PAYNE

GENERAL SHEET NOTES

1. VERTICAL DATUM FOR PROJECT IS NGVD29.




SITE PLAN VIEW
SCALE: 1" = 4'-0"




PLAN VIEW
SCALE: 1/4" = 1'-0"

NOTE:
THE FULL INNER CIRCUMFERENCE OF THE EXISTING 34" SEWER SHALL BE SPRAY COATED WITH A MONOLITHIC GEOPOLYMER STRUCTURAL LINING TO A DISTANCE OF 20 LF FROM THE INTERIOR FACE OF THE PROPOSED STRUCTURE




A SECTION
SCALE: 1/4" = 1'-0"

NOTE:
THE FULL CIRCUMFERENCE OF THE EXISTING 34" SEWER SHALL BE COATED WITH A MONOLITHIC GEOPOLYMER LINING TO A DISTANCE OF 20 LF FROM THE INTERIOR FACE OF THE PROPOSED STRUCTURE



B SECTION
SCALE: 1/4" = 1'-0"



REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN	WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE
DESIGNED	C. CRONIN	DRAWN	J. PAYNE
CHECKED	J. D'ALELIO		

FINAL DESIGN - JULY 2021









NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 RELOCATION STRUCTURE
PLAN AND SECTIONS

GENERAL SHEET NOTES

1. VERTICAL DATUM FOR PROJECT IS NGVD29.
2. DETAIL TYPICAL AT PRECAST/C.I.P. WALL INTERFACE. ROUGHEN TO 1/4" MIN.
3. #5 CORNER BARS SHALL BE SET BY PRECASTER. CONTRACTOR MAY COORDINATE TO HAVE THREADED INSERTS INSTALLED AS AN ALTERNATIVE.



BY: JAIMIE PAYNE
DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet Set\PAWT_III-5_DIVERSION STRUCTURES_PLAN\015616TENT.dwg, August 17, 2021 1:26:46 PM

REV	DATE	BY	DESCRIPTION
2	8/19/21	JP	ADDENDUM #1
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	J. PAYNE
CHECKED	J. D'ALESSIO


FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM


NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 DIVERSION STRUCTURE
PLAN AND SECTIONS

SHEET
S-2
195130227




GENERAL SHEET NOTES

1. VERTICAL DATUM FOR PROJECT IS NGVD29.




F SITE PLAN VIEW
SCALE: 1" = 4'-0"




2 DETAIL
S-3 SCALE: 1/2" = 1'-0"


NOTE: THE WORK AT THE OUTFALL IS ABOVE THE MEAN HIGH WATER LINE AND WILL BE IMPACTED BY THE TIDES. CONTRACTOR SHALL PLAN AND PROTECT THE WORK ACCORDINGLY.



F SECTION
S-3 SCALE: 1/4" = 1'-0"



G SECTION
S-3 SCALE: 1/4" = 1'-0"



BY: JAMIE PAYNE


DWG FILE: J:\6412 NBC CSO Consolidation Conduits\Civil\Sheet\Set\PAWT_III-A-5_DIVERSION STRUCTURES_PLAIN\0561TEDN\kingday July 27, 2021 10:20:43 AM

REV	DATE	BY	DESCRIPTION
1	5/13/20	JP	STANTEC COMMENTS

SCALE	AS SHOWN
WARNING	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED	C. CRONIN
DRAWN	B. MARINI
CHECKED	J. D'ALESIO

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM



NBC CONTRACT NO 308.05C
STRUCTURAL
OF-217 CONSOLIDATION CONDUIT
OF-217 REVETMENT
PLAN AND SECTION


SHEET
S-3
195130227

BY: JAMIE PAYNE


DWG FILE: J:\6412 NBC Consolidation Conduits\Drawing Files\Civil\Sheet Set\SRPAVT_JIA-5_DIVERSION STRUCTURE DETAILS\DWG.DWG Tuesday, July 27, 2021 10:20:48 AM

GENERAL SHEET NOTES


1. VERTICAL DATUM FOR PROJECT IS NGVD29.
2. GENERAL CONFIGURATION PRESENTED, PROVIDE IN ACCORDANCE WITH SPECIFICATION SECTION 06501.
3. RACK BLADES AND SPACERS TO BE EXTRA HIGH MOLECULAR WEIGHT HEXEN COPOLYMER (HXM POLYETHYLENE).
4. HORIZONTAL RODS SHALL BE PULTRUDED FRP.
5. PRECASTER SHALL COORDINATE WITH CONTRACTOR AND PROVIDE INSERTS 1/2" BOLTS (4" MIN. LENGTH).





FLOATABLES SCREEN
SCALE: 1" = 1'-0"




3 DETAIL
S-4 SCALE: 3" = 1'-0"




5 DETAIL
S-4 SCALE: 3" = 1'-0"




TOP SUPPORT
SCALE: 3" = 1'-0"




6 DETAIL
S-4 SCALE: 3" = 1'-0"




4 DETAIL
S-4 SCALE: 3" = 1'-0"



ELEVATION VIEW
SCALE: 1/2" = 1'-0"



PLAN VIEW
SCALE: 1/2" = 1'-0"





REV	DATE	BY	DESCRIPTION

SCALE	WARNING	DESIGNED	FINAL DESIGN - JULY 2021
SCALE	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DRAWN	
		CHECKED	

--	--	--	--



NARRAGANSETT BAY COMMISSION PHASE III COMBINED SEWER OVERFLOW PROGRAM	NBC CONTRACT NO 308.05C STRUCTURAL OF-217 CONSOLIDATION CONDUIT OF-217 DIVERSION STRUCTURE FLOATABLE SCREEN DETAILS
---	---





TYPICAL PENETRATION DETAIL
NOT TO SCALE

S-900


NOTES

1. SEE ELECTRICAL SHEETS FOR CONDUIT LOCATIONS.
2. ELECTRICAL ENCLOSURE TO BE ANCHORAGE TO BE PER MANUFACTURERS RECOMMENDATIONS.
3. CONCRETE TO HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 4000 PSI.
4. STEEL REINFORCING SHALL CONFORM TO ASTM A615 GRADE 60.



ELECTRICAL ENCLOSURE DETAIL
SCALE: 1/2" = 1'-0"

S-901



REV	DATE	BY	DESCRIPTION

SCALE
AS SHOWN

WARNING
0 1/2 1
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED T. WARZECKI
DRAWN J. PAYNE
CHECKED T. WARZECKI

FINAL DESIGN - JULY 2021



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

Stantec











NBC CONTRACT NO 308.04C
STRUCTURAL

OF-217 CONSOLIDATION CONDUIT
STRUCTURAL DETAILS I

SHEET
S-5
195130227

SINGLE LINE DIAGRAM, SCHEMATIC DIAGRAM SYMBOLOGY AND PLAN SYMBOLOGY

GENERAL ELECTRICAL NOTES



- ALL RACEWAYS AND EQUIPMENT SHALL BE INSTALLED AND GROUNDED IN ACCORDANCE WITH THE 2020 EDITION OF THE NATIONAL ELECTRICAL CODE AND APPLICABLE LOCAL CODES.
- THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF CONDUIT ENTRANCES OF ALL EQUIPMENT AGAINST APPROVED SHOP DRAWINGS BEFORE STUBBING UP CONDUITS.
- CONDUIT RUNS ARE SHOWN DIAGRAMMATICALLY ONLY AND SHALL BE INSTALLED IN A MANNER TO PREVENT CONFLICTS WITH EQUIPMENT OR STRUCTURAL CONDITIONS. EXPOSED CONDUIT SHALL BE INSTALLED PARALLEL OR PERPENDICULAR TO BEAMS AND WALLS. REFER TO SPECIFICATION SECTION 16130.
- IN THE EVENT OF INTERFERENCE BETWEEN ELECTRICAL EQUIPMENT SHOWN ON THE DRAWINGS AND OTHER EQUIPMENT, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN WRITING AND THE ENGINEER SHALL APPROVE PROPOSED CHANGES BEFORE THEY ARE MADE.
- THE WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE DETAILS WHETHER OR NOT THEY ARE REFERENCED ON THE DRAWINGS.
- ALL CONDUIT RUNS CROSSING EXPANSION JOINTS SHALL HAVE EXPANSION OR EXPANSION AND DEFLECTION TYPE FITTINGS. FOR LOCATIONS OF EXPANSION JOINTS, REFER TO THE STRUCTURAL DWGS.
- CONDUITS SHALL BE TERMINATED SO AS TO PERMIT NEAT CONNECTION TO MOTORS AND OTHER EQUIPMENT.
- CONDUITS FOR FUTURE EQUIPMENT OR EXTENSIONS SHALL BE TERMINATED AS INDICATED OR AS SPECIFIED.

BY: MIKE C PLOT DATE: Tuesday, July 27, 2021 9:18:01 AM DWG FILE: C:\pwworkdir\0520866\OF-217 Electrical - 2013.dwg

REV	DATE	BY	DESCRIPTION

SCALE: NO SCALE

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


DESIGNED: M. COTTER
DRAWN: R. BEAUVAIS
CHECKED: M. COTTER

FINAL DESIGN PHASE - JULY 2021



NBC CONTRACT NO 308.05C
GENERAL ELECTRICAL
NOTES & SYMBOLS

SHEET: GE-1
195130227



ELECTRICAL ABBREVIATIONS

A AMPERE, AUTOMATIC
 AC ALTERNATING CURRENT
 AF CIRCUIT BREAKER FRAME SIZE
 AM AMMETER
 ANN ANNUNCIATOR
 AS ADJUSTABLE SPEED
 AT AMPERE TRIP
 ATS AUTOMATIC TRANSFER SWITCH
 AUTO AUTOMATIC
 AWG AMERICAN WIRE GAUGE

BATT BATTERY
 BC BARE COPPER
 BKR BREAKER

C CONDUIT, NUMBERS FOLLOWING INDICATE WIRE QUANTITIES AND WIRE GAUGE SIZES
 CAP CAPACITOR
 CB CIRCUIT BREAKER
 CKT CIRCUIT
 CLF CURRENT LIMITING FUSE
 COM COMMON
 COMM COMMUNICATIONS
 COMP COMPARTMENT
 CP CONTROL PANEL
 CPT CONTROL POWER TRANSFORMER
 CR CONTROL RELAY, CARD READER
 CT CURRENT TRANSFORMER

DCS DISTRIBUTED CONTROL SYSTEM
 DISC DISCONNECT
 DISTR DISTRIBUTION
 DPDT DOUBLE POLE DOUBLE THROW
 DPST DOUBLE POLE SINGLE THROW

E EMERGENCY
 EMT ELECTRICAL METALLIC TUBING
 ENCL ENCLOSURE
 ETM ELAPSED TIME METER

F FREQUENCY, FUSE, FIXED
 FDR FEEDER
 FLA FULL LOAD AMPS
 FLUOR FLUORESCENT
 FM FREQUENCY METER
 FO FIBER OPTIC
 FVR FULL VOLTAGE REVERSING
 FVNR FULL VOLTAGE NON-REVERSING

GEN GENERATOR
 GFCI GROUND FAULT CIRCUIT INTERRUPTER
 GND GROUND

H HAND
 HD HEAT DETECTOR
 HH HAND HOLE
 HID HIGH INTENSITY DISCHARGE
 HOA HAND-OFF-AUTOMATIC
 HPS HIGH PRESSURE SODIUM
 HS HAND SWITCH
 HZ HERTZ

IMC INTERMEDIATE METALLIC CONDUIT
 INCAND INCANDESCENT
 IND INDICATION
 INST INSTANTANEOUS
 INST INSTANTANEOUS
 I/O INPUT/OUTPUT
 IS INTRINSICALLY SAFE
 Isc SHORT CIRCUIT CURRENT, AMPS
 ISO ISOLATION

J,JB JUNCTION BOX

KA KILO AMPERES
 KAIC KILO AMP INTERRUPTING CURRENT
 KCMIL KILO CIRCULAR MILS
 KVA KILOVOLT AMPERE

L LOCAL
 LCP LOCAL CONTROL PANEL
 LCS LOCAL CONTROL STATION
 LIT LEVEL INDICATING TRANSMITTER
 LOC LOCAL
 LOR LOCAL-OFF-REMOTE
 LOS LOCKOUT STOP PUSHBUTTON
 LP LIGHTING PANEL
 LRA LOCKED ROTOR AMPS
 LS LEVEL SWITCH
 LTG LIGHTING
 LTS LIGHTS

M MOTOR CONTACTOR COIL
 mA MILLIAMPERE
 MAINT MAINTENANCE
 MCP MOTOR CIRCUIT PROTECTOR
 MLO MAIN LUGS ONLY
 MOV MOTOR OPERATED VALVE
 MS MANUAL MOTOR STARTER
 MTS MANUAL TRANSFER SWITCH

NEUT NEUTRAL
 NP NAMEPLATE

O OPEN, OFF
 OL OVERLOAD

PA PUBLIC ADDRESS
 PB PUSHBUTTON, PULLBOX
 PC PHOTOCCELL
 PCM PROCESS CONTROL MODULE
 PF POWER FACTOR
 PFM POWER FACTOR METER
 PH PHASE
 PL PILOT LIGHT
 PNLBD PANELBOARD
 PP POWER PANELBOARD
 POS POSITION
 POT POTENTIOMETER
 PRI PRIMARY
 PT POTENTIAL TRANSFORMER
 PTZ PAN-TILT-ZOOM
 PWR POWER

R REMOTE
 RECPT RECEPTACLE
 RGS RIGID GALVANIZED STEEL
 RMS ROOT MEAN SQUARE
 RTU REMOTE TERMINAL UNIT
 RVSS REDUCED VOLTAGE SOLID STATE

SEL SW SELECTOR SWITCH
 SEQ SEQUENCE
 SHLD SHIELDED
 SIG SIGNAL
 SP SPARE
 SP HTR SPACE HEATER
 SPDT SINGLE POLE DOUBLE THROW
 SPST SINGLE POLE SINGLE THROW
 SS 316 STAINLESS STEEL
 SSM SOLID STATE METER
 SSMP SOLID STATE MOTOR PROTECTOR
 ST, SH SHUNT TRIP
 STR STARTER
 SSTU SOLID STATE TRIP UNIT
 SW SWITCH
 SWBD SWITCHBOARD
 SWGR SWITCHGEAR

TACH TACHOMETER
 TB TERMINAL BOX
 TERM TERMINAL
 TM REPEAT CYCLE TIMER
 TD TIME DELAY RELAY
 TS TEMPERATURE SWITCH
 TSP TWISTED SHIELDED PAIR

UPS UNINTERRUPTIBLE POWER SUPPLY

V VOLTAGE, VOLTS
 VA VOLT AMPERE
 VAR VOLT AMPERE REACTIVE
 VFD VARIABLE FREQUENCY DRIVE
 VM VOLTMETER
 VP VAPOR PROOF

W WATTS, WIRE
 WM WATT METER
 WP WEATHERPROOF

XFMR TRANSFORMER
 XMTR TRANSMITTER
 XP EXPLOSION PROOF

BY: MIKE C PLOT DATE: Tuesday, July 27, 2021 9:18:19 AM DWG FILE: C:\pwworkdir\0520668\OF-217 Electrical - 2013.dwg


REV	DATE	BY	DESCRIPTION

SCALE
 NO SCALE

WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED M.COTTER
 DRAWN R.BEAUVAIS
 CHECKED M.COTTER


FINAL DESIGN PHASE - JULY 2021




NARRAGANSETT BAY COMMISSION
 PHASE III COMBINED SEWER
 OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
 ELECTRICAL
 ABBREVIATIONS


SHEET
 GE-2
 195130227



BY: MIKE C
PLOT DATE: Tuesday, July 27, 2021 9:18:37 AM
DWG FILE: C:\pwworkdir\0520668\OF-217 Electrical - 2013.dwg




SITE PLAN
SCALE: 1" = 10'




OF-217 DIVERSION STRUCTURE
SCALE: 1/4" = 1'-0"

DUCT / CABLE SCHEDULE				
DUCT NO.	SIZE	CONDUCTORS	FROM	TO
D1	2"	PULL STRING - SERVICE WIRING PROVIDED BY OTHERS	UTILITY POLE	STUB UP NEXT TO ELECTRICAL ENCLOSURE
D2	2"	PULL STRING - SPARE CONDUIT	UTILITY POLE	STUB UP NEXT TO ELECTRICAL ENCLOSURE
D3	4"	PULL STRING - CABLE BY VENDOR PROVIDED BY OTHERS	ELECTRICAL ENCLOSURE	OF-217 DIVERSION STRUCTURE LEVEL TRANSMITTER LOCATION



- NOTES:**
- BACKFILL DUCT BANK IN LAYERS AND MANUALLY TAMP OR "PUDDLE" CONCRETE FILL. PROVIDE RED DUCT BANK MARKER TAPES, READING "CAUTION - ELECTRICAL LINES BELOW", OVER ENTIRE LENGTH OF DUCTLINE. LOCATE TAPES 12 INCHES BELOW GRADE. PROVIDE A TAPE FOR EVERY 12 INCHES OF WIDTH OF DUCTLINE.
 - A MINIMUM OF 12" SEPARATION SHALL BE KEPT BETWEEN DUCT BANK SECTIONS WITHIN SAME TRENCH.
 - REINFORCING REBAR IS TO BE #5 ASTM A615 GRADE 60 STEEL REBAR.

1 DUCTBANK SECTIONS
NOT TO SCALE



GENERAL SHEET NOTES

- NONE

SHEET KEYNOTES

- 60"x36"x18", NEMA 3R STAINLESS STEEL TRAFFIC BOX ELECTRICAL ENCLOSURE MOUNTED ON A CONCRETE BASE, REFER TO DRAWING E-2 DETAIL 3.
- ELECTRIC HANDHOLE, REFER DRAWING E-2 DETAIL 6.

REV	DATE	BY	DESCRIPTION

SCALE: AS SHOWN

WARNING: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED: M. COTTER
DRAWN: R. BEAUVAIS
CHECKED: M. COTTER

FINAL DESIGN PHASE - JULY 2021




NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM


NBC CONTRACT NO 308.05C
ELECTRICAL

SITE PLAN, DUCTBANK SECTIONS, AND
OF-217 DIVERSION STRUCTURE PLAN


SHEET
E-1
195130227




BY: MIKE C PLOT DATE: Tuesday, July 27, 2021 9:19:16 AM DWG FILE: C:\pwworkdir\0520868\OF-217 Electrical - 2013.dwg




1 CONDUIT RISER DIAGRAM
NOT TO SCALE



4 CONDUIT THROUGH STRUCTURE WALL DETAIL
NOT TO SCALE




2 ELECTRICAL ENCLOSURE INTERIOR LAYOUT
SCALE: 1" = 1'-0"





3 ELECTRICAL ENCLOSURE BASE DETAIL
NOT TO SCALE

NOTES:
1. REINFORCING REBAR IS TO BE #5 ASTM A615 GRADE 60 STEEL REBAR.
2. EXPLOSION PROOF SEAL FITTINGS ARE NOT TO BE FILLED, INSTALLATION OF CABLE AND SEALANT WILL BE BY OTHERS.
3. SEAL AND CAP THE ENDS OF CONDUITS.




5 SERVICE RISER POLE
NOT TO SCALE




6 ELECTRIC HANDHOLE DETAIL
NOT TO SCALE

NOTES:
1. CHIMNEY HEIGHT IS KEPT TO MINIMUM TO FACILITATE WIRE PULLING IN HANDHOLE FROM ABOVE GRADE.
2. CONCRETE TO HAVE MINIMUM STRENGTH OF 5,000 PSI AT 28 DAYS, REINFORCING REBAR IS TO BE #5 ASTM A615 GRADE 60 STEEL REBAR.
3. PROVIDE HANDHOLE FRAME, RING AND COVER.
4. REFER TO DUCTBANK SECTIONS FOR THE REQUIRED NUMBER OF CONDUIT ENTRANCES. PROVIDE CONDUIT ENTRY SPACE ON NON-USED SIDES FOR A MINIMUM (4) 4" FUTURE CONDUITS.
5. REFER TO SITE PLAN FOR HANDHOLE SIDES CONDUITS ARE ENTERING.



REV	DATE	BY	DESCRIPTION

SCALE	NO SCALE	WARNING 0 1/2 1 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE	DESIGNED M. COTTER	FINAL DESIGN PHASE - JULY 2021
			DRAWN R. BEAUVAIS	
			CHECKED M. COTTER	



NARRAGANSETT BAY COMMISSION
PHASE III COMBINED SEWER
OVERFLOW PROGRAM

NBC CONTRACT NO 308.05C
ELECTRICAL
CONDUIT RISER DIAGRAM
AND DETAILS