

# City of Taunton, Massachusetts

## Wastewater Treatment Facility Improvements

### Phase I




**Mayor**  
Shaunna O'Connell

**Department of Public Works**  
Frederic J. Cornaglia - Commissioner  
Anthony Abreau - Assistant Commissioner

**City Engineer**  
Michael Patneaude, P.E.

**City Council**  
Deborah Carr  
Donald L. Cleary  
Chris Coute  
Gerald Croteau  
Phillip Duarte  
John M. McCaul  
Jeff Postell  
David W. Pottier  
Barry Sanders



LOCATION MAP  
NOT TO SCALE



Project  
Location

PROJECT LOCATION

LOCUS MAP  
NOT TO SCALE

**ISSUED FOR SRF SUBMISSION  
NOT FOR CONSTRUCTION**

**Contract S-2021-1  
CWSRF No. 4605**

Issue Date:  
May 11, 2021



Prepared By:






















**LEGEND**

[Solid Grey]	EXISTING BUILDING
[Light Grey]	PROPOSED STRUCTURE
[Hatched]	FUTURE STRUCTURE
[Dotted]	EXISTING PAVEMENT
[Cross-hatched]	PROPOSED PAVEMENT


PREPARED BY  
  
 www.BETA-Inc.com

REGISTERED PROFESSIONAL  
  
 Joseph P. Rodriguez, Jr.

SUBCONSULTANT

PROJECT  
**Taunton Wastewater Treatment Facility Improvements Phase 1**  
 Taunton, MA


TITLE  
**WWTF Process Areas Key Plan**



PROCESS AREAS	
0	GENERAL / SITE WORK
1	HEADWORKS
2	PRIMARY CLARIFICATION / SLUDGE PUMPING
3	BIOLOGICAL TREATMENT TANKS - (FUTURE CONTRACT)
4	FINAL CLARIFIERS / SECONDARY SLUDGE PUMPING - (FUTURE CONTRACT)
5	DISINFECTION / DECHLORINATION
6	BLOWERS
7	SOLIDS HANDLING
8	ODOR CONTROL
9	NON-PROCESS BUILDINGS

NO.	REVISIONS	DATE

DRAWN BY: BM  
 DESIGNED BY: MA  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE  
  
 SCALE IN FEET: 1"=40'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:  
**Not for Construction**  
 SHEET NO.  
**G-1.5**

5/11/2021 9:53 AM J:\TAUNTON\WWTF DESIGN\AUTOCAD\PLAN SET\PHASE 1\WWTF PROCESS AREAS DWG (BETA STD BW.CTB)























5/11/2021 9:53 AM J:\TAUNTON\WTF DESIGN\AUTOCAD\PLAN SET\PHASE 1\WTF SITE PLAN - EXIST.DWG (BETA STD BW.CTB)

PREPARED BY  
  
 www.BETA-Inc.com

REGISTERED PROFESSIONAL  
  
 Joseph F. Ferrigno, Jr.


SUBCONSULTANT

PROJECT  
**Taunton Wastewater Treatment Facility Improvements Phase 1**  
 Taunton, MA

TITLE  
**WWTF Existing Site Plan**

NO.	REVISIONS	DATE

DRAWN BY: BM  
 DESIGNED BY: BM  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE  
  
 SCALE IN FEET: 1"=40'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:  
**Not for Construction**  
 SHEET NO.  
**C-1.1**












DESCRIPTION	LOCATION	COORDINATES	ELEVATION
BENCHMARK	UTILITY POLE SPIKE	N 2779536.01, E 765815.13	21.02
BENCHMARK	HYDRANT BONNET BOLT	N 2779571.66, E 765897.89	19.28
GRIT CHAMBER NO.1	NORTHEAST CORNER	N 2779365.42, E 765620.25	
	SOUTHWEST CORNER	N 2779390.25, E 765616.14	
LIME SILO FOUNDATION	SEE STRUCTURAL DRAWINGS		
PRIMARY CLARIFIER 1	CENTER OF TANK	N 2779255.79, E 765701.68	
PRIMARY CLARIFIER 2	CENTER OF TANK	N 2779311.57, E 765710.71	
PRIMARY CLARIFIER 3	CENTER OF TANK	N 2779369.32, E 765720.06	
PRIMARY CLARIFIER 4	SEE STRUCTURAL DRAWINGS		
AERATION TANK NO.1	SOUTHWEST CORNER	N 2779321.46, E 765833.64	
	SOUTHWEST CORNER	N 2779302.85, E 765949.32	
AERATION TANK NO.3	NORTHEAST CORNER	N 2779413.29, E 765965.50	
	SOUTHWEST CORNER	N 2779389.42, E 765961.76	
BLOWER BUILDING FOUNDATION	SEE STRUCTURAL DRAWINGS		
FINAL CLARIFIER NO.1	CENTER OF TANK	N 2779203.71, E 765866.65	
FINAL CLARIFIER NO.2	CENTER OF TANK	N 2779178.96, E 766021.68	
FINAL CLARIFIER NO.3	CENTER OF TANK	N 2779328.33, E 766112.97	
FINAL CLARIFIER NO.4	CENTER OF TANK	N 2779303.10, E 766267.93	
AERATION TANK NO.4	NORTHWEST CORNER	N 2779205.40, E 766178.14	
	SOUTHWEST CORNER	N 2779063.02, E 766155.49	
AERATION TANK NO.6	NORTHWEST CORNER	N 2779188.50, E 766281.83	
	SOUTHWEST CORNER	N 2779047.62, E 766259.35	
CHLORINE CONTACT TANK INFLUENT	NORTHWEST CORNER	N 2779118.03, E 766359.45	
	NORTHEAST CORNER	N 2779115.64, E 766404.59	

LEGEND	
	EXISTING BUILDING
	PROPOSED STRUCTURE
	FUTURE STRUCTURE
	EXISTING PAVEMENT
	PROPOSED PAVEMENT

**NOTE:**  
PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL VERIFY THE LAYOUT OF ALL STRUCTURES BY COORDINATES AND REPORT ANY DISCREPANCIES TO THE ENGINEER.



PREPARED BY  
  
 www.BETA-Inc.com

REGISTERED PROFESSIONAL  
  
 Joseph F. Ferrigno, Jr.

SUBCONSULTANT

PROJECT  
**Taunton Wastewater Treatment Facility Improvements Phase 1**  
 Taunton, MA

TITLE  
**WWTF Proposed Site Plan**

NO.	REVISIONS	DATE


DRAWN BY: BM  
 DESIGNED BY: BM  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE  
  
 SCALE IN FEET: 1"=40'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:  
**Not for Construction**  
 SHEET NO.  
**C-1.4**

5/11/2021 9:54 AM J:\TAUNTON\WWTF DESIGN\AUTOCAD\PLAN SET\PHASE 1\WWTF PROP SITE PLAN - ALT.1.DWG (BETA STD BW.CTB)





PREPARED BY  
**BETA**  
 www.BETA-Inc.com

REGISTERED PROFESSIONAL  
  
 Joseph F. Ferrigno, Jr.

SUBCONSULTANT

PROJECT  
**Taunton Wastewater Treatment Facility Improvements Phase 1**  
 Taunton, MA

TITLE  
**Erosion Control Plan**

NO.	REVISIONS	DATE

DRAWN BY: BM  
 DESIGNED BY: BM  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE  
  
 SCALE IN FEET: 1"=40'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:  
**Not for Construction**  
 SHEET NO.  
**C-15**

5/11/2021 9:54 AM J:\TAUNTON\WTF DESIGN\AUTOCAD\PLAN SET\PHASE 1\WTF PROP SITE PLAN - ALT 1.DWG (BETA STD BW CTE)



































SHEET C-1.9

SHEET C-1.12

SHEET C-1.14

PREPARED BY  
  
 www.BETA-Inc.com

REGISTERED PROFESSIONAL  
  
 Joseph F. Ferrigno, Jr.


SUBCONSULTANT

PROJECT  
**Taunton Wastewater Treatment Facility Improvements Phase 1**  
 Taunton, MA

TITLE  
**Site & Yard Piping Plan VI**

NO.	REVISIONS	DATE

DRAWN BY: BM  
 DESIGNED BY: BM  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE  
  
 SCALE IN FEET: 1"=10'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:  
**Not for Construction**  
 SHEET NO.  
**C-1.13**

5/11/2021 9:55 AM J:\TAUNTON\WWTFF DESIGN\AUTOCAD\PLAN SET\PHASE 1\WWTFF YARD PIPING - PROP.DWG (BETA STD BW.CTB)




















PREPARED BY  
**BETA**  
 www.BETA-Inc.com

REGISTERED PROFESSIONAL  
  
 Joseph F. Ferrigno, Jr.


SUBCONSULTANT

PROJECT  
**Taunton Wastewater Treatment Facility Improvements Phase 1**  
 Taunton, MA

TITLE  
**Site & Yard Piping Plan X**

NO.	REVISIONS	DATE


NO. REVISIONS DATE  
 DRAWN BY: BM  
 DESIGNED BY: BM  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE  
  
 SCALE IN FEET: 1"=10'




UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:  
**Not for Construction**  
 SHEET NO.  
**C-1.17**

5/11/2021 9:56 AM J:\TAUNTON\WWTF DESIGN\AUTOCAD\PLAN SET\PHASE 1\WWTF YARD PIPING - PROP.DWG (BETA STD BW.CTB)







- NOTES:**
- FOR LOCATIONS WHERE WATER MAINS DO NOT MAINTAIN 10-FOOT HORIZONTAL SEPARATION FROM SEWER FM'S OR PROCESS PIPING, BACKFILL WATER MAIN IN ACCORDANCE WITH CONTROLLED DENSITY BACKFILL OF DUCTILE IRON WATER PIPE DETAIL THIS SHEET



- NOTES:**
- \* ALL D.I.C.L. WATER PIPE THAT IS BACKFILLED WITH CONTROLLED DENSITY FILL, MUST BE ENCASED WITH 8-MIL LLD POLYETHYLENE IN ACCORDANCE ANSI/AWWA C105/A2.5, METHOD OF INSTALLATION.
  - THE PIPE SHALL BE PROPERLY SECURED AND SUPPORTED TO PREVENT DISPLACEMENT DURING THE POURING OF CONTROLLED DENSITY FILL.



- NOTES:**
- AT CROSSINGS, ONE FULL LENGTH OF WATER PIPE SHALL BE LOCATED SO BOTH JOINTS WILL BE AS FAR FROM THE SEWER FM OR PROCESS PIPE AS POSSIBLE.
  - WATER MAINS CROSSING UNDER SEWER OR PROCESS PIPING SHALL BE LAID TO PROVIDE A MINIMUM VERTICAL DISTANCE OF 18 INCHES BETWEEN INVERT OF THE SEWER FM OR PROCESS PIPE AND CROWN OF THE WATER MAIN.
  - ALL D.I.C.L. WATER PIPE THAT IS BACKFILLED WITH CONTROLLED DENSITY FILL, MUST BE ENCASED WITH 8-MIL LLD POLYETHYLENE IN ACCORDANCE ANSI/AWWA C105/A2.5, METHOD OF INSTALLATION.
  - THE PIPE SHALL BE PROPERLY SECURED AND SUPPORTED TO PREVENT DISPLACEMENT DURING THE POURING OF CONTROLLED DENSITY FILL.



- NOTES:**
- WATER MAINS SHALL CROSS OVER SEWER FM'S & PROCESS PIPING AS MUCH AS POSSIBLE.
  - WHEN A WATER MAIN CROSSES UNDER A SEWER FM OR PROCESS PIPE, SEE DETAIL "WATER MAIN CROSSING UNDER SEWER FORCE MAINS & PROCESS PIPING" ON THIS SHEET.
  - AT CROSSINGS, ONE FULL LENGTH OF WATER PIPE SHALL BE LOCATED SO BOTH JOINTS WILL BE AS FAR FROM THE SEWER FM OR PROCESS PIPE AS POSSIBLE.
  - WATER MAINS CROSSING OVER SEWER OR PROCESS PIPING SHALL BE LAID TO PROVIDE A MINIMUM VERTICAL DISTANCE OF 18 INCHES BETWEEN INVERT OF WATER MAIN AND CROWN OF SEWER FM OR PROCESS PIPE.
  - ALL D.I.C.L. WATER PIPE THAT IS BACKFILLED WITH CONTROLLED DENSITY FILL, MUST BE ENCASED WITH 8-MIL LLD POLYETHYLENE IN ACCORDANCE ANSI/AWWA C105/A2.5, METHOD OF INSTALLATION.
  - THE PIPE SHALL BE PROPERLY SECURED AND SUPPORTED TO PREVENT DISPLACEMENT DURING THE POURING OF CONTROLLED DENSITY FILL.

TITLE  
**Civil Details I**

NO.	REVISIONS	DATE

DRAWN BY:	BM
DESIGNED BY:	BM
CHECKED BY:	--
ISSUE DATE:	5/11/2021
BETA JOB NO.:	6050
SCALE	AS SHOWN
UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:	
<b>Not for Construction</b>	
SHEET NO.	CD-1







































PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT

PROJECT

Taunton Wastewater Treatment Facility Improvements Phase 1

Taunton, MA

TITLE

Proposed Blower Building Wall Sections

NO. REVISIONS DATE

DRAWN BY: --


DESIGNED BY: --

CHECKED BY: --

ISSUE DATE: 3/4/2020

BETA JOB NO.: 6050

SCALE




UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION


Not for Construction

SHEET NO.


A-6.3




SCUPPER DETAIL 1 SCALE: 1"= 1'-0"




EAVE DETAIL 2 SCALE: 1"= 1'-0"




EAVE DETAIL 3 SCALE: 1"= 1'-0"




LADDER DETAIL 4 SCALE: 1"= 1'-0"




SECTION A SCALE: 1/2"= 1'-0" A-6.1



SECTION B SCALE: 1/2"= 1'-0" A-6.1



SECTION C SCALE: 1/2"= 1'-0" A-6.1



SECTION D SCALE: 1/2"= 1'-0" A-6.1

5/7/2021 2:43 PM N:\USHYANNIS\PROJECTS\11111186884-TAUNTON WWTF DESIGN SERVICES\CADD\DRAWINGS\ARCHITECTURAL\1186884-AMOD-A-6.3 BETA.DWG (BETA STB BW.STB)

































PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT


PROJECT

Taunton Wastewater Treatment Facility Improvements Phase 1

Taunton, MA


TITLE

Storage Building Plans and Elevations




LOWER LEVEL PLAN

SCALE: 1/8"=1'-0"




ROOF PLAN


SCALE: 1/8"=1'-0"




NORTH ELEVATION



EAST ELEVATION



SOUTH ELEVATION



WEST ELEVATION

ELEVATIONS

SCALE: 1/8"=1'-0"

CODE ANALYSIS

2015 INTERNATIONAL EXISTING BUILDING CODE SUMMARY

Alteration Level 1

Work consists of the replacement of existing roof system, and repair and cleaning of existing brick and stucco.

GENERAL NOTES


- 1. VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS IN FIELD.
2. ALL ROOFS TO PROVIDE A UL CLASS A RATING.
3. SEE SCHEDULE SHEET FOR DOOR INFORMATION.

NOTES

- 1. REMOVE EXISTING ROOF MEMBRANE, INSULATION, FASCIA, ROOF DRAINS AND ASSOCIATED FLASHING. INSPECT SUBSTRATE AND REPAIR AS NECESSARY. COORDINATE TEMPORARY REMOVAL AND RE-INSTALLATION OF ROOF HATCHES AND EQUIPMENT.
2. CLEAN EXISTING BRICK. REPAIR AND REPOINT AS NECESSARY.
3. CLEAN EXISTING STUCCO AND REPAIR AS NECESSARY
4. FLASH IN ACCORDANCE WITH ROOF SYSTEM MANUFACTURERS' STANDARD DETAILS AND 20 YEAR WARRANTY REQUIREMENTS.
5. EXTEND EXISTING CURBS AS NEEDED TO ACHIEVE A MINIMUM OF 10 INCHES ABOVE FINISHED ELEVATIONS.
6. INSTALL ROOF DRAIN INTO EXISTING PIPING, ADDING PIPE EXTENSIONS IF NECESSARY TO RAISE IT TO THE NEW INSULATION THICKNESS. FLASH IN ACCORDANCE WITH MANUFACTURERS' STANDARD DETAILS AND 20 YEAR WARRANTY REQUIREMENTS.

Table with 3 columns: NO., REVISIONS, DATE

Table with 2 columns: FIELD, VALUE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

Not for Construction

SHEET NO.

A-9.6

5/7/2021 2:45 PM N:\USHYANNIS\PROJECTS\1111111186884-TAUNTON WWTF DESIGN SERVICES\CADD\DRAWINGS\ARCHITECTURAL\11186844-AMOD-A-9.6 BETA.DWG (BETA-STB BW.STB)







**SUBMITTALS, TESTING, AND INSPECTIONS:**

- SUBMITTALS AND TESTING SHALL BE AS REQUIRED BY THE MASSACHUSETTS STATE BUILDING CODE AND THESE FOLLOWING REQUIREMENTS.
- THE CONTRACTOR SHALL PROVIDE FOR AN INDEPENDENT TESTING AGENCY TO PERFORM REQUIRED TESTING.
- THE CONTRACTOR SHALL COORDINATE ALL WORK WITH THE TESTING AGENCY AND THE ENGINEERS OF RECORD ACCORDINGLY.
- NOTIFY THE GEOTECHNICAL ENGINEER OF RECORD PRIOR TO FOUNDATION EXCAVATION.
- NOTIFY THE STRUCTURAL ENGINEER OF RECORD PRIOR TO FIRST CONCRETE PLACEMENT.
- SUBMITTALS INCLUDE BUT NOT LIMITED TO:  
DEWATERING  
BORROW MATERIAL  
CONCRETE MIX DESIGN  
STEEL REINFORCING  
ACCESSORIES  
STRUCTURAL STEEL/COLD FORMED METAL
- TESTS/INSPECTIONS INCLUDES BUT NOT LIMITED TO:  
EARTHWORK  
CONCRETE STRENGTH  
REINFORCING STEEL INSTALLATION  
CONCRETE PLACEMENT AND CURING  
STEEL BOLTING
- THE CONTRACTOR SHALL KEEP COMPLETE AND ORGANIZED RECORDS OF ALL TESTS AND INSPECTIONS AND PROVIDE THEM TO THE ENGINEER SO THAT THE FINAL AFFIDAVIT CAN BE PREPARED. A BINDER SHALL BE MAINTAINED AT THE JOBSITE AT ALL TIMES FOR THE ENGINEER'S INSPECTION.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER, IN ADVANCE, BEFORE CONCEALING ANY WORK THAT WILL REQUIRE OBSERVATION NEEDED TO PREPARE THE FINAL AFFIDAVIT.

**PENETRATION SCHEDULE:**


PENETRATION NUMBER	PENETRATION TYPE (SEE S-X)	PENETRATION LOCATION	CENTERLINE ELEVATION	PIPE DESCRIPTION	PIPE MATERIAL	NOMINAL SIZE (IN)
P-1.1	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	HEADWORKS EFFLUENT CHANNEL	31.67	PRIMARY INFLUENT	DUCTILE IRON	24
P-1.2	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	PRIMARY DISTRIBUTION BOX	31.63	PRIMARY INFLUENT	DUCTILE IRON	24
P-1.3	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	PRIMARY DISTRIBUTION BOX	24.70	PRIMARY INFLUENT	DUCTILE IRON	24
P-1.4	WALL SLEEVE	PRIMARY DISTRIBUTION BOX	33.75	LIME SLURRY	PVC	2
P-2.1	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	PRIMARY CLARIFIER NO. 4	18.25	PRIMARY INFLUENT	DUCTILE IRON	24
P-2.2	WALL SLEEVE	PRIMARY CLARIFIER NO. 4	28.50	PRIMARY SCUM	DUCTILE IRON	4
P-2.3	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	PRIMARY CLARIFIER NO. 4	30.33	PRIMARY EFFLUENT	DUCTILE IRON	20
P-2.4	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	PRIMARY CLARIFIER NO. 4	18.39	PRIMARY SLUDGE	DUCTILE IRON	8
P-2.5	WALL SLEEVE	NEW SCUM WELL	28.50	PRIMARY SCUM	DUCTILE IRON	4
P-2.6	WALL SLEEVE	NEW SCUM WELL	28.50	PRIMARY SCUM	DUCTILE IRON	4
P-2.7	WALL SLEEVE	PRIMARY SLUDGE PUMP STATION (NORTH WALL)	28.50	PRIMARY SCUM	DUCTILE IRON	4
P-2.8	FLUSH FLANGE x FLUSH FLANGE WALL PIPE	PRIMARY SLUDGE PUMP STATION (NORTH WALL)	18.00	PRIMARY SCUM	DUCTILE IRON	8
P-2.9	WALL SLEEVE	PRIMARY SLUDGE PUMP STATION (NORTH WALL)	18.00	PRIMARY SLUDGE	DUCTILE IRON	8
P-2.10	WALL SLEEVE	PRIMARY SLUDGE PUMP STATION (NORTH WALL)	27.17	PRIMARY EFFLUENT	DUCTILE IRON	20
P-2.11	WALL SLEEVE	PRIMARY SLUDGE PUMP ROOF (NORTHWEST CORNER)	33.50	PLANT WATER	GALVANIZED STEEL	2
P-5.1	WALL SLEEVE	CHLORINE CONTACT TANK (NORTH WALL)	7.67	PLANT WATER	DUCTILE IRON	16
P-5.2	WALL SLEEVE	CHLORINE CONTACT TANK (NORTH WALL)	7.67	PLANT WATER	DUCTILE IRON	16
P-5.3	WALL SLEEVE	CHLORINE CONTACT TANK (WEST WALL)	10.25	SCUM TROUGH	DUCTILE IRON	10
P-5.4	WALL SLEEVE	CHLORINE CONTACT TANK (WEST WALL)	8.95	SCUM	DUCTILE IRON	8
P-5.5	WALL SLEEVE	CHLORINE CONTACT TANK (EAST WALL)	10.25	SCUM TROUGH	DUCTILE IRON	10
P-5.6	WALL SLEEVE	CHLORINE CONTACT TANK (EAST WALL)	8.95	SCUM	DUCTILE IRON	8
P-5.7	WALL SLEEVE	CHLORINE MANHOLE	9.00	SODIUM HYPOCHLORITE	PVC	3/4
P-5.8	WALL SLEEVE	CHEMICAL HANDLING BLDG (SOUTH WALL)	7.67	PLANT WATER	DUCTILE IRON	16
P-5.9	WALL SLEEVE	CHEMICAL HANDLING BLDG (WEST WALL)	8.00	PLANT WATER	DUCTILE IRON	14
P-5.10	WALL SLEEVE	CHEMICAL HANDLING BLDG (WEST WALL)	9.50	SODIUM HYPOCHLORITE	PVC	3/4
P-5.11	WALL SLEEVE	CHEMICAL HANDLING BLDG (NORTH WALL)	15.00	SODIUM HYPOCHLORITE	PVC	1
P-5.12	WALL SLEEVE	CHEMICAL HANDLING BLDG (WEST WALL)	4.53	PLANT WATER	DUCTILE IRON	14
P-6.1*	WALL SLEEVE	BLOWER BUILDING (NORTH WALL)	37.00	AIR INTAKE	SS SCHEDULE 10S	18
P-6.2*	WALL SLEEVE	BLOWER BUILDING (NORTH WALL)	37.00	AIR INTAKE	SS SCHEDULE 10S	18
P-6.3*	WALL SLEEVE	BLOWER BUILDING (NORTH WALL)	37.00	AIR INTAKE	SS SCHEDULE 10S	18
P-6.4*	WALL SLEEVE	BLOWER BUILDING (EAST WALL)	37.00	DISCHARGE HEADER	SS SCHEDULE 10S	30

\* PENETRATIONS ASSUME BLOWER EQUIPMENT TO BE NEXTURBO GTB-T20-XY. IF ALTERNATE EQUIPMENT IS USED, SIZE AND LOCATION OF PENETRATIONS WILL VARY AND NEED TO BE COORDINATED WITH MANUFACTURER.

**LIST OF ABBREVIATIONS:**

ARCH.	- ARCHITECTURAL	(LLH)	- LONG LEG HORIZONTAL
ADD'L	- ADDITIONAL	(LLV)	- LONG LEG VERTICAL
APPROX.	- APPROXIMATE	LOC.'S	- LOCATIONS
BRG.	- BEARING	MAX.	- MAXIMUM
B.O.	- BOTTOM OF	MIN.	- MINIMUM
C-C	- CENTER TO CENTER	MISC.	- MISCELLANEOUS
CL	- CENTERLINE	N.F.	- NEAR FACE
C.I.P.	- CAST IN PLACE	N.S.	- NEAR SIDE
CONC.	- CONCRETE	N.T.S.	- NOT TO SCALE
CONST.	- CONSTRUCTION	NO.	- NUMBER
CONT.	- CONTINUOUS	O.C.	- ON CENTER
C.Y.	- CUBIC YARD	O.D.	- OUTSIDE DIAMETER
d	- DEEP	O.F.	- OUTSIDE FACE
DET.	- DETAIL	PERIM.	- PERIMETER
DTL.	- DETAIL	P	- PLATE
DIA.	- DIAMETER	PVC	- POLYVINYL CHLORIDE
DWG.	- DRAWING	P.S.F.	- POUNDS PER SQUARE FOOT
EA.	- EACH	P.S.I.	- POUNDS PER SQUARE INCH
EL.	- ELEVATION	RAD.	- RADIUS
ELEV.	- ELEVATION	REINF.	- REINFORCING
EMBED.	- EMBEDMENT	REQ'D	- REQUIRED
E.F.	- EACH FACE	SECT.	- SECTION
E.S.	- EACH SIDE	SCH.	- SCHEDULE
E.W.	- EACH WAY	S.F.	- SQUARE FOOT
EXIST.	- EXISTING	SHT.	- SHEET
EXP.	- EXPANSION	SIM.	- SIMILAR
FIN.	- FINISH	SP.	- SPACES
F.O.	- FACE OF	S.S.	- STAINLESS STEEL
FT.	- FEET/FOOT	STD.	- STANDARD
FTG.	- FOOTING	STL.	- STEEL
GA.	- GAUGE	SYM.	- SYMMETRIC
GALV.	- GALVANIZED	t	- THICK
GC	- GENERAL CONTRACTOR	T&B	- TOP AND BOTTOM
h	- HIGH	T.O.	- TOP OF
HORIZ.	- HORIZONTAL	T.O.S.	- TOP OF SLAB
H.A.	- HIGH POINT	T.O.W.	- TOP OF WALL
I.F.	- INSIDE FACE	TYP.	- TYPICAL
IN.	- INCH	U.N.O.	- UNLESS NOTED OTHERWISE
I.D.	- INSIDE DIAMETER	VERT.	- VERTICAL
INFO.	- INFORMATION	W.W.F.	- WELDED WIRE FABRIC
INV.	- INVERT	w	- WIDE
JT.	- JOINT	w/	- WITH
K.S.I.	- KIPS PER SQUARE INCH	ø	- DIAMETER
LG.	- LONG		

**SECTION AND DETAIL DESIGNATIONS:**



**STAY-IN-PLACE FORM NOTES:**

- FOR 2" S.I.P. FORM, SET BOTTOM OF FORM 1" BELOW ELEVATION SHOWN IN DRAWINGS, FOR 3" S.I.P. FOR, SET BOTTOM OF FORM 1 1/2" BELOW ELEVATIONS.
- FORM ENDS SHALL BE CRIMPED CLOSED IN A TAPERED MANNER. SEPERATE END CLOSURE PIECES WILL NOT BE ALLOWED.
- SUPPORT ANGLES SHALL BE PLACED IN THE "LEG DOWN" POSITION WHERE POSSIBLE. WHERE "LEG UP" POSITION IS NECESSARY, THE UPPER MOST PORTION OF THE ANGLE SHALL NOT PROJECT MORE THAN 1" ABOVE THE TOP OF FLANGE. THE CONTRACTOR SHALL HAVE AN ASSORTMENT OF ANGLES OF VARIOUS SIZES AVAILABLE ON THE SITE TO CONFORM TO THIS REQUIREMENT.
- ALL MAIN STEEL REINFORCEMENT IN THE LOWER MAT SHALL BE CENTERED OVER THE VALLEY OF THE S.I.P. FORM.
- CONTRACTOR SHALL DESIGN AND DETAIL ALL ELEMENTS OF THE FORMING SYSTEM AND SHALL SUBMIT TO THE ENGINEER FOR APPROVAL.
- IN CASES WHERE STANDARD 2" OR 3" DEEP S.I.P. FORMS DO NOT SATISFY DESIGN REQUIREMENTS AN ALTERNATIVE FORMING SYSTEM CONSISTING OF DEEPER S.I.P. FORMS OR REMOVABLE FORM SHALL BE DESIGNED BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE DESIGN THICKNESS OF THE SLAB SHALL NOT CHANGE.

PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT

PROJECT

**Taunton Wastewater Treatment Facility Improvements Phase 1**

TAUNTON, MA

TITLE

Structural Notes (2 of 2)

NO. REVISIONS DATE

DRAWN BY: BN  
DESIGNED BY: BN  
CHECKED BY: TMW  
ISSUE DATE: 5/11/2021  
BETA JOB NO.: 6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO. SG-2




































































































































































**PLAN (EL. 32.0)**  
SCALE: 1/4" = 1'-0"



**SECTION 1**  
SCALE: 1/4" = 1'-0"

MATCH LINE A-A SHEET M-2.3

PREPARED BY



REGISTERED PROFESSIONAL



SUBCONSULTANT

PROJECT

**Taunton Wastewater Treatment Facility Improvements Phase 1**

Taunton, MA

TITLE

**Primary Sludge Pump Station Demolition Plans & Sections II**

NO.	REVISIONS	DATE

DRAWN BY:	BM
DESIGNED BY:	JD
CHECKED BY:	--
ISSUE DATE:	5/11/2021
BETA JOB NO.:	6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION.

**Not for Construction**

SHEET NO.

M-2.4

5/11/2021 10:12 AM J:\TAUNTON\WTF DESIGN\AUTOCAD\PLAN SET\PHASE 1\PRIMARY CLARIFIERS & SLUDGE PS - EXIST. PLANS & SECTIONS.DWG (BETA STD BW.CTB)



































































NOTE: TIERODS SHALL BE EQUALLY SPACED AROUND PIPE.

PIPE SIZE	TIERODS		FLANGE CLAMP			
	NO.	DIA.	THICKNESS	NO. OF FLANGE BOLTS PER CLAMP	"A"	"B"
6"	2	1/2"	1/2"	2	2"	7-3/4"
8"	2	5/8"	1/2"	2	2"	8-5/8"
10"	2	3/4"	1/2"	2	2"	7-3/4"
12"	2	1"	1/2"	2	2"	8-1/2"
14"	2	1-1/8"	3/4"	2	2"	9"
16"	2	1-1/4"	7/8"	3	2"	12-1/4"
18"	2	1-3/8"	7/8"	3	2-1/2"	13"
20"	3	1-3/8"	1"	2	2-1/2"	8"
24"	3	1-3/8"	1"	2	2-1/2"	8-3/4"
30"	4	1-3/4"	1"	2	2-1/2"	12-1/4"
36"	4	1-3/4"	1-1/4"	3	2-1/2"	8-1/2"
42"	6	1-3/4"	1-1/4"	2	2-1/2"	12-3/4"
48"	6	1-3/4"	1-1/4"	3	2-1/2"	12-1/2"
	8			3		


**SLEEVE COUPLING RESTRAINT  
(150 PSI FLANGE CLAMP ASSEMBLY)** 432

SCALE: NOT TO SCALE




**FLUSHING CONNECTION** 433

SCALE: NOT TO SCALE




**SLIDE GATE**

SCALE: NOT TO SCALE



**DIAPHRAGM PRESSURE GAUGE**



**PRESSURE GAUGE**

NOTES:

- FOR STEEL, GALVANIZED STEEL, AND PVC 2 1/2" AND SMALLER USE A BUSHING IN A TEE.
- FOR DUCTILE IRON AND FIBERGLASS REINFORCED PLASTIC PIPE, ALL SIZES, USE PIPE SADDLE WITH BUSHING.
- FOR STEEL AND STAINLESS STEEL PIPES 3" AND LARGER, AND PRESSURE VESSELS, USE THRED-O-LET AS SHOWN.
- PROVIDE SNUBBER FOR POSITIVE DISPLACEMENT PUMP INSTALLATIONS.


**PRESSURE GAUGE MOUNTING DETAILS** 434

SCALE: NOT TO SCALE

PREPARED BY



REGISTERED PROFESSIONAL



*Joseph F. Ferrigno, Jr.*

SUBCONSULTANT

PROJECT

**Taunton Wastewater Treatment Facility Improvements Phase 1**

Taunton, MA

TITLE

**Mechanical Details III**

NO. REVISIONS DATE

DRAWN BY: BM  
 DESIGNED BY: BM  
 CHECKED BY: --  
 ISSUE DATE: 5/11/2021  
 BETA JOB NO.: 6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION:

**Not for Construction**

SHEET NO.

MD-3



4/27/2021 7:54 AM W:\YEAR - 2018\18009.00 - TAUNTON\W\T\UPGRADE\HVAC\DEPARTMENT\PHASE 1\18009.00\HVAC LEGEND SCHEDULE AND DETAIL\BETA STB BWJ(STB)

GENERAL NOTES

- 1. HVAC WORK IS INDICATED DIAGRAMMATICALLY. EXACT LOCATIONS OF ALL COMPONENTS ARE TO BE DETERMINED IN THE FIELD AND BY THE ACTUAL BUILDING CONDITIONS. EXISTING DUCTS, PIPING OR EQUIPMENT INTERFERING WITH OTHER INSTALLATIONS SHALL BE RELOCATED AS REQUIRED AT NO ADDITIONAL COST TO THE OWNER. EXACT LOCATIONS MUST HAVE THE APPROVAL OF THE ARCHITECT.
2. ALL WORK SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE ANY INSTALLATION IS MADE.
3. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH STATE CODES, MANUFACTURER'S APPROVED PUBLISHED LITERATURE, AND AUTHORITIES HAVING JURISDICTION.
4. INSTALLATION OF EQUIPMENT SHALL PERMIT ACCESSIBILITY FOR SERVICE AND/OR REPLACEMENT.
5. ALL CEILING MOUNTED EQUIPMENT SHALL BE INSTALLED IN SUCH A WAY THAT LIGHTS, PIPING, AND DUCTWORK DO NOT BLOCK ACCESS TO UNITS AND RELATED ACCESSORIES.
6. HVAC CONTRACTOR SHALL COORDINATE ALL WALL, CEILING, FLOOR, ROOF AND BEAM PENETRATIONS WITH ARCHITECT AND STRUCTURAL ENGINEER.
7. ALL DUCT SIZES SHOWN ARE NET INSIDE CLEAR DIMENSIONS.
8. PROVIDE VOLUME DAMPERS AT EVERY MAIN BRANCH TAKE-OFF AND AS INDICATED AND IN SUCH OTHER LOCATIONS WHERE REQUIRED TO PROPERLY BALANCE THE SYSTEM. DO NOT INSTALL VOLUME DAMPERS IN NECKS OF DIFFUSERS OR AT DISCHARGE OR INLET GRILLES IN DUCTWORK.
9. PROVIDE INSTRUMENT TEST HOLES WITH CAPS IN AIR DISTRIBUTION SYSTEMS AS REQUIRED TO BALANCE SYSTEM.
10. HVAC CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHEETMETAL TRANSITIONS AT AIR TERMINAL UNITS, FANS, COILS, AND OTHER SIMILAR HVAC EQUIPMENT.
11. ALL OPEN ENDED DUCTS IN THE CEILING PLENUM SHALL BE UNOBSTRUCTED FOR A MINIMUM DISTANCE OF 24" FROM THE OPENING TO ALLOW FREE AIR FLOW AND SHALL HAVE 3/4" WIRE MESH SCREENING.
12. ALL MISCELLANEOUS STRUCTURAL SUPPORTS REQUIRED FOR HVAC EQUIPMENT INSTALLATION SHALL BE PROVIDED BY HVAC SUBCONTRACTOR.
13. EXACT LOCATION OF CEILING DIFFUSERS, GRILLES AND REGISTERS TO BE DETERMINED BY ARCHITECTURAL REFLECTED CEILING PLAN.
14. INSTALL ALL PIPING BELOW DUCTWORK UNLESS CLEARANCE CONDITION REQUIRES PIPING TO BE ABOVE.
15. EXACT ELEVATION FOR SIDE WALL DIFFUSERS, REGISTERS AND GRILLES SHALL BE APPROVED BY THE ARCHITECT BEFORE INSTALLATION.
16. UNLESS OTHERWISE NOTED, ALL PIPING RUNOUTS SHALL BE 3/4"
17. ALL EXPOSED EQUIPMENT (REGISTERS, UNIT HEATERS, ETC.) SHALL HAVE COLORS SELECTED BY THE ARCHITECT, UNLESS NOTED OTHERWISE.
18. HVAC SUBCONTRACTOR SHALL BLANK OFF AND INSULATE ALL UNUSED LOUVER AREA.
19. PITCH AIR INTAKE PLENUMS AND PROVIDE DRAIN TO NEAREST FLOOR DRAIN.
20. ALL REGISTERS, GRILLES AND DIFFUSERS LOCATED IN WALLS NEAR FLOOR SHALL BE HEAVY-DUTY TYPE DESIGNED TO WITHSTAND RUGGED IMPACT. REFER TO SCHEDULE. THE SECTION OF DUCTWORK BEHIND THE AIR DEVICE SHALL BE PAINTED FLAT BLACK.
21. EXACT LOCATION OF THERMOSTAT TO BE COORDINATED WITH FINAL LOCATION OF WALL MOUNTED ARCHITECTURAL AND ELECTRICAL EQUIPMENT.
22. ALL MAIN BRANCH PIPES FROM RISERS SHALL HAVE ISOLATION VALVES NEAR SHAFTS. PROVIDE SHUT-OFF VALVES AT EACH SUPPLY BRANCH AND COMBINATION BALANCING SHUT-OFF VALVE AT EACH RETURN BRANCH.
23. PROVIDE FLEXIBLE CONNECTOR ON INTAKES AND DISCHARGES OF ALL AIR HANDLING UNITS.
24. REFRIGERATION PIPING SIZED BY UNIT MANUFACTURER. SUBMIT CALCULATIONS TO ENGINEER FOR APPROVAL.
25. DUCT MOUNTED SMOKE DETECTOR - FURNISHED AND WIRED BY THE ELECTRICAL CONTRACTOR, INSTALLED BY THE HVAC CONTRACTOR.
26. ROOF OPENINGS SHALL BE SIZED FROM APPROVED SHOP DRAWINGS.
27. ALL FLOOR MOUNTED MECHANICAL EQUIPMENT, BOILERS, PUMPS, AIR HANDLERS, ETC. SHALL HAVE A CONCRETE PAD 4" HIGH AND 6" BEYOND EQUIPMENT FOOT PRINT ON ALL FOUR SIDES. CONCRETE PADS SHALL BE SIZE FROM APPROVED SHOP DRAWINGS. CONCRETE PADS BY G.C.
28. ALL DAMPER MOTORS SHALL BE 24 VOLT.
29. PROVIDE DUCT MOUNTED SMOKE DAMPERS AT ALL SMOKE BARRIERS, REFER TO ARCH. DRAWINGS FOR LOCATION. SMOKE DAMPERS SHALL BE CLOSED AND ASSOCIATED EXH. FAN OR AHU SHALL BE SHUT-DOWN UPON DETECTION OF SMOKE AS SENSED BY AREA SMOKE DETECTORS. DAMPERS SHALL BE RUSKIN TYPE SD 60 OR EQUAL.

DEMOLITION NOTES

- 1. UNLESS OTHERWISE NOTED, ALL EXISTING HVAC SYSTEMS WITHIN HATCH MARKS (HOT WATER SUPPLY, HOT WATER RETURN, SUPPLY DUCTWORK, EXHAUST DUCTWORK, ETC) AND ASSOCIATED EQUIPMENT IS TO BE DEMOLISHED OR SALVAGED. REMOVE THE EQUIPMENT TO BE DEMOLISHED OR SALVAGED PER SECTION 02050. ALL CONTROL DEVICES ASSOCIATED WITH THE DEMOLISHED EQUIPMENT SHALL BE REMOVED.
2. NO PIPING, DUCTWORK OR EQUIPMENT INDICATED FOR DEMOLITION WILL BE REUSED OR SALVAGED UNLESS SPECIFICALLY NOTED AS SUCH. ALL EQUIPMENT REMOVED SHALL BE REMOVED FROM SITE AND PROPERLY DISPOSED OF, PRIOR TO REMOVAL OF EQUIPMENT COORDINATE WITH OWNER FOR ANY EQUIPMENT THE OWNER WILL KEEP.
3. EXISTING EQUIPMENT INDICATED ON THE DEMOLITION PLANS ARE BASED ON SITE OBSERVATIONS AND IT IS NOT THE INTENTION OF THESE DRAWINGS TO SHOW ALL EQUIPMENT AND MATERIALS TO BE DISCONNECTED AND/OR REMOVED.


ABBREVIATIONS

Table with 2 columns: Abbreviation and Description. Includes entries like ACD (AUTOMATIC CONTROL DAMPER), AFF (ACCESS DOOR), AP (ABOVE FINISHED FLOOR), ARCH (ARCHITECT), ATC (AUTOMATIC TEMPERATURE CONTROL), BDD (BACKDRAFT DAMPER), BTU (BRITISH THERMAL UNIT), BTUH (BRITISH THERMAL UNIT PER HOUR), BOP (BOTTOM OF DUCT), CAP (CAPACITY), CD (CEILING DIFFUSER), CFM (CUBIC FEET PER MINUTE), CO (CLEANOUT), CONT (CONTROLLER), CP (CUT AND CAP), DIA (DIAMETER), DB (DRY BULB TEMPERATURE), DC (DUST COLLECTOR), DDC (DIRECT DIGITAL CONTROL), DN (DOWN), DWG (DRAWING), DX (DIRECT EXPANSION COOLING), EA (EXHAUST AIR), EAT (ENTERING AIR TEMPERATURE), EBB (ELECTRIC BASEBOARD RADIATION), ECH (ELECTRIC CABINET HEATER), ECON (AIR-SIDE ECONOMIZER), EF (EXHAUST FAN), EFF (EFFICIENCY), ELV (ELEVATION), ER (EXHAUST REGISTER), ESP (EXTERNAL STATIC PRESSURE), ETR (EXISTING TO REMAIN), EWT (ENTERING WATER TEMPERATURE), EXH (EXHAUST), FA (FREE AREA), FD (FIRE DAMPER), FLA (FULL LOAD AMPS), FOB (FLAT ON BOTTOM), FOT (FLAT ON TOP), FPI (FINS PER INCH), FPM (FEET PER MINUTE), FT (FEET), FTR (FINNED TUBE RADIATION), GAL (GALLONS), GALV (GALVANIZED), GC (GENERAL CONTRACTOR), GF (GLYCOL FEED), GPM (GALLONS PER MINUTE), HP (HORSEPOWER), HVAC (HEATING, VENTILATING AND AIR CONDITIONING), HG (HOT GAS REHEAT), HW (HOT WATER), HZ (HERTZ), IN (INCHES), KE (KITCHEN EXHAUST), KW (KILOWATTS), LAT (LEAVING AIR TEMPERATURE), LD (LINEAR DIFFUSER), LF (LINEAR FEET), LWT (LEAVING WATER TEMPERATURE), MBH (THOUSANDS OF BTU'S PER HOUR), MCC (MOTOR CONTROL CENTER), NC (NORMALLY CLOSED), NIC (NOT IN CONTRACT), NO (NORMALLY OPEN), NTS (NOT TO SCALE), OA (OUTSIDE AIR), OAT (OUTSIDE AIR TEMPERATURE), OBD (OPPOSED BLADE DAMPER), OD (OUTSIDE DIAMETER), OED (OPEN ENDED DUCT), POS (PROVIDED UNDER OTHER SECTIONS), PSI (POUNDS PER SQUARE INCH (GAUGE)), PD (PRESSURE DROP), PRV (PRESSURE REDUCING VALVE), PG (PROPYLENE GLYCOL), R (RETURN), RA (RETURN AIR), RB (REBALANCE), RF (RETURN/EXHAUST FAN), RG (RETURN GRILLE), RM (ROOM), RPM (REVOLUTIONS PER MINUTE), RR (RETURN REGISTER), S (SUPPLY), SA (SUPPLY AIR), SAT (SUPPLY AIR TEMPERATURE), SF (SQUARE FEET, SUPPLY FAN), SP (STATIC PRESSURE), SR (SUPPLY REGISTER), SS (STAINLESS STEEL), STL (STEEL), TYP (TYPICAL), UC (UNDERCUT DOOR), V (VOLTS), VAV (VARIABLE AIR VOLUME), VD (VOLUME DAMPER), VFD (VARIABLE FREQUENCY DRIVE), W/ (WITH), W/O (WITHOUT), WB (WET BULB TEMPERATURE), WG (WATER GAUGE), WMS (WIRE MESH SCREEN).


PIPING LEGEND

Table with 2 columns: Symbol and Description. Includes CD (CONDENSATE DRAIN), HWS (HOT WATER SUPPLY), HWR (HOT WATER RETURN), RL (REFRIGERANT LIQUID), RS (REFRIGERANT SUCTION).


EQUIPMENT TAG SYMBOLS & ABBREVIATIONS




VALVES AND ACCESSORIES




DUCTWORK LEGEND/SYMBOLS




INSTRUMENTATION



FLOW DIAGRAM EQUIPMENT SYMBOLS



SINGLE LINE DUCTWORK



PREPARED BY



REGISTERED PROFESSIONAL



SUBCONSULTANT



PROJECT

Taunton Wastewater Treatment Facility Improvements Phase 1

Taunton, MA

TITLE

Hvac Legend and General Notes

Table with 3 columns: NO., REVISIONS, DATE. Contains a grid for tracking revisions.

DRAWN BY: RLB

DESIGNED BY: RHB

CHECKED BY: RHB

ISSUE DATE: 10/16/2020

BETA JOB NO.: 6050

SCALE

NONE

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

Not for Construction

SHEET NO.

H-0.1



ENERGY RECOVERY UNIT SCHEDULE (PART 1)

TAG NO.	BUILDING	SUPPLY AIR PERFORMANCE							EXHAUST AIR NORMAL PERFORMANCE					DX COOLING COIL							HOT WATER HEATING COIL							ELECTRIC HEATER DATA					ELECTRICAL DATA															
		SUPPLY IN CFM	MIN. OA IN CFM	ESP (IN WC)	TSP (IN WC)	FAN RPM	OPERATING POWER HP	MOTOR SIZE HP	EXH./RET. OUT CFM	E.S.P. IN (W.C.)	TOTAL SP IN (W.C.)	FAN RPM	OPERATING POWER HP	MOTOR SIZE HP	REFRIG TYPE	TOTAL MBH	SENSIBLE MBH	ROWS	EAT (DB °F)	EAT (WB °F)	LAT (DB °F)	LAT (WB °F)	CAPACITY (MBH)	GPM	EAT (DB °F)	LAT (DB °F)	EWT (DB °F)	LWT (DB °F)	% GLYCOL	WPD (FT)	APD (IN WC)	KW	ENT. °F	LVG. °F	AMPS	CONTROL	V	PHASE	HZ	MCA	MOCP	V	PHASE	HZ				
2ERV-1	PIPE GALLERY BUILDING	11,343	11,343	1.0	3.016	1961	(2) 4.88	(2) 5	11,343	0.65	2.226	2055	(2) 5.43	(2) 7.5	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	415.1	44.6	41.6	75.4	180	160	40% P.G.	9.1	0.051	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	35.7	45	480	3	60
2ERV-2	PIPE GALLERY BUILDING	13,505	13,505	1.0	3.099	2050	(2) 4.94	(2) 5	13,505	1.0	2.528	1588	(2) 2.77	(2) 3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	765.1	85.5	41.2	95.6	180	160	40% P.G.	7.5	0.474	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	29.8	35	480	3	60	
5ERV-1	CHEMICAL HANDLING BUILDING	2,825	950	1.5	3.126	2820	(1) 2.36	(1) 5	950	1.0	1.606	1699	(1) 0.53	(1) 5	R-410a	68.3	60.9	4	76.0	63.6	56.3	55.5	N/A	N/A	N/A	N/A	N/A	N/A	N/A	20	67.7	90.1	-	SCR	480	3	60	23.9	30	480	3	60						
6ERV-1	BLOWER BUILDING	6,000	6,000	1.0	3.388	2039	(1) 5.5	(1) 7.5	6,000	1.0	2.329	2089	(1) 5.64	(1) 7.5	R-410a	339.8	205.3	6	80.4	68.0	49.3	49.1	N/A	N/A	N/A	N/A	N/A	N/A	N/A	40	48.0	69.0	-	SCR	480	3	60	76.6	90	480	3	60						
9ERV-1	ADMINISTRATION BUILDING	3,200	3,200	1.5	3.408	1935	(1) 2.79	(1) 3	3,200	1.5	2.809	3297	(1) 3.41	(1) 5	R-410a	192.9	114.4	6	80.9	68.5	48.4	48.3	168.5	18.1	45.9	94.5	180	160	40% P.G.	1.3	0.133	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	12.4	15	480	3	60			

ENERGY RECOVERY UNIT SCHEDULE (PART 2)

TAG NO.	ENERGY RECOVERY WHEEL PERFORMANCE												WEIGHT LBS	SUPPLY FILTER	OUTDOOR FILTER	MANUFACTURER MODEL NUMBER	REMARKS
	WINTER CONDITIONS DESIGN						SUMMER CONDITIONS DESIGN										
	OUTDOOR			INDOOR			OUTDOOR			INDOOR							
	DB °F	WB °F	RH%	DB °F	WB °F	RH%	DB °F	WB °F	RH%	DB °F	WB °F	RH%					
2ERV-1	7.4	5.3	46.7	50	90.8	76.2	80.7	50	5,379	MERV-6	MERV-8	GREENHECK RVE-120-74-30H	①②③④⑤⑥⑦⑧⑨⑩				
2ERV-2	7.4	5.3	46.7	50	90.8	76.2	80.7	50	7,604	MERV-6	MERV-8	GREENHECK RVE-180-81-30H	①②③④⑤⑥⑦⑧⑨⑩				
5ERV-1	7.4	5.3	63.5	50	90.8	76.2	80.7	50	3,108	MERV-6	MERV-8	GREENHECK RVE-40-30-30L-5D	①②③④⑤⑥ ⑧⑨⑩⑪				
6ERV-1	7.4	5.3	63.5	50	90.8	76.2	80.7	50	4,949	MERV-6	MERV-8	GREENHECK RVE-85-52-30H-30D	①②③④⑤⑥⑦⑧⑨⑩⑪				
9ERV-1	7.4	5.3	63.5	50	90.8	76.2	80.7	50	2,525	MERV-6	MERV-8	GREENHECK RVE-40-36-30H	①②③④⑤⑥⑦⑧⑨⑩				

- ① BASE RAILS ② LOW LEAKAGE DAMPERS ③ RECIRC. DAMPER ④ FACTORY SUPPLY & EXHAUST FAN VFD ⑤ ENERGY BYPASS WHEEL DAMPER
- ⑥ FACTORY MOUNTED DISCONNECT ⑦ SINGLE POINT POWER CONNECTION ⑧ COORDINATE SUPPLY & EXHAUST BOTTOM DISCHARGE WITH FLOOR PLANS
- ⑨ INSTALLED OUTDOORS ⑩ AIR FLOW STATIONS ⑪ TWO POINT POWER CONNECTION (ONE FOR UNIT AND ONE FOR ELECTRIC HEAT)

EXHAUST FAN SCHEDULE

TAG NO.	BUILDING	CFM	ESP (IN WC)	SPEED (RPM)		DRIVE	ELECTRICAL DATA				MANUFACTURER & MODEL #	REMARKS
				FAN	MOTOR		HP	V	PH	HZ		
5EF-1	CHEMICAL HANDLING BUILDING	450	0.45	1353	1725	DIRECT	1/4	120	1	60	GREENHECK SE1-12-432-VG	
5EF-2	CHEMICAL HANDLING BUILDING	125	0.45	1014	1350	DIRECT	1/4	120	1	60	GREENHECK AER-E20C-605-VG	
9LEF-1	ADMIN BUILDING LAB EXHAUST	660	2.50	3687	3600	DIRECT	1.5	480	3	60	GREENHECK VEKTOR-H-9	

PREPARED BY



www.BETA-Inc.com

REGISTERED PROFESSIONAL

SUBCONSULTANT



Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328.9215  
web: www.sar.com

PROJECT

**Taunton Wastewater Treatment Facility Improvements Phase 1**

Taunton, MA

TITLE

Hvac Schedules

NO. REVISIONS DATE

DRAWN BY: RLB  
DESIGNED BY: RHB  
CHECKED BY: RHB  
ISSUE DATE: 10/16/2020  
BETA JOB NO.: 6050

SCALE

NONE

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO. H-0.2















































4/27/2021 8:09 AM W:\YEAR - 2018\18009.00 - TAUNTON WWTF UPGRADES\HVAC DEPARTMENT\PHASE 1\18009.00 HVAC PRIMARY CLARIFIERS & SLUDGE PS-PHASE 1.DWG (BETA STB BW STB)



PLAN  
SCALE: 1/8"= 1'-0"

PREPARED BY




www.BETA-Inc.com

---

REGISTERED PROFESSIONAL

---

SUBCONSULTANT



**SAR**  
ENGINEERING, INC.

Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328-9215  
web: www.sar.com

---

PROJECT

**Taunton Wastewater Treatment Facility Improvements Phase 1**

Taunton, MA

---

TITLE

**Hvac Pipe Gallery New Work Roof Plan**

---

NO.	REVISIONS	DATE

---

DRAWN BY: RLB

DESIGNED BY: RHB

CHECKED BY: RHB

ISSUE DATE: 10/16/2020

BETA JOB NO.: 6050

---

SCALE

AS SHOWN

---

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**


---

SHEET NO.

H-2.3



4/27/2021 8:07 AM W:\YEAR - 2018\18009.00 - TAUNTON WWTF UPGRADES\HVAC DEPARTMENT\PHASE 1\18009.00 HVAC CHEMICAL HANDLING BUILDING PHASE 1.DWG (BETA STB BW.STB)



**BASEMENT - PLAN**

SCALE: 1/4" = 1'-0"

PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT



Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328.9215  
web: www.sar.com

PROJECT

**Taunton Wastewater  
Treatment Facility  
Improvements  
Phase 1**

Taunton, MA

TITLE

**Hvac Demolition  
Chemical Handling  
Building  
Basement Plan**


NO.	REVISIONS	DATE

DRAWN BY: RLB

DESIGNED BY: RHB

CHECKED BY: RHB

ISSUE DATE: 10/16/2020

BETA JOB NO.: 6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO.

H-5.1







































































### OIL FIRED WATER HEATER SCHEDULE

DESIGNATION	MANUFACTURER	MODEL	LOCATION	GALS.	RECOVERY		GPH #2 FUEL OIL	OIL CONN. SIZE	FLUE CONN. SIZE	REMARKS
					G.P.H.	Δ TEMP °F				
9DWH-1	AO SMITH	COF-199*	ADMIN BLDG	86	191	100	1.42	1/2"	8"	-

\* MANUFACTURERS NAMES AND MODEL NUMBERS ARE SHOWN ONLY TO REPRESENT TYPE, STYLE AND LEVEL OF QUALITY EXPECTED, REFER TO SPECIFICATIONS FOR ACCEPTABLE EQUAL MANUFACTURERS.

### ELECTRIC WATER HEATER SCHEDULE

DESIGNATION	MANUFACTURER	MODEL	LOCATION	GALS.	RECOVERY		KW	VOLTS	PHASE	HZ.	REMARKS
					G.P.H.	Δ TEMP °F					
5DWH-1	A.O. SMITH	DRE-120-15	CHEMICAL BLDG	120	61	100	15	480	3	60	-
9DWH-2	A.O. SMITH	ENT-30	ADMIN BLDG	30	48	100	4.5	208	1	60	SERVICES LAB SYSTEMS

\* MANUFACTURERS NAMES AND MODEL NUMBERS ARE SHOWN ONLY TO REPRESENT TYPE, STYLE AND LEVEL OF QUALITY EXPECTED, REFER TO SPECIFICATIONS FOR ACCEPTABLE EQUAL MANUFACTURERS.

### CIRCULATING PUMP SCHEDULE

DESIGNATION	LOCATION	WATER HEATER SERVED	MODEL	CAPACITY (GPM)	HEAD (FEET)	TYPE	ELECTRICAL REQUIREMENTS				REMARKS
							RPM	HP	VOLTS	Φ	
5.DWP-1	MECH ROOM	5DWH-1	TACO 006B	2	6	INLINE	3250	1/40	115	1	SERVES 120° HW SYSTEM
9.DWP-1	ADMIN BLDG	5DWH-1	TACO 006B	2	6	INLINE	3250	1/40	115	1	SERVES 120° HW SYSTEM
9.DWP-2	ADMIN BLDG	5DWH-1	TACO 006B	2	6	INLINE	3250	1/40	115	1	SERVES 120° HW LAB SYSTEM

\* MANUFACTURERS NAMES AND MODEL NUMBERS ARE SHOWN ONLY TO REPRESENT TYPE, STYLE AND LEVEL OF QUALITY EXPECTED, REFER TO SPECIFICATIONS FOR ACCEPTABLE EQUAL MANUFACTURERS.

### PLUMBING FIXTURE SCHEDULE

DESIGNATION	FIXTURE DESCRIPTION	CONNECTION SIZE						REMARKS	
		W1	HW1	BLW	SAN	V	NPW1		NPHW1
WC-1	WATER CLOSET	1"	-	-	4"	2"	-	-	WALL HUNG - CARRIER SUPPORTED
WC-1A	WATER CLOSET	1"	-	-	4"	2"	-	-	WALL HUNG - CARRIER SUPPORTED
UR-1	URINAL	3/4"	-	-	2"	2"	-	-	WALL HUNG - CARRIER SUPPORTED
LAV-1	LAVATORY	1/2"	1/2"	-	2"	2"	-	-	WALL HUNG - CARRIER SUPPORTED
LAV-1A	LAVATORY	1/2"	1/2"	-	2"	2"	-	-	WALL HUNG - CARRIER SUPPORTED
KS-1	KITCHEN SINK	1/2"	1/2"	-	2"	2"	-	-	DROP IN
SS-1	JANITOR SINK	1/2"	1/2"	-	3"	2"	-	-	FAUCET SHALL HAVE INTEGRAL CHECK VALVES
SH-1	SHOWER	1/2"	1/2"	-	3"	2"	-	-	-
SH-1A	SHOWER	1/2"	1/2"	-	3"	2"	-	-	-
HB	HOSE BIBB	1/2"	-	-	-	-	-	-	-
EWU-1	EMERGENCY SHOWER/EYEWASH	-	-	1 1/4"	-	-	-	-	INTERIOR MOUNTED, CORROSION RESISTANT, EMERGENCY SHOWER/EYEWASH (COMBINATION UNIT) WITH HORN, STROBE AND FLOW SWITCH
EWU-2	EMERGENCY SHOWER/EYEWASH	-	-	1 1/4"	-	-	-	-	EXTERIOR MOUNTED, CORROSION RESISTANT, EMERGENCY SHOWER/EYEWASH (COMBINATION UNIT) WITH HORN, STROBE AND FLOW SWITCH

### SUMP PUMP SCHEDULE

DESIGNATION	LOCATION	MODEL	CAPACITY (GPM)	HEAD (FEET)	TYPE	ELECTRICAL REQUIREMENTS				REMARKS
						RPM	HP	VOLTS	Φ	
5SP-1	CHEMICAL HANDLING UNITS	WEIL 2443	20	40	DUPLEX SUBMERSIBLE	1750	1/2	480	3	AUTOMATIC WITH FLOAT

### SHOCK ABSORBER SCHEDULE

PDI RATING SYMBOL	A	B	C	D	E
PRECISION PLUMBING PRODUCTS	SC-500	SC-750	SC-1000	SC-1250	SC-1500
WATTS REGULATOR COMPANY	0750030	0750053	0750060	0750070	0750090
WADE	5-P	10-P	20-P	50-P	75-P

\* MANUFACTURERS NAMES AND MODEL NUMBERS ARE SHOWN ONLY TO REPRESENT TYPE, STYLE AND LEVEL OF QUALITY EXPECTED, REFER TO SPECIFICATIONS FOR ACCEPTABLE EQUAL MANUFACTURERS.  
\*\* PROVIDE WITH SHUT-OFF VALVE.

### DRAIN SCHEDULE

DESIGNATION	TYPE	MANUFACTURER	MODEL	OUTLET	STRAINER	REMARKS
FD'A'	FD	J.R. SMITH	2005Y-A-P050	NO HUB	NICK-BRZ	FINISHED AREAS
FD'B'	FD	J.R. SMITH	9700C-CF8M-NB	CAULK	NICK-BRZ	CLASSIFIED OR HAZARDOUS AREAS
FD'C'	FD	J.R. SMITH	2005Y-B-P050	CAULK	NICK-BRZ	SHOWERS
RD'A'	RD	ZURN	Z121	NO HUB	CAST IRON DOME	REPLACE DRAIN TO ACCOMMODATE NEW ROOF

\* ALL FLOOR DRAINS SHALL BE PROVIDED WITH AUTOMATIC TRAP PRIMERS. REFER TO DETAIL FOR PIPING ARRANGEMENT.  
\* MANUFACTURERS NAMES AND MODEL NUMBERS ARE SHOWN ONLY TO REPRESENT TYPE, STYLE AND LEVEL OF QUALITY EXPECTED, REFER TO SPECIFICATIONS FOR ACCEPTABLE EQUAL MANUFACTURERS.

PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT



Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328.9215  
web: www.sar.com

PROJECT

**Taunton Wastewater Treatment Facility Improvements Phase 1**

Taunton, MA

TITLE

Plumbing Schedules

NO. REVISIONS DATE

DRAWN BY: RLB

DESIGNED BY: RHB

CHECKED BY: RHB

ISSUE DATE: 10/16/2020

BETA JOB NO.: 6050

SCALE

NONE

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO.

P-0.2



























































































PAGE INTENTIONALLY  
LEFT BLANK  
RESERVED FOR  
PHASE II

PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT



Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328-9215  
web: www.sar.com

PROJECT

**Taunton Wastewater  
Treatment Facility  
Improvements  
Phase 1**

Taunton, MA

TITLE

**INSTRUMENTATION  
& CONTROLS  
BIOLOGICAL  
TREATMENT  
TRAIN #1**


NO.	REVISIONS	DATE
-----	-----------	------

DRAWN BY:	RB
DESIGNED BY:	MC
CHECKED BY:	MC
ISSUE DATE:	10/16/2020
BETA JOB NO.:	6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO. I-0.6







PAGE INTENTIONALLY  
LEFT BLANK  
RESERVED FOR  
PHASE II

PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT



Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328-9215  
web: www.sar.com

PROJECT

**Taunton Wastewater  
Treatment Facility  
Improvements  
Phase 1**

Taunton, MA

TITLE

**INSTRUMENTATION  
& CONTROLS  
SECONDARY  
ANOXIC TANKS**


NO.	REVISIONS	DATE
-----	-----------	------

DRAWN BY:	RB
DESIGNED BY:	MC
CHECKED BY:	MC
ISSUE DATE:	10/16/2020
BETA JOB NO.:	6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO. 1-0.9





PAGE INTENTIONALLY  
LEFT BLANK  
RESERVED FOR  
PHASE II

PREPARED BY



REGISTERED PROFESSIONAL

SUBCONSULTANT



Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 309  
Braintree, Massachusetts 02184  
617.328-9215  
web: www.sar.com

PROJECT

**Taunton Wastewater  
Treatment Facility  
Improvements  
Phase 1**

Taunton, MA

TITLE

**INSTRUMENTATION  
& CONTROLS  
FINAL  
CLARIFIERS  
#1 & #2**


NO.	REVISIONS	DATE
-----	-----------	------

DRAWN BY:	RB
DESIGNED BY:	MC
CHECKED BY:	MC
ISSUE DATE:	10/16/2020
BETA JOB NO.:	6050

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**Not for Construction**

SHEET NO. I-0.11













































































































































































































































